

The Brattle Group

Cost of New Entry Estimates For Combustion Turbine and Combined-Cycle Plants in PJM

August 24, 2011

Kathleen Spees
Samuel A. Newell
Robert Carlton
Bin Zhou
Johannes P. Pfeifenberger
The Brattle Group

with
CH2M HILL
Wood Group Power Operations

Prepared for



PJM Interconnection, L.L.C.

TABLE OF CONTENTS

Executive Summary	1
I. Background.....	4
A. Study Objective.....	4
B. Analytical Approach	4
II. Determination of Reference Technology	5
A. Approach to Determining Reference Technology Characteristics	5
B. Siting Plant Locations within Each CONE Area	5
C. Plant Configuration and Size	8
D. Turbine Model	9
E. Combined-cycle Cooling System	11
F. Duct Firing and Power Augmentation	11
G. NO _x Controls	12
H. Dual-fuel Capability.....	15
I. Gas Compression	17
J. Black Start Capability	17
III. Reference Technology Performance and Specifications	17
IV. Capital Cost Estimates	19
A. Plant Proper Capital Costs	19
1. Plant Developer and Contractor Arrangements.....	19
2. Owner-furnished Equipment and Sales Tax	19
3. Engineering Procurement and Construction Costs	20
4. Capital Drawdown Schedules.....	21
B. Owner’s Capital Costs	21
1. Land	21
2. Emissions Reductions Credits	22
3. Gas Interconnection	24
4. Electric Interconnection.....	25
5. Net Start-Up Fuel Costs during Testing	26
6. O&M Mobilization and Startup.....	27
7. Project Development, Financing Fees, and Owner’s Contingency	28
V. Fixed and Variable Operation and Maintenance Costs.....	29
A. Property Tax.....	29
B. Insurance	30
C. Annual Fixed Fees for Plant Operation and Maintenance	30
D. Asset Management Costs.....	31
E. Variable Operation and Maintenance Costs	31
VI. Financial Assumptions	32
A. Inflation.....	32
B. Income Tax and Depreciation Schedule	34
C. Cost of Capital	35
1. Estimated Cost of Capital for a Portfolio of Merchant Generation Companies ...	35
2. Cost-of-Capital Estimates from Industry Analysts and Fairness Opinions	39

3. After-Tax Weighted-Average Cost of Capital Estimate.....	40
D. Interest During Construction.....	41
VII. Summary of Capital, Fixed, and Levelized Costs.....	42
A. Total Capital Costs.....	42
B. Total Fixed O&M Costs.....	43
C. Levelized Cost of New Entry.....	44
Bibliography	48
List of Acronyms	53
Appendix A. CH2M HILL Simple-cycle Cost Estimates	A-1
Appendix A.1. Simple-cycle Plant Proper Cost Estimate Report.....	A-2
Appendix A.2. Layout Drawing for Dual-fuel CT with SCR.....	A-28
Appendix A.3. Project Schedule for Dual-fuel CT with SCR	A-30
Appendix A.4. Cost Detail for CT with SCR in CONE Area 1.....	A-32
Appendix A.5. Cash Flow Schedule for CT with SCR in CONE Area 1	A-36
Appendix B. CH2M HILL Combined-cycle Cost Estimates	B-1
Appendix B.1. Combined-cycle Plant Proper Cost Estimate Report.....	B-2
Appendix B.2. Layout Drawing for Dual-fuel CC	B-31
Appendix B.3. Project Schedule for Dual-fuel CC.....	B-33
Appendix B.4. Cost Detail for CC in CONE Area 1	B-36
Appendix B.5. Cash Flow Schedule for CC in CONE Area 1	B-40
Appendix C. Wood Group O&M Cost Estimates.....	C-1

Acknowledgements

The authors would like to thank David Cheever, Rod Gartner, and others at CH2M HILL for providing their rigorous analysis of engineering costs and for contributing their expertise in generation development to numerous other aspects of our analysis. We would also like to thank the PJM staff and Wood Group for their cooperation and responsiveness to our many questions and requests. Opinions expressed in this report, as well as any errors or omissions, are the authors' alone.

EXECUTIVE SUMMARY

This report documents our study of the gross Cost of New Entry (“CONE”) for combustion turbine (“CT”) and combined-cycle (“CC”) power plants with a target online date of June 1, 2015, consistent with the 2015/16 delivery year in PJM’s capacity market. We prepared this study in cooperation with CH2M HILL, a major engineering procurement, and construction company with extensive experience in the design and construction of power plants, and Wood Group, a power plant operation and maintenance (“O&M”) service provider.

Gross CONE includes both the capital and ongoing fixed operating costs required to build and operate a new plant. We present these estimates for consideration by PJM Interconnection and stakeholders as they update the administrative CONE parameters for PJM’s capacity market, the Reliability Pricing Model (“RPM”). The CT CONE parameter is used to define points of the Variable Resource Requirement (VRR) curve; both CC and CT CONE parameters are used for calculating offer price screens under the Minimum Offer Price Rule (“MOPR”) for new generation offering capacity into RPM. We provide separate CT and CC CONE estimates for each of the five administrative CONE Areas in PJM.

Table 1 shows our recommended CONE for gas CT plants in each CONE Area based on levelized plant capital costs and annual fixed operation and maintenance (“FOM”) costs for the 2015/16 delivery year. The table shows the major components of the CONE calculation including overnight costs, plant net summer installed capacity (“ICAP”), annual ongoing fixed O&M costs, and the after-tax weighted-average cost of capital (“ATWACC”). Our CONE estimates are presented on a “level nominal” basis (*i.e.*, equal payments over the plant’s economic life) as well as on a “level real” basis (*i.e.*, payments that start lower but increase with inflation over time). As we explain in our concurrent report, Second Performance Assessment of PJM’s Reliability Pricing Model, August 26, 2011 (“2011 RPM Report”), we recommend transitioning toward using a level-real CONE for MOPR purposes; for defining the VRR curve, we also recommend transitioning to level-real contingent on the implementation of several other recommendations.

Our estimates differ by CONE area due to differences in plant configuration assumptions, differences in labor rates, and other locational differences in capital and fixed costs. In each CONE area, except for the Rest of RTO area, all plants are configured with dual fuel. In addition, the CT plants are fitted with Selective Catalytic Reduction (“SCR”) in each location except in Dominion, where the current Ozone attainment status does not yet require an SCR. We also provide costs for plants with dual-fuel capability and SCRs in each Area in case future developments necessitate such investments.

The Eastern Mid-Atlantic Area Council (“Eastern MAAC” or “EMAAC”) and Western MAAC regions have the highest CONE estimates at \$112/kW-year (\$307/MW-day) and \$109/kW-year (\$298/MW-day) respectively on a level real basis. The Southwest MAAC and Rest of RTO areas are somewhat lower, both at \$103/kW-year (\$283/MW-day), primarily because of the non-union labor availability in Southwest MAAC and the lack of dual-fuel capability in the Rest of RTO region. The lowest CONE estimate is in Dominion at \$93/kW-year (\$254/MW-day), due

to lower non-union labor rates and avoiding an SCR. Avoiding an SCR in Dominion reduces overnight capital costs by approximately \$24 million, while avoiding dual-fuel capability in the Rest of RTO area reduces capital costs by approximately \$19 million. These corresponding level-nominal costs are shown in Table 1.

Table 1 also shows the CONE estimates Power Project Management (“PPM”) provided to PJM in 2008. PJM stakeholders agreed to use those estimates for setting points on the VRR curve by discounting them by 10 percent and then escalating them with the Handy-Whitman Index. To facilitate a more direct comparison of the PPM study to ours, we present the PPM results without discount, and inflation adjusted to 2015 dollars. As such, our level-nominal estimates are \$19 to 23/kW-year (\$53 to 62/MW-day) lower than the PPM estimates in the three CONE Areas reported. Our estimates are lower primarily due to reductions in equipment, materials, and labor costs since 2008 relative to inflation, as well as economies of scale associated with the larger size of the GE 7FA.05 turbine compared to the previously examined GE7FA.03 turbine model.

Finally, Table 1 also shows the CONE PJM has applied in its recent auction for the 2014/15 delivery year, escalated for one year of inflation to represent 2015/16 dollar values.

Table 1
Recommended Gas CT CONE for 2015/16

CONE Area	Total Plant Capital Cost (\$M)	Net Summer ICAP (MW)	Overnight Cost (\$/kW)	Fixed O&M (\$/kW-y)	After-Tax WACC (%)	Levelized Gross CONE		PJM 2014/15 CT CONE (\$/kW-y)
						Level Real (\$/kW-y)	Level Nominal (\$/kW-y)	
Brattle 2011 Estimate								<i>Escalated at CPI</i>
<i>June 1, 2015 Online Date (2015\$)</i>								<i>for 1 Year</i>
1 Eastern MAAC	\$308.3	390	\$791.2	\$15.7	8.47%	\$112.0	\$134.0	\$142.1
2 Southwest MAAC	\$281.5	390	\$722.6	\$15.8	8.49%	\$103.4	\$123.7	\$131.4
3 Rest of RTO	\$287.3	390	\$737.3	\$15.2	8.46%	\$103.1	\$123.5	\$135.0
4 Western MAAC	\$299.3	390	\$768.2	\$15.1	8.44%	\$108.6	\$130.1	\$131.4
5 Dominion	\$254.7	392	\$649.8	\$14.7	8.54%	\$92.8	\$111.0	\$131.5
Power Project Management, LLC 2008 Update								
<i>June 1, 2008 Online Date (Escalated at CPI from 2008\$ to 2015\$)</i>								
1 Eastern MAAC	\$350.3	336	\$1,042.2	\$17.2	8.07%	n/a	\$154.4	n/a
2 Southwest MAAC	\$322.1	336	\$958.4	\$17.5	8.09%	n/a	\$142.8	n/a
3 Rest of RTO	\$332.5	336	\$989.4	\$15.3	8.11%	n/a	\$146.1	n/a

Sources and Notes:

Overnight costs are the sum of nominal dollars expended over time and exclude interest during construction.

Dominion estimate excludes an SCR; with SCR CONE increases to \$100.8/kW-year level real and \$120.6/kW-year level nominal.

Rest of RTO CONE is for single fuel; dual-fuel CONE would be \$110.7/kW-year level real and \$132.5/kW-year level nominal.

PPM’s estimates shown here were discounted by 10% in settlement and escalated at the Handy-Whitman Index for setting the administrative gross CONE parameters over the 2012/13 through 2014/15 delivery years PJM Interconnection, L.L.C. (2011d), p. 10; Power Project Management (2008).

PPM’s numbers are escalated according to historical inflation over 2008-2011 and at 2.5% inflation rate over 2011-2015, see Federal Reserve Bank of St. Louis (2011) and Section VI.A.

Table 2 shows our recommended 2015/16 CONE for gas CC plants. These estimates are compared to the most recent estimates developed by Pasteris Energy for PJM in 2011. In each location, the gas CC plant is configured with an SCR. The plants have dual-fuel capability in all CONE Areas except in the Rest of RTO Area. Avoiding dual-fuel capability in the Rest of RTO Area reduces capital costs by approximately \$18 million.

Eastern MAAC has the highest CC CONE at \$141/kW-year (\$385/MW-day) on a level real basis, while Rest of RTO and Western MAAC are a bit lower, both at \$135/kW-year (\$370/MW-day). Southwest MAAC and Dominion have the lowest CONE estimates at \$123/kW-year (\$338/MW-day) and \$120/kW-year (\$329/MW-day) respectively, primarily due to non-union labor rates in those locations. Our estimates are \$6 to 12/kW-year (\$17 to 32/MW-day) below the Pasteris Energy CONE estimates on a level-nominal basis primarily due to a higher ICAP rating. Our higher plant ICAP rating reflects the larger size of the GE 7FA.05 turbine relative to the GE7FA.04 turbine model examined by Pasteris, as well as the greater duct firing capability in the plant we examine. Table 2 also shows the CC CONE value PJM has utilized for the 2014/15 delivery year, inflation adjusted to 2015/16 dollar values.

Table 2
Recommended Gas CC CONE for 2015/16

CONE Area	Total Plant Capital Cost (\$M)	Net Summer ICAP (MW)	Overnight Cost (\$/kW)	Fixed O&M (\$/kW-y)	After-Tax WACC (%)	Levelized Gross CONE		PJM 2014/15 CC CONE (\$/kW-y)
						Level Real (\$/kW-y)	Level Nominal (\$/kW-y)	
Brattle 2011 Estimate								<i>Escalated at CPI</i>
<i>June 1, 2015 Online Date (2015\$)</i>								<i>for 1 Year</i>
1 Eastern MAAC	\$621.2	656	\$947.5	\$16.7	8.47%	\$140.5	\$168.1	\$179.6
2 Southwest MAAC	\$537.2	656	\$819.3	\$16.6	8.49%	\$123.3	\$147.5	\$158.7
3 Rest of RTO	\$599.0	656	\$913.5	\$16.0	8.46%	\$135.5	\$162.1	\$168.5
4 Western MAAC	\$597.4	656	\$911.1	\$15.8	8.44%	\$135.1	\$161.8	\$158.7
5 Dominion	\$532.9	656	\$812.8	\$15.4	8.54%	\$120.2	\$143.8	\$158.7
Pasteris 2011 Update								
<i>June 1, 2014 Online Date (Escalated at CPI from 2014\$ to 2015\$)</i>								
1 Eastern MAAC	\$710.9	601	\$1,183.1	\$18.5	8.07%	n/a	\$179.6	n/a
2 Southwest MAAC	\$618.7	601	\$1,029.5	\$18.8	8.09%	n/a	\$158.7	n/a
3 Rest of RTO	\$678.0	601	\$1,128.3	\$16.9	8.11%	n/a	\$168.5	n/a

Sources and Notes:

Overnight costs are the sum of nominal dollars expended over time and exclude interest during construction.

Rest of RTO CONE is for single fuel; dual-fuel CONE would be \$138.9/kW-year level real and \$136.3/kW-year level nominal.

Pasteris Energy's 2011 CONE estimates were used as the basis for the CC CONE estimate for the 2014/15 delivery year, see Pasteris Energy (2011), pg. 55.

Pasteris Energy's numbers are escalated at 2.5% inflation rate, see and Section VI.A.

I. BACKGROUND

A. STUDY OBJECTIVE

The Cost of New Entry (“CONE”) is an administrative parameter used in PJM’s capacity market, the Reliability Pricing Model (“RPM”), with CONE values defined separately in each of five CONE Areas.¹ The CONE parameter for a gas combustion turbine (“CT”) is used as an input for calculating points on the Variable Resource Requirement (“VRR”) curve.² The CONE parameters for a gas combined cycle (“CC”) as well as a gas CT are used in calculating offer price screens under the Minimum Offer Price Rule (“MOPR”) for new generation offering capacity into RPM.³

As a requirement of the Open Access Transmission Tariff (“OATT”), PJM is required to review the CONE parameter for the delivery year starting June 1, 2015 and every third year after that.⁴ Between these triennial reviews, CONE is updated annually according to the Handy-Whitman Index. We were asked to assist PJM and stakeholders in this triennial review by developing CONE estimates for new gas CT and CC plants in each of the five CONE Areas. In this study, we define the gas CT and CC reference technologies for each CONE Area and estimate plant capital and other fixed costs for each plant.

B. ANALYTICAL APPROACH

For a particular reference technology, CONE is made up of plant capital costs, which must be leveled to produce an annual cost, plus annual fixed operation and maintenance (“FOM”) costs. Our analytical starting point is the selection of the most economic reference technologies and feasible siting locations in each CONE Area. For each CC and CT in each area, we characterized the reference plants by size, turbine technology, configuration, and typical site characteristics. Key configuration variables include NO_x controls, duct firing and other power augmentation, cooling systems, dual-fuel capability, and gas compression. We selected specific characteristics based on our analysis of the predominant practice among recently-developed plants; our analysis of technologies, regulations, and infrastructure; and guidance from engineering sub-contractors. Key site characteristics include proximity to high voltage transmission infrastructure and interstate gas pipelines, siting attractiveness as indicated by units recently built or currently under construction, and availability of vacant industrial land. Our analysis for selecting plant locations and technical specifications is presented in Section II. A summary of the resulting technical and site characteristics of the identified reference technologies is presented in Section III.

To develop estimates of plant proper capital costs for the reference gas CT and CC plants in each CONE area, *The Brattle Group* sub-contracted with CH2M HILL Engineers, Inc. CH2M HILL

¹ PJM (2011b), p. 2278

² PJM (2011b), p. 2280.

³ PJM (2011b), pp. 2297-2300.

⁴ PJM (2011b), p. 2280.

is an engineering, procurement, and construction (“EPC”) company with extensive experience in the design and construction of gas CT and CC plants. They developed capital and construction cost estimates using the same data and models they use to support their bids for actual projects. The results of their analysis are presented in Section IV.A with detailed supporting documentation for the CT and CC technologies in Appendices A and B. Separately, we estimated several plant owner’s costs, as described in Section IV.B. Given the combined, comprehensive costs of each reference plant, we estimated levelized annual capital carrying costs using standard financial techniques, as described in Section VI.

The Brattle Group also sub-contracted with Wood Group Power Operations, Inc. to estimate fixed and variable O&M costs for the reference CT and CC plants. Wood Group has extensive experience providing outsourced O&M services to owners of generation plants, and has previously provided O&M estimates for PJM in previous CONE studies. The results of their analysis are presented in Sections IV.B.6, V.C, and V.E, with additional supporting details included in Appendix C.

We separately estimated several other fixed annual operations costs that will be incurred over the plant life but that are not covered under an O&M services provider’s scope. Our analyses were further informed by a number of conversations with plant operators and developers.

II. DETERMINATION OF REFERENCE TECHNOLOGY

A. APPROACH TO DETERMINING REFERENCE TECHNOLOGY CHARACTERISTICS

We determined the reference technology primarily using a “revealed preferences” approach, in order to assess the market’s determination of the most attractive technology for investment. The advantage of this approach is that it is informed by the choices that actual developers found to be most feasible and economic. However, because technologies and environmental regulations continue to evolve, we supplement this “revealed preference” approach with guidance from CH2M HILL and with additional analysis of underlying economics, regulations, and infrastructure.

As the basis for determining most of the selected reference technology specifications, we closely examined all gas CT and CC plants developed in PJM and the U.S. since 2002, including plants currently under construction. We characterized these plants by size, turbine technology, plant configuration, NO_x controls and emissions rates, duct firing, dual-fuel capability, and cooling systems.

B. SITING PLANT LOCATIONS WITHIN EACH CONE AREA

The Open Access Transmission Tariff (“OATT”) requires a separate Gross CONE parameter in each of five CONE Areas as summarized in Table 3.⁵

⁵ PJM Interconnection, L.L.C. (2011b), p. 2278.

**Table 3
CONE Areas**

CONE Area	Transmission Zones	States
1 Eastern MAAC	AECO, DPL, JCPL, PECO, PSEG, RECO	NJ, MD, DE
2 Southwest MAAC	BGE, PEPCO	MD, DC
3 Rest of RTO	AEP, APS, ATSI, ComEd, DAY, DEOK, DQL	WV, VA, OH, IN, IL, KY, TN, MI
4 Western MAAC	MetEd, Penelec, PPL	PA
5 Dominion	Dominion	VA, NC

Sources and Notes:

PJM Interconnection, L.L.C. (2011b), p. 2284.

PJM Interconnection, L.L.C. (2011c)

CONE Areas fall on exact transmission zone boundaries but not on exact state boundaries.

We conducted a siting evaluation to select a specific county to use as the cost estimate basis for the reference plant within each CONE Area. Our primary criteria for identifying feasible and favorable locations were: (1) the availability of high voltage transmission infrastructure; (2) the availability of a major gas pipeline; (3) siting attractiveness as indicated by units recently built or currently under construction; and (4) the availability of vacant industrial land.⁶ Figure 1 and Figure 2 show the locations of gas CT and CC units built in PJM since 2002.

**Figure 1
Gas CTs under Construction or Built Since 2002**



Sources and Notes:

Plant locations from Ventyx (2011). Mapped with Google Maps (2011).

Map shows 27 different plants built since 2002.

⁶ Plant locations from Ventyx (2011), transmission infrastructure from PJM (2008), gas pipeline locations from Platts (2011), and vacant industrial land sales postings from Loopnet (2011).

Figure 2
Gas CCs under Construction or Built Since 2002



Sources and Notes:

Plant locations from Ventyx (2011). Mapped with Google Maps (2011).
 Map shows 25 different plants built since 2002, and excludes cogeneration facilities.

Table 4 shows the counties we selected in our siting exercise along with the transmission zone, infrastructure available, the selected generator step-up (“GSU”) high side-voltage, and the gas pipelines available in that county. The Eastern MAAC, Western MAAC, and Dominion CONE Areas each have multiple counties that meet our selection criteria, with several recent projects having been developed along corridors with major gas pipelines and with substantial electric infrastructure. In these areas, we selected locations with more recent projects where possible, recognizing that there are multiple locations with equally good siting opportunities. The Rest of RTO CONE Area is the largest geographically, spanning many states and containing a large number of recent builds. We selected a county near Chicago because this location has the highest concentration of recent projects.

Our siting selection for the Southwest MAAC CONE Area is less certain because there are no gas-fired generation projects recently built or under construction. In order to select a feasible site, we used additional criteria to supplement our requirement of electric and gas infrastructure availability. We selected Charles County over other counties because of a greater availability of vacant industrial land relative to the more densely developed locations along the Transco and Columbia pipelines.⁷ Further, the only permitted prospective gas plant in the CONE Area is in Charles County, the 640 MW CPV St. Charles gas CC project.⁸ The most recently built gas-fired facility in Southwest MAAC is the 230 MW Panda Cogeneration project, built in 1996 in the neighboring Prince Georges County immediately across the county line. We did not select this county due to the relatively longer gas interconnection lateral that would be required.⁹

⁷ For example, few vacant industrial properties are listed for sale or have been recently transacted in Howard or Montgomery counties in Maryland. In the past 2 years, the only transaction in Howard or Montgomery county for over 20 acres of vacant industrial land was located in Elkridge, Maryland, in Howard county, see Maryland Assessment Records (2011).

⁸ Ventyx (2011).

⁹ Ventyx (2011) and Platts (2011).

Table 4
Selected Locations for Reference Plants

CONE Area and County	Zone	Transmission		Gas Pipelines
		Infrastructure Available (kV)	GSU High-Side Voltage (kV)	
1 Middlesex, NJ	JCPL	130, 230, 500	230	Transco, Texas Eastern
2 Charles County, MD	PEPCO	230, 500	230	Dominion Cove Point
3 Will, IL	COMED	138, 345	345	ANR, Natural (NGPL), Midwestern, Guardian/Vector
4 Northampton, PA	PPL	138, 230, 500	230	Transco, Columbia
5 Fauquier, VA	DOM	115, 230, 500	230	Transco, Columbia, Dominion

Sources and Notes:

Transmission infrastructure information from PJM (2008).
Gas pipeline information from Platts (2011).

C. PLANT CONFIGURATION AND SIZE

We selected plant size and configuration based on a review of gas CT and CC projects currently under construction or built in PJM since 2002. Table 5 shows the amount of gas CT capacity built in PJM since 2002 for each plant size bracket. The plant size refers to the total plant size including all CT units installed at each site, with most plants including multiple turbine units. We selected a target plant size of 400-500 MW, which is the dominant size for newly-built CT plants in PJM, representing 2.8 of the 7.5 GW of PJM simple-cycle turbines built or under construction since 2002. This is the most common plant size range in the Rest of RTO and Dominion CONE Areas, representing three of the 13 recently built plants in the Rest of RTO Area and both of the two plants recently-built in Dominion. The Eastern MAAC CONE Area had three recently built plants, with the middle-sized one in the 400-500 MW range. Although there no sizeable recent projects in the Southwest MAAC and Western MAAC CONE Areas, we use the same 400-500 MW gas CT plant range for these areas.

Table 5
PJM Gas CT Plants under Construction or Built Since 2002

CONE Area	< 100 (MW)	100-200 (MW)	200-300 (MW)	300-400 (MW)	400-500 (MW)	500-600 (MW)	600-700 (MW)	700-800 (MW)	800-900 (MW)	Total (MW)
1 Eastern MAAC	48	0	0	326	462	0	639	0	0	1,474
2 Southwest MAAC	0	0	0	0	0	0	0	0	0	0
3 Rest of RTO	80	156	888	664	1,351	1,088	0	0	825	5,052
4 Western MAAC	10	0	0	0	0	0	0	0	0	10
5 Dominion	0	0	0	0	947	0	0	0	0	947
Total	138	156	888	990	2,760	1,088	639	0	825	7,484

Sources and Notes:

Plant information from Ventyx (2011).
Table includes only new plants, not additions to existing plants.

Similarly, we determined the predominant configuration for gas CC plants based on a survey of PJM plants currently under construction or built since 2002. Table 6 shows the amount of gas CC capacity built for each plant size and configuration. As the table shows, the dominant size

and configuration has been 500-700 MW in a 2x1 configuration.¹⁰ As we discuss in Sections II.D and II.F, we specified a slightly larger 2x1 plant consistent with the increased size of the new 7FA.05 turbine model.

Table 6
PJM Gas CC Plants under Construction or Built Since 2002

	< 300	300-500	500-700	700-900	900-1100	1100-1300	Total
	<i>(MW)</i>	<i>(MW)</i>	<i>(MW)</i>	<i>(MW)</i>	<i>(MW)</i>	<i>(MW)</i>	<i>(MW)</i>
2 x 1	0	0	5,593	0	0	0	5,593
2 x 2	0	0	573	0	0	0	573
3 x 1	245	0	556	2,386	0	0	3,187
4 x 2	0	0	0	0	1,080	3,725	4,805
4 x 4	0	0	0	0	0	1,140	1,140
6 x 2	0	0	0	0	935	1,130	2,065
Total	245	0	6,723	2,386	2,015	5,995	17,364

Sources and Notes:

Plant information from Ventyx (2011).

Table includes only new plants, not additions to existing plants.

D. TURBINE MODEL

We determined the predominant turbine models by reviewing the turbines installed in gas-fired plants in the United States since 2002. Table 7 shows the total installed capacity and costs of the most widely-used turbines used in gas CT plants since 2002.¹¹ The most commonly installed turbine since 2002 in simple-cycle configuration has been the GE Frame 7FA model turbine followed closely in terms of installed MW by the GE 7EA, although for our purposes we did not select that smaller turbine model because the 7FA has both a lower heatrate and a lower cost per unit of power output.

We also note that the 7FA turbine model has changed substantially during the period from 2002 to the 2015 installation date that we use for our turbine model. The 7FA.03 model available in 2003 had a nameplate capacity rating of 175 MW, while the 7FA.04 model had a higher rating of 183 MW. The new 7FA.05 model that is now available and will replace the 7FA.04 has a higher rating of 211 MW.¹² The updated 7FA.05 model also has a substantially improved heatrate.¹³

¹⁰ Also note that the second-most common configuration is 4x2, or two 2x1 units at a single plant.

¹¹ We use the Ventyx Energy Velocity database to identify the installed MW and turbine type for each technology. The database does not identify the turbine technology for all turbines.

¹² See GE (2009), p. 7.

¹³ The efficiency of the 7FA.05 is 1.4 percentage points higher than the 7FA.03 model on an LHV basis. See GE (2009), p. 5.

Table 7
Gas CT Units Installed by Turbine Type in the U.S. Since 2002

Turbine Model	Installed Since 2002		Cost
	<i>(MW)</i>	<i>(count)</i>	<i>(\$/kW)</i>
General Electric Co-MS7001FA GT	11,571	87	\$232
General Electric Co-MS7001EA	10,115	119	\$266
Siemens Power Generation Inc-SGT6-5000F	3,120	15	\$226
General Electric Co-LM6000PC Sprint	2,805	55	\$319
General Electric Co-LM6000PC	2,596	59	\$334
General Electric Co-GE LM6000	2,451	57	\$340
General Electric Co-LMS100PB-DLE2	1,881	19	\$296
Pratt & Whitney-FT8 Twinpac	1,860	30	\$298
General Electric Co-LMS100PA-SAC	1,854	18	\$300
Pratt & Whitney-FT8 SwiftPac	976	16	n/a

Sources and Notes:

Installed MW and number of units by turbine model from Ventyx (2011). This database is not completely comprehensive in identifying turbine model, with about 80% of the total MW installed since 2002 being identified by turbine type.

Turbine cost (excluding balance of plant) from *Gas Turbine World* (2010).

Similarly for gas CC plants, Table 8 shows the amount of capacity installed by turbine type since 2002, as well as cost information based on a typical configuration from *Gas Turbine World*. Like the gas CT plant, we chose the GE 7FA turbine because of its predominance and low capital costs compared with other turbines.

Table 8
Gas CC Units Installed by Turbine Type in the U.S. Since 2002

Turbine Model	Installed Since 2002		Cost
	<i>(MW)</i>	<i>(Count)</i>	<i>(\$/kW)</i>
General Electric Co-MS7001FA GT	32,940	180	\$473
Siemens Power Generation Inc-501FD	11,232	54	\$499
Mitsubishi Heavy Industries-M501G	5,874	22	\$504
Siemens Power Generation Inc-SGT6-6000G	1,335	5	n/a
General Electric Co-MS7001FB	1,260	7	\$466
Mitsubishi Heavy Industries-M501F	925	5	\$537
General Electric Co-MS7001EA	765	9	\$524
Siemens Power Generation Inc-V84.2	452	4	\$459
General Electric Co-LM6000PC Sprint	204	4	n/a
General Electric Co-LM6000PD Sprint	172	4	n/a

Sources and Notes:

Installed MW by turbine model from Ventyx (2011). This database is not completely comprehensive in identifying turbine model, with 35% of the total MW installed since 2002 being identified by turbine type.

Unit cost (including steam turbine but excluding balance of plant) assumes a typical configuration and steam turbine, from *Gas Turbine World* (2010).

E. COMBINED-CYCLE COOLING SYSTEM

For the reference combined-cycle plant, we assumed a closed-loop circulating water cooling system with a multiple-cell mechanical draft cooling tower, based on the predominance of cooling towers among new CCs and CH2M HILL’s recommendation. Among the 15 CC units installed in PJM since 2002 and reporting cooling system data, 13 have cooling towers while 2 have air cooling or once-through cooling systems.¹⁴

F. DUCT FIRING AND POWER AUGMENTATION

For the reference CC plant, we included duct firing capability, consistent with predominant practice among projects in PJM and elsewhere. We determined that a cost-effective amount of duct firing to include was 74 MW at 92 °F (76 MW at 59 °F) based on guidance from CH2M HILL, and consultation with GE representatives. According to CH2M and GE, this quantity of duct firing is consistent with 7FA.05 2x1 projects currently being developed.

For CCs and CTs, we also evaluated additional power augmentation options by comparing the capital costs and incremental output available if investing in each option. Table 9 and Table 10 compare inlet evaporative cooling to inlet chilling and to no power augmentation for both gas CT and CC plants. These cost and performance metrics were calculated by CH2M HILL using GE software, and while self-consistent, represent rough approximations of equipment and balance of plant (“BOP”) cost components without considering detailed locational, materials escalation, or other engineering cost factors.

¹⁴ Ventyx (2011).

We selected inlet evaporative cooling for power augmentation for both plant types because it increases their output substantially for only a small increase in cost. The slightly higher output that inlet chilling could provide does not appear cost-effective for the incremental cost, as indicated by the relatively higher cost per unit of output than that of the overall plant.

Table 9
Power Augmentation Comparison for Gas CT

	Total Cost (\$m)	Capacity		Incremental Output		Incremental Costs	
		ISO Conditions (MW)	Summer Conditions (MW)	ISO Conditions (MW)	Summer Conditions (MW)	ISO Conditions (\$/kW)	Summer Conditions (\$/kW)
None	\$192	412	377				
Inlet Evaporative Cooling	\$193	420	395	8	18	\$84	\$39
Inlet Chilling	\$205	425	417	5	22	\$2,306	\$555

Sources and Notes:

CH2M HILL (2011), using GE software.

International Organization for Standardization (ISO) conditions are 59 °F and 60% relative humidity.

Summer conditions are 90 °F and 53% relative humidity.

Table 10
Power Augmentation Comparison for Gas CC

	Total Cost (\$m)	Capacity		Incremental Output		Incremental Costs	
		ISO Conditions (MW)	Summer Conditions (MW)	ISO Conditions (MW)	Summer Conditions (MW)	ISO Conditions (\$/kW)	Summer Conditions (\$/kW)
None	\$449	618	550				
Inlet Evaporative Cooling	\$450	627	589	10	39	\$62	\$16
Inlet Chilling	\$463	633	613	5	24	\$2,640	\$580

Sources and Notes:

CH2M HILL (2011), using GE software.

International Organization for Standardization (ISO) conditions are 59 °F and 60% relative humidity.

Summer conditions are 90 °F and 53% relative humidity.

G. NO_x CONTROLS

In determining the NO_x controls that will be required for each new unit to pass its new source review (“NSR”) and receive an operating air permit, we considered the following: controls installed by recently developed gas-fired units, tightening standards due to recent and imminent EPA regulations, special permitting considerations in each plant location, and special technological considerations for each plant configuration we selected.

Table 11 contains a summary of NO_x control equipment on units built in PJM since 2002. The data is displayed separately for single-fuel and dual-fuel gas CCs and CTs, and by turbine type. The table shows that there are several NO_x controls that are consistently required under NSR for all units regardless of locational air permitting considerations. The table shows that all 7FA units in either CT or CC configuration are equipped with dry low-NO_x burners, as expected because dry-low NO_x burners are part of the 7FA turbine model design. All 7FA CC and CT units with dual-fuel capability are also equipped with water injection for NO_x control for use during firing

on distillate.¹⁵ Most recently built CCs installed with 7FA or non-7FA turbines have also been fitted with Selective Catalytic Reduction (“SCR”) controls.

Table 11
Number of Turbines with NO_x Control Equipment in PJM Units Installed Since 2002

	Single Fuel		Dual Fuel	
	All Turbine Models (count)	7FA Turbines (count)	All Turbine Models (count)	7FA Turbines (count)
Gas CT				
Dry Low NO _x Burners	39	7	23	17
Selective Catalytic Reduction	16	0	1	0
Water Injection	20	1	24	17
Total	55	7	24	17
Gas CC				
Dry Low NO _x Burners	17	11	10	10
Selective Catalytic Reduction	18	11	13	10
Water Injection	0	0	9	9
Total	18	11	13	10

Sources and Notes:
Ventyx (2011).

The data in Table 11 indicate that 7FAs in simply cycle mode have not installed SCRs. However, this does not prove that SCRs will be infeasible or unneeded in 2015 as environmental regulations continue to tighten. Many recently-built non-7FA CTs have been fitted with an SCR. Although no recently-built 7FA CTs have been fitted with SCRs, one earlier unit was fitted with this technology, however, it is not located in PJM.¹⁶ There are two reasons that few SCRs have been required on 7FAs in simple-cycle configuration. First, the 7FA has a relatively lower emissions rate than most other turbines even without an SCR because of its dry low-NO_x burning technology. The 7FA.05 NO_x emissions rate is 9 ppm without an SCR (2 ppm with an SCR), while many emissions standards have been developed based on the maximum allowed emissions rates of 25 ppm for gas CTs.¹⁷

Second, the temperature of 7FA turbine exhaust is very high, which requires the exhaust to be diluted through tempering air fans to avoid damaging the SCR equipment. Adding a hot SCR to a 7FA in simple-cycle configuration incurs a higher cost than adding a typical SCR to a turbine with a lower exhaust temperature. Despite the higher costs, CH2M HILL has confirmed with three potential suppliers of hot SCR controls that they have received inquiries and budget requests for hot SCRs on large F-class turbines for projects currently under development in the

¹⁵ Confirmed based on guidance from CH2M HILL and GE representatives.

¹⁶ The Rowan plant in Salisbury, North Carolina built in 2001, see Ventyx (2011).

¹⁷ See for example, New Jersey State Department of Environmental Protection (2011), pg. 29, as well as the Ozone Transport Commission (2010), pg. 4, both stipulate a maximum CT emissions rate of 25 ppm.

U.S. In particular, the Mirant Marsh Landing Generating station in Contra Costa County, CA will be fitted with a hot SCR and is currently expected to complete construction in 2013.¹⁸

The determination of whether a particular CT project will require an SCR in order to receive an air permit will be determined based on the outcome of the new source review (“NSR”), as determined on a case-by-case basis for each plant. The NSR is overseen by a state regulatory agency in most cases and is guided by the current status in meeting the National Ambient Air Quality Standards (“NAAQS”). In locations that are in attainment of the NAAQS, the NSR is conducted under the Prevention of Significant Deterioration (“PSD”) rules that require units to install the Best Available Control Technology (“BACT”) in order to obtain approval. In locations that are designated as non-attainment of the NAAQS, the Non-Attainment NSR (“NNSR”) rule require units to apply the more stringent Lowest Achievable Emissions Rate (“LAER”) standard.¹⁹ In locations that have previously been in non-attainment and are currently in “maintenance” of the NAAQS, the NSR will generally continue to impose a stringent control technology standard in order to maintain air quality pollutant levels.

The attainment status for ozone, for which NO_x is a precursor, is the most relevant for determining whether an SCR will be required. Table 12 shows the current 8-hour ozone attainment status based on current NAAQS. The EPA is currently in the process of tightening its NAAQS for ozone with new standards to be ruled soon after the publication of this study that will likely bring more areas into nonattainment.²⁰ Additional regulatory uncertainty regarding the need for an SCR is also introduced by the Cross-State Air Pollution Rule (“CSAPR”) finalized on July 6, 2011 that will require PJM states to revise their SIPs in order to help meet ozone NAAQS not only in their own states but also in specific downwind locations in other states.²¹

Table 12
8-Hour Ozone Attainment Status

CONE Area	County	Ozone Attainment Status
1 Eastern MAAC	Middlesex, NJ	Nonattainment
2 Southwest MAAC	Charles County, MD	Nonattainment
3 Rest of RTO	Will, IL	Nonattainment
4 Western MAAC	Northampton, PA	Maintenance
5 Dominion	Fauquier, VA	Attainment

Sources and Notes:
EPA (2011a).

After considering the regulatory and technological factors described above, we believe the most likely outcome of a 7FA simple-cycle NSR for an online date of June 1, 2015 is that the project will be required to be fitted with an SCR if it is currently in a non-attainment or maintenance area for ozone, but that it will not need an SCR if it is in an attainment area. Table 13 contains a

¹⁸ The plant permit to construct contains details about the plant configuration and SCR, see BAAQMD (2010). Online date from Ventyx (2011).

¹⁹ See EPA (2011b).

²⁰ See EPA (2011c).

²¹ See EPA (2011d).

summary of the resulting NO_x controls that we selected for each plant configuration, by location. All plants are assumed to have dry-low NO_x combustion, consistent with the 7FA turbine model. For all CONE Areas other than “Rest of RTO,” the units are equipped with dual-fuel capability and are therefore also equipped with water injection.²² Finally, we assume that all CC CT plants in ozone non-attainment areas will be equipped with an SCR, with the exception of the Dominion CT plant, assumed not to have an SCR. However, because of the current regulatory and technological uncertainty regarding the need for an SCR on CTs in each location, we also provide alternative CT CONE estimates in sensitivity cases that we recommend PJM and stakeholders use if these uncertainties are resolved in the future.

Table 13
NO_x Control Equipment for Gas CT and CC Plant

CONE Area	Gas CT			Gas CC		
	SCR	Dry Low NO _x	Water	SCR	Dry Low NO _x	Water
	(Y/N)	Burners (Y/N)	Injection (Y/N)	(Y/N)	Burners (Y/N)	Injection (Y/N)
1 Eastern MAAC	Y	Y	Y	Y	Y	Y
2 Southwest MAAC	Y	Y	Y	Y	Y	Y
3 Rest of RTO	Y	Y	N	Y	Y	N
4 Western MAAC	Y	Y	Y	Y	Y	Y
5 Dominion	N	Y	Y	Y	Y	Y

H. DUAL-FUEL CAPABILITY

To determine whether each reference unit should be equipped with dual-fuel capability, we considered the prevalence of dual-fuel capability in existing and recently built units. We also analyzed the need for dual-fuel capability based on the frequency of gas curtailment events in each location.

Table 14 and Table 15 summarize dual-fuel or single-fuel capability for all CT and CC capacity for the states containing the selected location within each CONE Area. These tables show clear patterns in the Eastern MAAC, Rest of RTO, and Dominion CONE Areas. In Eastern MAAC, the majority of CTs and CCs have been equipped with dual-fuel capability. In the Rest of RTO area, almost no gas CTs and CCs have dual-fuel capability, except for one CT plant in Illinois. In the Dominion Area, dual-fuel capability is dominant for both gas CT and CC plants.

There was not a definitive pattern in the other two CONE Areas, due to the lack of recently constructed units in some cases and due to the mix of dual-fuel and non-dual-fuel plants in Western MAAC. To supplement our analysis in these areas, we examined the number of non-maintenance curtailments on the Transcontinental pipeline (which runs through all of the eastern CONE Areas) as well as the ANR pipeline (which runs through ComEd). Table 16 shows that curtailments on the Transco pipeline have been much more frequent than along the ANR pipeline. Based on this information and the predominance of dual-fuel capability in other eastern

²² Our sensitivity case with dual-fuel capability in the Rest of RTO CONE Area is also equipped with water injection.

locations, we decided that these locations would be most appropriately fitted with dual-fuel capability.

Table 14
Single-Fuel and Dual-Fuel Gas CTs in Selected PJM States

CONE Area	State	Units Installed Since 2002			All Units Installed		
		Gas Only (MW)	Dual Fuel (MW)	Total (MW)	Gas Only (MW)	Dual Fuel (MW)	Total (MW)
1 Eastern MAAC	New Jersey	326	90	416	368	2,208	2,575
2 Southwest MAAC	Maryland	0	0	0	236	557	792
3 Rest of RTO	Illinois	2,192	456	2,648	5,736	456	6,192
4 Western MAAC	Pennsylvania	0	0	0	447	0	447
5 Dominion	Virginia	0	1,428	1,428	0	2,990	2,990

Sources and Notes:

Ventyx (2011).

Summary numbers include all PJM units within the selected state.

Table 15
Single-Fuel and Dual-Fuel Gas CCs in Selected PJM States

CONE Area	State	Units Installed Since 2002			All Units Installed		
		Gas Only (MW)	Dual Fuel (MW)	Total (MW)	Gas Only (MW)	Dual Fuel (MW)	Total (MW)
1 Eastern MAAC	New Jersey	766	1,780	2,546	820	2,735	3,555
2 Southwest MAAC	Maryland	0	0	0	0	0	0
3 Rest of RTO	Illinois	1,140	0	1,140	1,144	0	1,144
4 Western MAAC	Pennsylvania	1,920	1,130	3,050	2,589	1,130	3,719
5 Dominion	Virginia	0	1,494	1,494	0	2,801	2,801

Sources and Notes:

Ventyx (2011).

Summary numbers include all PJM units within the selected state.

Table 16
Non-Maintenance Curtailments Since 2010

	# of Curtailments
ANR Pipeline Co	3
Transcontinental Gas Pipe Line Corp	46

Sources and Notes:

Ventyx (2011).

To summarize, we determined that the reference units should have dual-fuel capability with the exception of the Rest of RTO CONE Area. However, for consistency and at the request of PJM, we also evaluated the cost of dual-fuel plants in the Rest of RTO area. We also considered whether units without dual-fuel capability would need to contract for firm gas delivery. We contacted several plant operators in the ComEd transmission zone and confirmed that they do not currently have firm gas delivery contracts. We therefore conclude that firm gas commitments need not be considered as part of our study.

I. GAS COMPRESSION

We determined that gas compression would generally not be needed for new gas plants located near and/or along the major gas pipelines selected in our study. Although gas pressures occasionally fall below the pressures the reference plants require, these instances are rare enough that gas compression capability would be generally unused. To support this conclusion we inquired with gas pipeline operators to confirm the average and realistic minimum expected gas pressures in each location. The New Jersey site has the lowest gas pressures of all CONE Areas; however, we confirmed with individual plant operators in New Jersey that no on-site gas compression was needed at their facilities. Further, these eastern plants' ability to meet capacity obligations is supported by having dual-fuel capability.

J. BLACK START CAPABILITY

We do not include black start capability in either the CC or the CT reference units because few recently built gas units have this capability. Table 17 shows the number of gas CT and CC units that have been built and are currently operating with or without black start capability since 2002 based on PJM data. We reviewed these data by CONE Area and found no locational differences.

Table 17
Black Start Capability in Gas Plants Built Since 2002

	Gas CT	Gas CC
Total Number of Plants Built	24	21
Total Number of Plants with Black Start	4	1

Sources and Notes:
PJM (2011a).

III. REFERENCE TECHNOLOGY PERFORMANCE AND SPECIFICATIONS

Table 18 shows the summary of plant characteristics selected in Section II as well as major plant performance characteristics as determined by CH2M HILL. As discussed in Section II.D, we identified the GE 7FA.05 turbine as the most appropriate technology for the reference gas CT and CC plants. This turbine is substantially larger than previous models, with the 7FA.05 model having an increased nominal capacity rating 36 MW relative to the 7FA.03, as well as having a substantially improved heatrate.²³ This increases output significantly for both the gas CT and CC plants relative to previous PJM CONE studies, due to the larger gas turbine in all configurations as well as an increased size for the heat recovery steam generator ("HRSG") and steam turbine on the CC. Table 19 contains a summary of emissions rates under each plant configuration.

²³ General Electric (2011a).

Table 18
Gas CT and CC Plant Characteristics and Performance

Plant Characteristic	Simple Cycle	Combined Cycle
Turbine Model	GE 7FA.05	GE 7FA.05
Configuration	2 x 0	2 x 1
Net Plant Power Rating	CONE Areas 1-4 (w/ SCR): 418 MW at 59 °F 390 MW at 92 °F CONE Area 5 (w/o SCR): 420 MW at 59 °F 392 MW at 92 °F	Baseload (w/o Duct Firing): 627 MW at 59 °F 584 MW at 92 °F Maximum Load (w/ Duct Firing): 701 MW at 59 °F 656 MW at 92 °F
Cooling System	n/a	Cooling Tower
Power Augmentation	Evaporative Cooling	Evaporative Cooling
Net Heat Rate (HHV)	CONE Areas 1-4 (w/ SCR): 10,094 btu/kWh at 59 °F 10,320 btu/kWh at 92 °F CONE Area 5 (w/o SCR): 10,036 btu/kWh at 59 °F 10,257 btu/kWh at 92 °F	Baseload (w/o Duct Firing): 6,722 btu/kWh 59 °F 6,883 btu/kWh 92 °F Maximum Load (w/ Duct Firing): 6,914 btu/kWh at 59 °F 7,096 btu/kWh at 92 °F
NO _x Controls	Dry Low NO _x Burners Selective Catalytic Reduction (Areas 1-4) Water Injection for DFO (Areas 1-2, 4-5)	Dry Low NO _x Burners Selective Catalytic Reduction Water Injection for DFO (Areas 1-2, 4-5)
Dual Fuel Capability	Single Fuel (Area 3) Distillate Fuel Oil (Areas 1-2, 4-5)	Single Fuel (Area 3) Distillate Fuel Oil (Areas 1-2, 4-5)
Blackstart Capability	None	None
On-Site Gas Compression	None	None

Sources and Notes:

Plant specifications are based on reference technology determination study as presented in Section II.
Plant technical performance data were determined by CH2M HILL (2011).

Table 19
Gas CT and CC Plant Emissions Rates

	NO_x		VOC		CO	
	NG <i>(ppm)</i>	Fuel Oil <i>(ppm)</i>	NG <i>(ppm)</i>	Fuel Oil <i>(ppm)</i>	NG <i>(ppm)</i>	Fuel Oil <i>(ppm)</i>
Gas CT No SCR	9	42	7	7	9	20
Gas CT w/ SCR	2	5	5	5	5	11
Gas CC	2	5	5	5	5	11

Sources and Notes:

Plant emissions data were determined by CH2M HILL (2011).

IV. CAPITAL COST ESTIMATES

Costs for the gas CT and CC plants are broken into two categories: capital costs and fixed operation and maintenance (“FOM”) costs. Capital costs are incurred when constructing the power plant, before the commercial online date. Power plant developers typically hire an engineering, procurement, and construction (“EPC”) company to complete construction and to ensure the plant operates properly. The costs of EPC contractor services, as well as the costs of major Owner-Furnished Equipment (“OFE”), were estimated by CH2M HILL as summarized in Section IV.A below for plant proper costs. There are additional owner’s capital costs that a gas CT or CC developer would face, such as the purchasing of land, development costs, interconnection costs, start-up fuel, and owner’s contingency which we estimate in Section IV.B.

A. PLANT PROPER CAPITAL COSTS

Plant proper costs include most of the costs required to engineer and construct a plant including the costs of major equipment and EPC services. CH2M HILL developed engineering cost estimates for the reference technology and sensitivity case estimates in our study as summarized here. Full documentation and supporting details regarding these estimates are included as Appendices A and B for the simple-cycle and combined-cycle technologies respectively.

1. Plant Developer and Contractor Arrangements

We asked CH2M HILL to assume that a plant owner will contract with an EPC services provider to engineer and construct the project. The EPC contractor would then be responsible for procuring all equipment and materials with the exception of major Owner-Furnished Equipment. The OFE consists of the plant gas turbines and SCR units for the simple-cycle plants, and the gas turbines, steam turbines, and HRSG units in the combined-cycle case. The OFE in our scenario is purchased by the owner and then assigned to the EPC contractor, meaning that, while the owner initially orders the equipment, the EPC contractor takes on responsibility for handling delivery and installation of the equipment.

We also asked CH2M HILL to assume that the EPC contractor will be taking on all contingency risk associated with cost overruns for all items within their scope. This associated contingency risk includes all contingency risk associated with the assigned OFE including delivery delays, but excludes any contingency risk associated with potential change orders to the EPC scope.

2. Owner-furnished Equipment and Sales Tax

The plant proper costs that will be paid directly by the owner include the costs of OFE and sales tax incurred in procuring the OFE, as well as the sales tax incurred by the EPC contractor and passed through to the owner. Table 20 summarizes these direct owner’s costs for the simple-cycle plant, with OFE including two 7FA.05 gas turbines and a hot SCR. Table 21 summarizes these costs for the combined-cycle plant, with the OFE including two 7FA.05 gas turbines, a steam turbine, and two HRSG units. These owner costs are incurred over the capital drawdown schedule as summarized in Section IV.A.4. Additional supporting documentation for these costs is included in Appendix A for the simple-cycle and Appendix B for the combined-cycle configurations.

Table 20
CT Costs of Owner-Furnished Equipment and Sales Taxes

CONE Area	OFE				Sales Tax				Total	
	CT		SCR		OFE Scope		EPC Scope			
	(\$m)	(\$/kW)	(\$m)	(\$/kW)	(\$m)	(\$/kW)	(\$m)	(\$/kW)	(\$m)	(\$/kW)
1 Eastern MAAC	\$93.0	\$238.7	\$21.5	\$55.2	\$8.0	\$20.6	\$2.3	\$6.0	\$124.9	\$320.5
2 Southwest MAAC	\$93.0	\$238.7	\$21.5	\$55.2	\$6.9	\$17.6	\$2.0	\$5.1	\$123.4	\$316.7
3 Rest of RTO	\$90.0	\$231.0	\$21.5	\$55.2	\$7.8	\$20.0	\$2.0	\$5.2	\$121.3	\$311.4
4 Western MAAC	\$93.0	\$238.7	\$21.5	\$55.2	\$6.9	\$17.6	\$2.0	\$5.2	\$123.4	\$316.7
5 Dominion	\$93.0	\$237.2	\$0.0	\$0.0	\$4.7	\$11.9	\$1.8	\$4.6	\$99.5	\$253.7

Sources and Notes:

Owner-furnished equipment and sales tax data provided by CH2M HILL (2011).

Table 21
CC Costs of Owner-Furnished Equipment and Sales Taxes

CONE Area	OFE						Sales Tax				Total	
	CT		HRSG		ST		OFE Scope		EPC Scope			
	(\$m)	(\$/kW)	(\$m)	(\$/kW)	(\$m)	(\$/kW)	(\$m)	(\$/kW)	(\$m)	(\$/kW)	(\$m)	(\$/kW)
1 Eastern MAAC	\$93.0	\$141.8	\$41.0	\$62.5	\$42.0	\$64.1	\$12.3	\$18.8	\$6.5	\$9.9	\$194.8	\$297.1
2 Southwest MAAC	\$93.0	\$141.8	\$41.0	\$62.5	\$42.0	\$64.1	\$10.6	\$16.1	\$5.5	\$8.4	\$192.1	\$292.9
3 Rest of RTO	\$90.0	\$137.3	\$41.0	\$62.5	\$42.0	\$64.1	\$12.1	\$18.5	\$6.1	\$9.4	\$191.3	\$291.7
4 Western MAAC	\$93.0	\$141.8	\$41.0	\$62.5	\$42.0	\$64.1	\$10.6	\$16.1	\$5.5	\$8.5	\$192.1	\$293.0
5 Dominion	\$93.0	\$141.8	\$41.0	\$62.5	\$42.0	\$64.1	\$8.8	\$13.4	\$4.6	\$7.0	\$189.4	\$288.9

Sources and Notes:

Owner-furnished equipment and sales tax data provided by CH2M HILL (2011).

3. Engineering Procurement and Construction Costs

All other plant proper costs are paid to the EPC contractor as summarized in Table 22 and Table 23. These costs include all EPC costs required to engineer and construct the plant after considering specific locational and time-dependent escalation rates for materials, equipment, and labor. Direct project costs include, but are not limited to, materials, instrumentation, site work, craft labor, freight, and balance of plant (“BOP”) mechanical and electrical equipment. Indirect costs include taxes, builder’s all risk insurance, and performance and payment bonds. Management costs include project management, engineering, procurement, site management, and startup. Contingency costs are incorporated for all potential cost over-runs within EPC scope and a project profit margin is included.

These EPC costs are incurred over the capital drawdown schedule as summarized in Section IV.A.4. Additional supporting documentation for these costs is included in Appendix A for the simple-cycle and Appendix B for the combined-cycle configurations.

Table 22
EPC Costs for Gas CT Plants

CONE Area	EPC Costs	
	(\$m)	(\$/kW)
1 Eastern MAAC	\$130.6	\$335.1
2 Southwest MAAC	\$105.0	\$269.5
3 Rest of RTO	\$113.6	\$291.5
4 Western MAAC	\$123.0	\$315.8
5 Dominion	\$104.0	\$265.3

Sources and Notes:

EPC Costs provided by CH2M HILL (2011).

Table 23
EPC Costs for Gas CC Plants

CONE Area	EPC Costs	
	(\$m)	(\$/kW)
1 Eastern MAAC	\$356.2	\$543.3
2 Southwest MAAC	\$274.6	\$418.8
3 Rest of RTO	\$334.9	\$510.8
4 Western MAAC	\$333.4	\$508.6
5 Dominion	\$274.4	\$418.5

Sources and Notes:

EPC Costs provided by CH2M HILL (2011).

4. Capital Drawdown Schedules

CH2M HILL has developed monthly capital drawdown schedules over the project development period for each plant configuration. Separate monthly drawdown schedules have been developed for the direct owner's plant proper costs identified in Section IV.A.2, as well as for the EPC costs identified in Section IV.A.3. These drawdown schedules differ slightly for each plant, but representative drawdown schedules are included for one simple-cycle plant in Appendix A.5, consistent with the project schedule in Appendix A.4, as well as for one combined-cycle plant in Appendix B.5 consistent with the project schedule in Appendix B.4.

B. OWNER'S CAPITAL COSTS

Outside of the plant proper owner and EPC costs, there are additional costs an owner must incur in the development and construction of a generating plant. We estimate these costs, which include land, emissions reductions credits, gas interconnection, electric interconnection, start-up fuel during testing, and owner's contingency. We developed these cost estimates based on publicly-available sources, except for project development and owner's contingency, for which estimates are based on industry experience and conversations with a number of project developers and plant operators.

1. Land

We estimated the cost of land by reviewing historical transaction prices and current asking prices for vacant industrial land for sale in each selected county. We narrowed the recent transactions

and current land offers by looking only at land greater than 20 acres, and considering only sites listed as vacant or classified as “unimproved land.” We estimated land costs using a weighted average of historical transaction prices when available, supplemented with current asking prices. Table 24 shows the range and number of observations for current asking prices as well as recent transactions on industrial land.

**Table 24
Current and Historical Land Costs**

CONE Area	County	Current Asking Prices		Recent Transactions	
		Range	Observations	Range	Observations
		(\$000/acre)	(count)	(\$000/acre)	(count)
1 Eastern MAAC	Middlesex, NJ	\$70-\$236	5	\$228-\$306	2
2 Southwest MAAC	Charles County, MD	\$78-\$217	6	\$97-\$217	4
3 Rest of RTO	Will, IL	\$42-\$217	15	\$83-\$189	4
4 Western MAAC	Northampton, PA	\$13-\$209	8	\$136	1
5 Dominion	Fauquier, VA	\$42-\$335	2	\$11-\$34	3

Sources and Notes:

- Current Asking Prices from LoopNet (2011).
- New Jersey Assessment Records (2011).
- Maryland Assessment Records (2011).
- Illinois Assessment Records (2011).
- Pennsylvania Assessment Records (2011).
- Virginia Assessment Records (2011).

Table 25 shows the resulting land prices we used for each CONE Area (calculated by taking a weighted average of the historical transactions and current offerings). We also include the acreage needed, based on recommendations from CH2M HILL, and report the final estimated cost for the land for each location.

**Table 25
Gas CT and CC Land Costs**

CONE Area	County	Land Price (\$/acre)	Acreage		Cost	
			Gas CT (acres)	Gas CC (acres)	Gas CT (\$m)	Gas CC (\$m)
			[1]	[2]	[3]	[4]
1 Eastern MAAC	Middlesex, NJ	\$129,000	30	40	\$3.87	\$5.16
2 Southwest MAAC	Charles County, MD	\$120,000	30	40	\$3.60	\$4.80
3 Rest of RTO	Will, IL	\$80,000	30	40	\$2.40	\$3.20
4 Western MAAC	Northampton, PA	\$90,000	30	40	\$2.70	\$3.60
5 Dominion	Fauquier, VA	\$118,000	30	40	\$3.54	\$4.72

2. Emissions Reductions Credits

As part of its NSR, a plant may be required to procure emissions reductions credits (ERCs) in areas that are in Maintenance or Nonattainment of the EPA’s National Ambient Air Quality Standards (NAAQS). ERCs represent permanent reductions in air quality pollutants that must be purchased to offset the emissions of new major sources. A new plant must obtain ERCs from nearby existing facilities that have created ERCs by permanently reducing their emissions output

through retirement or other means.²⁴ We estimate ERC costs for VOCs and NO_x, which are precursors to ozone and for which both the CC and CT plants will be considered major sources.

To estimate the number of ERCs needed, we started with two recently permitted plants, the Bayonne Energy Center gas CT and the York Energy Center gas CC facilities. Both air permits specify a potential to emit (PTE), or the maximum potential emissions limit for the year.²⁵ We then developed an estimate of PTE for each reference plant by scaling based on each plant's heatrate, emissions rate, and total MW rating as summarized in Table 26.

Table 26
Total Potential to Emit

	Capacity (MW)	Heat Rate (btu/kWh)	Emission Rates		Potential to Emit	
			NO _x (ppm)	VOC (ppm)	NO _x (tpy)	VOC (tpy)
Recently Permitted Plants						
Bayonne (CT)	512	9,519	2.5	2.5	109.5	36.8
York Energy Center (CC)	1,100	7,727	2.0	2.0	460.2	46.2
Reference Technology						
Gas CT No SCR	392	10,036	9.0	7.0	318.2	83.2
Gas CT w/ SCR	390	10,094	2.0	5.0	70.8	59.5
Gas CC	656	6,722	2.0	5.0	238.8	59.9

Sources and Notes:

- See Bayonne Permits Obtained (2011), pg. 151 for capacity, pg. 158 for emission rates, and pg. 76 for PTE
- See York Energy Center Permits Obtained (2005) for capacity, emissions rates, and potential to emit
- See Ventyx (2011) for heat rate information
- See CH2M HILL Engineers, Inc. (2011) for reference technology specifications.

We used locational cost estimates for ERCs provided by CH2M HILL to determine the total compliance costs as shown in Table 27 and Table 28. In each case the total ERCs that must be procured is also multiplied by a location-specific offset ratio, reflecting the requirement to procure offsets in excess of PTE at a rate that depends on the severity of ozone Nonattainment as reported previously in Table 12. Because Dominion is in Attainment, we do not estimate ERC costs for that location.

²⁴ See EPA (2011e)

²⁵ See Bayonne Permits Obtained (2011) and York Energy Center Permits Obtained (2005).

Table 27
Gas CT Emission Reduction Credits

CONE Area	Emissions Offsets		Emission Offset Cost and Ratio				ERC Costs		
	NOx (tpy)	VOC (tpy)	NOx (\$/tpy)	VOC (\$/tpy)	NOx (ratio)	VOC (ratio)	NOx (\$m)	VOC (\$m)	Total (\$m)
1 Eastern MAAC	71	59	\$4,000	\$4,000	1.30	1.30	\$0.37	\$0.31	\$0.68
2 Southwest MAAC	71	59	\$3,000	\$5,000	1.30	1.30	\$0.28	\$0.39	\$0.66
3 Rest of RTO	71	59	\$5,000	\$4,000	1.15	1.15	\$0.41	\$0.27	\$0.68
4 Western MAAC	71	59	\$4,000	\$4,000	1.15	1.15	\$0.33	\$0.27	\$0.60
5 Dominion	--	--	--	--	--	--	--	--	--

Sources and Notes:

Emissions offsets from Table 25.

Emission offset costs from CH2M HILL Engineers, Inc. (2011).

Emission offset ratios from Evolution Markets (2011).

Table 28
Gas CC Emission Reduction Credits

CONE Area	Emissions Offsets		Emission Offset Cost				ERC Costs		
	NOx (tpy)	VOC (tpy)	NOx (\$/tpy)	VOC (\$/tpy)	NOx (ratio)	VOC (ratio)	NOx (\$)	VOC (\$)	Total (\$)
1 Eastern MAAC	239	60	\$4,000	\$4,000	1.30	1.30	\$1.24	\$0.31	\$1.55
2 Southwest MAAC	239	60	\$3,000	\$5,000	1.30	1.30	\$0.93	\$0.39	\$1.32
3 Rest of RTO	239	60	\$5,000	\$4,000	1.15	1.15	\$1.37	\$0.28	\$1.65
4 Western MAAC	239	60	\$4,000	\$4,000	1.15	1.15	\$1.10	\$0.28	\$1.37
5 Dominion	--	--	--	--	--	--	--	--	--

Sources and Notes:

Emissions offsets from Table 25.

Emission offset costs from CH2M HILL Engineers, Inc. (2011).

Emission offset ratios from Evolution Markets (2011).

3. Gas Interconnection

To estimate gas interconnection costs, we used historical gas lateral interconnection costs filed with the Federal Energy Regulatory Commission (“FERC”). Each gas plant must build a lateral pipeline from a major natural gas pipeline in order to operate. Total pipeline costs depend on several factors, including pipeline width, pipeline length, terrain, right-of-way costs, and whether a project has a metering station, which measures quality and amount of natural gas being transferred in a pipeline. Table 29 shows historical pipeline costs for several projects with publicly-reported costs.

Table 29
Historical Gas Lateral Project Costs Filed with FERC

Expansion		State	Pipeline Width	Pipeline Length	Pipeline Cost	Meter Station	Station Cost
			<i>(inches)</i>	<i>(miles)</i>	<i>(\$/mile)</i>	<i>(Y/N)</i>	<i>(m\$)</i>
Delta Lateral Project	[1]	DE	16	3.42	\$2.77	Y	\$3.33
MarkWest	[2]	NM	16	3.16	\$1.10	N	n/a
Texas Eastern Transmission	[3]	LA	20	3.79	\$3.76	Y	\$3.16
Gulfstream	[4]	FL	20	17.74	\$3.44	Y	\$3.72
Bayonne Delivery Lateral Project	[5]	NJ	20	6.24	\$2.21	Y	\$3.86
Columbia Gas	[6]	NJ	24	23.80	\$1.63	Y	\$3.09
Duke Energy Indiana	[7]	IN	20	19.50	\$1.92	Y	\$3.75
Average					\$2.40		\$3.48

Sources and Notes:

- [1] Delta Lateral Project (2009).
- [2] MarkWest (2007).
- [3] Texas Eastern Transmission Co. (2007).
- [4] Gulfstream (2006).
- [5] Bayonne Delivery Lateral Project (2009).
- [6] Columbia Gas (2001).
- [7] Duke Energy Indiana, Inc. (2010).

Pipeline lengths range from 3 to 23 miles. For the gas CT and CC plants in our study, we selected siting locations in the same county as a major gas pipeline, with a reasonable availability of vacant industrial land. For this reason, we assume that each plant will interconnect with a pipeline with a 5-mile gas lateral, a reasonable assumption based on historical pipeline lengths. In addition, each plant will be equipped with a metering station.²⁶ Total gas interconnection costs vary widely from location to location, but we estimate a cost consistent with the average observed. We estimate the total gas interconnection cost for each CONE area is \$16 million based on \$2.5 million per mile for 5 miles plus \$3.5 million for the metering station.

4. Electric Interconnection

We estimated electric interconnection costs based on historical electric interconnection cost data provided by PJM.²⁷ Electric interconnection costs consist of two categories of costs: direct connection costs and network upgrade costs. Direct connection costs will be incurred by any new project connecting to the network. Network upgrade costs do not always occur, but are incurred when improvements, such as replacing the transformer, are required.

To determine the most appropriate basis for determining expected interconnection costs, we reviewed interconnection costs for plants recently built and summarized them by voltage, plant size, and location. The total range of interconnection costs is quite large, depending on both voltage and plant size. Interconnections below 138kV vary substantially as a function of voltage and can be quite low, while interconnection costs above that threshold did not appear to vary substantially by voltage. For projects above 138kV, plant size is another factor affecting

²⁶ Note that while meter stations are not included in all projects in Table 29, this means only that the meter station cost was not included as part of the public filing, not that the project was without a meter station.

²⁷ PJM Interconnection, L.L.C. (2011a).

interconnection costs, as summarized in Table 31. We did not observe any systematically different costs by location. The wide range of costs, particularly network upgrade costs, over a relatively small number of observations for large plants, means that the upgrade costs for any individual project may vary substantially. To estimate costs for our reference plants, we examined the costs for similarly-sized plants.

For the CT, we reviewed interconnection costs for 300-500 MW plants. The average direct interconnect cost was \$3.1 million and the average network upgrade cost was \$7.7 million, for a total of \$10.8 million. For the CC, we considered 500-750 MW plants. The average direct interconnect cost is \$7.7 million and the average network upgrade cost is \$7.9 million. Based on these numbers, we estimate the total interconnection costs at approximately \$11.0 million for the CT and \$15.5 million for the CC.

Table 30
Historical Electric Interconnection Costs in PJM

Plant Size	Observations (count)	Direct Interconnection Costs		Network Upgrade Costs		Total Costs	
		Avg. (\$m)	Median (\$m)	Avg. (\$m)	Median (\$m)	Avg. (\$m)	Median (\$m)
100-300 MW	5	\$1.1	\$0.2	\$4.4	\$0.1	\$5.5	\$0.3
300-500 MW	4	\$3.1	\$3.2	\$7.7	\$6.7	\$10.8	\$9.8
500-750 MW	9	\$7.7	\$4.0	\$7.9	\$2.5	\$15.6	\$6.5

Sources and Notes:

Source is PJM (2011a).

Excludes plants that are interconnected at 138kV or lower.

5. Net Start-Up Fuel Costs during Testing

Before commencing full commercial operations, new generation plants must undergo testing to ensure the plant is functioning and producing power correctly. This occurs in the months before the online date and involves testing the turbine generators on natural gas, as well as fuel oil if it has dual-fuel capability. We received fuel consumption and energy production data from CH2M HILL for each plant type based on data from recently built projects.²⁸ During testing, a plant will pay for the natural gas and fuel oil consumption, and will receive revenues for its energy production.

We estimated the cost of natural gas using Henry Hub futures through 2015 and adding a basis differential to each delivery point. We used the Chicago Citygate basis differential for the Rest of RTO CONE Area, and our estimate of the Transco Zone 6 Non-New York (Z6 NNY) basis for all other CONE areas.²⁹ We averaged the delivered price over the months of testing to obtain

²⁸ Reported in Appendices A.1 and B.1 for the simple cycle and combined cycle plants respectively.

²⁹ Because Z6 NNY basis future is an illiquid product there are no futures data available there. Instead we used the Zone 6 New York (Z6 NY) basis after adjusting for the historical relationship between the two. Historically, the Z6 NNY and Z6 NY prices are nearly identical except for three winter months when the Z6 NY prices spikes much higher than (but with a strong correlation to) the Z6 NNY price. Because neither the Z6 NY and Chicago Citygate basis futures are available as far forward as 2015, we increased the monthly-varying basis futures at the rate of inflation for subsequent years. Henry hub futures and basis differentials were downloaded from Bloomberg (2011).

a natural gas price estimate. We estimated the cost of fuel oil using distillate futures through 2012, extended to 2015 using historical relationship between crude oil and distillate prices.³⁰

We estimated the future energy price based on PJM Eastern Hub for Eastern MAAC, Northern Illinois Hub for the Rest of RTO, and PJM Western Hub for all other CONE Areas.³¹ We calculated a 2012 market heat rate based on electricity and gas futures in each location, and assuming this market heat rate would remain constant to 2015. We averaged the resulting estimates for locational day-ahead on-peak and off-peak energy prices to estimate the average revenues that would be received during testing. Table 31 summarizes these gas, oil, and energy price estimates as well as our total resulting net startup cost estimates. Net costs are highest in the Rest of RTO Area where energy prices are lowest, and are lower for CC plants, which have a lower heatrate and whose costs will be lower relative to their revenues. In Eastern MAAC our net startup fuel cost is actually negative due to our higher energy price estimate in that location.

Table 31
Startup Production and Fuel Consumption During Testing

	Energy Production			Fuel Consumption						Total Cost (\$m)
	Energy Produced (MWh)	Energy Price (\$/MWh)	Energy Sales (\$m)	Natural Gas (MMBtu)	Natural Gas Price (\$/MMBtu)	NG Cost (\$m)	Fuel Oil (MMBtu)	Fuel Oil Price (MMBtu)	Fuel Oil Cost (\$m)	
Gas CT										
1 Eastern MAAC	215,000	62.7	13.5	2,000,000	7.02	14.0	75,060	21.9	1.6	2.21
2 Southwest MAAC	215,000	54.8	11.8	2,000,000	7.02	14.0	75,060	21.9	1.6	3.90
3 Rest of RTO	215,000	41.6	8.9	2,000,000	5.67	11.3	75,060	21.9	1.6	4.05
4 Western MAAC	215,000	54.8	11.8	2,000,000	7.02	14.0	75,060	21.9	1.6	3.90
5 Dominion	215,000	54.8	11.8	2,000,000	7.02	14.0	75,060	21.9	1.6	3.90
Gas CC										
1 Eastern MAAC	546,788	62.7	34.3	4,138,657	7.24	30.0	75,060	22.1	1.7	-2.65
2 Southwest MAAC	546,788	54.8	30.0	4,138,657	7.24	30.0	75,060	22.1	1.7	1.66
3 Rest of RTO	546,788	41.6	22.8	4,138,657	5.71	23.7	75,060	22.1	1.7	2.56
4 Western MAAC	546,788	54.8	30.0	4,138,657	7.24	30.0	75,060	22.1	1.7	1.66
5 Dominion	546,788	54.8	30.0	4,138,657	7.24	30.0	75,060	22.1	1.7	1.66

Sources and Notes:

Energy production and fuel consumption from CH2M HILL Engineers, Inc. (2011).
Energy and fuel prices from Bloomberg (2011).

6. O&M Mobilization and Startup

Concurrent with their estimates of O&M and service agreement costs presented in Sections 30V.CV.EV.E and X, Wood Group has provided estimates of pre-operation mobilization costs. These costs summarized in Table 32 would be incurred during construction in the last year prior to the commercial online date. Additional supporting details for these estimates are included in Appendix C.

³⁰ Number 2. distillate and WTI Cushing crude oil futures from Bloomberg (2011).

³¹ Mapping is based on the portion of price nodes in each zone that are combined for the aggregate hub node price.

Table 32
Pre-Operation Mobilization Costs

CONE Area	Gas CT (\$m)	Gas CC (\$m)
1 Eastern MAAC	\$1.2	\$2.9
2 Southwest MAAC	\$1.1	\$2.7
3 Rest of RTO	\$1.1	\$2.8
4 Western MAAC	\$1.1	\$2.6
5 Dominion	\$1.0	\$2.6

Sources and Notes:

For additional details see Wood Group report in Appendix C.

7. Project Development, Financing Fees, and Owner’s Contingency

For several categories of owner’s costs, there are no readily available public sources documenting them. We estimated these costs based on industry experience and discussions with a number of project developers and plant operators.

Project development costs are the owner’s costs for all development activities from the initial feasibility studies through project startup, exclusive of plant proper and other owner’s costs that we estimated separately. These costs include market studies, interconnection studies, staff time for project development, permitting fees, legal fees, water and sewer interconnection, and technical professionals hired throughout development and construction. Owner’s costs also include financing fees to pay lenders for securing the project debt, financial advisor fees, and legal fees for contract support, including gas procurement contracts, construction contracts, lease agreements, and O&M contracts. We estimate these fees at \$6 million for the simple-cycle and \$8 million for the combined-cycle plants. We estimate financing fees at 200 basis points applied to the 50% portion of the project financed with debt as discussed in detail in Section VI.

Owner’s contingency reflects the expected value of unforeseen cost categories that may fall outside of the original scope of the project, additional materials needed, unforeseen costs incurred for permits or land, or price increases on materials not anticipated by the owner. Our estimates are consistent with our assumed arrangement in which the EPC contractor will take on all contingency risk associated with cost items in their scope, but will not take on any risks associated with change orders. Further, we considered the actual expected realized contingency costs, and excluded any reserve funds that may often be set aside in case of contingency but that would not be expected to be spent on average. Finally, we excluded contingencies associated with gas and electric interconnections since our estimates in those categories already reflect an expected value based on the average of actual projects. The owner’s contingency estimate is 3% of total project oversight costs before considering contingency or interest during construction (“IDC”).

V. FIXED AND VARIABLE OPERATION AND MAINTENANCE COSTS

Once the plant enters commercial operation, the plant owners incur fixed costs each year, including property taxes, plant insurance, facility fees for operating labor and minor maintenance, and asset management costs. We subcontracted with the O&M services provider Wood Group Power Operations, Inc. to estimate facility operation and maintenance fees as part of our Gross CONE calculation. Wood Group also provided estimate for variable O&M costs and major maintenance and long-term service agreement (“LTSA”) costs for use in PJM’s dispatch modeling of E&AS offsets.

A. PROPERTY TAX

We calculated property tax rates for each location using state and county property records to calculate the implied tax rate based on 2010 taxes paid by the current plant owners in each CONE Area. For each location, we determined the relevant tax rates, which in many cases apply only to the assessed value of land, but in other cases also apply to the value of the plant. Table 33 contains a summary of the plant tax rates and total annual taxes in each county where we estimated the first year of operation (increasing each year by the 2.5% inflation rate that we estimated in Section VI.A).

For Eastern MAAC we considered property tax rates paid by 3 different power plant owners in Middlesex, NJ.³² Each owner paid 4.25% property taxes on the land only and had no additional taxes for the plant on the land. In Southwest MAAC, power plant owners paid 1.14% tax on land and \$831/MW tax on the power plant.³³ In the Rest of RTO CONE Area represented by Will County, IL, property taxes are 1.72% of land market value³⁴ (5.15% tax rate on one-third land market value).³⁵ In Western MAAC, the power plant owner paid taxes at a rate of 3.02% on the value of the land plus \$135/MW on the power plant.³⁶ In Dominion, we found property taxes did not need to be paid by power plants in Fauquier County, and the Commissioner of the Revenue Office confirmed that power plants are exempt from property tax.

³² Used property tax information from AES Red Oak, LLC., North Jersey Energy Associates, and Reliant Energy NJ Holdings. See New Jersey Assessment Records (2011).

³³ Used property tax information from Mirant Mid-Atlantic LLC. See Maryland Assessment Records (2011).

³⁴ Illinois Department of Revenue (2011), p. 11.

³⁵ Used property tax information from Midwest Generation LLC. See Illinois Assessment Records (2011).

³⁶ Used property tax information from Conectiv Bethlehem LLC. See Pennsylvania Assessment Records (2011).

Table 33
Property Taxes for Gas CT and CC Plants

CONE Area	County	Property Tax Rate		Property Tax	
		Land (%)	Plant (\$/MW-yr)	Gas CT (\$/yr)	Gas CC (\$/yr)
1 Eastern MAAC	Middlesex, NJ	4.25%	\$0	\$164,475	\$219,300
2 Southwest MAAC	Charles County, MD	1.14%	\$831	\$390,060	\$637,251
3 Rest of RTO	Will, IL	1.72%	\$0	\$41,163	\$54,884
4 Western MAAC	Northampton, PA	3.02%	\$135	\$138,240	\$203,355
5 Dominion	Fauquier, VA	0.00%	\$0	\$0	\$0

Sources and Notes:

- New Jersey Assessment Records (2011).
- Maryland Assessment Records (2011).
- Illinois Assessment Records (2011).
- Pennsylvania Assessment Records (2011).
- Virginia Assessment Records (2011).

B. INSURANCE

We estimated insurance costs by contacting insurance companies with experience insuring gas CT and CC plants. Insurance coverage includes general liability, property, boiler and machinery, and business interruption. We estimated the annual premiums for the CT and CC plants at \$1.75 million and \$3.75 million respectively for the first online year, increasing at the 2.5% inflation rate that we estimated in Section VI.A.

C. ANNUAL FIXED FEES FOR PLANT OPERATION AND MAINTENANCE

We subcontracted with Wood Group to estimate annual fixed O&M costs. Table 34 and Table 35 show the first year annual fixed O&M expenses for the CT and CC reference plant in each location, with costs increasing with inflation over time. The largest component of the fixed operating expenses is the staff labor costs, accounting for approximately half of the total fixed O&M costs depending on plant type and location. The remaining annual O&M services costs are comprised of consumables, office administration, maintenance and minor repairs, and corporate and administrative charges. Additional supporting details for the Wood Group estimates are contained in Appendix C.

Table 34
Gas CT First Year Annual Fixed O&M Expenses

	CONE Area				
	1	2	3	4	5
	EMAAC (\$m)	SWMAAC (\$m)	RTO (\$m)	WMAAC (\$m)	DOM (\$m)
Facility Staff Labor Costs	\$1.47	\$1.30	\$1.38	\$1.26	\$1.25
Consumables	\$0.16	\$0.16	\$0.16	\$0.16	\$0.16
Office Administration	\$0.16	\$0.16	\$0.16	\$0.16	\$0.16
Maintenance & Minor Repairs	\$0.51	\$0.51	\$0.51	\$0.51	\$0.51
Corporate & Administrative Charges	\$0.41	\$0.41	\$0.41	\$0.41	\$0.41
Total	\$2.72	\$2.54	\$2.62	\$2.50	\$2.50

Sources and Notes:

For additional details see Wood Group report in Appendix C.

Table 35
Gas CC First Year Annual Fixed O&M Expenses

	CONE Area				
	1	2	3	4	5
	EMAAC (\$m)	SWMAAC (\$m)	RTO (\$m)	WMAAC (\$m)	DOM (\$m)
Facility Staff Labor Costs	\$3.88	\$3.45	\$3.63	\$3.34	\$3.31
Consumables	\$0.30	\$0.30	\$0.30	\$0.30	\$0.30
Office Administration	\$0.21	\$0.21	\$0.21	\$0.21	\$0.21
Maintenance & Minor Repairs	\$0.92	\$0.92	\$0.92	\$0.92	\$0.92
Corporate & Administrative Charges	\$0.43	\$0.43	\$0.43	\$0.43	\$0.43
Total	\$5.74	\$5.31	\$5.49	\$5.20	\$5.17

Sources and Notes:

For additional details see Wood Group report in Appendix C.

D. ASSET MANAGEMENT COSTS

Asset management costs are costs associated with ongoing compliance, permitting, legal, contract management, fuel management, accounting, energy sales management, ISO interface, and administrative overhead. We estimated asset management costs at \$1.5 million annually for both the CT and CC plants based on estimates provided to us by several asset owners.

E. VARIABLE OPERATION AND MAINTENANCE COSTS

Variable operation and maintenance (“VOM”) costs are not part of gross CONE but are needed for estimating administrative E&AS offsets. Wood Group has estimated two components of these VOM costs consistent with their other O&M estimates: (1) the relatively small variable component of the facilities O&M costs, primarily consisting of consumables, and (2) the larger costs associated with major maintenance overhauls through an LTSA. Table 36 contains a summary of these variable costs by CONE Area.

As explained in more detail in Appendix C, the LTSA contract structures vary, but we asked Wood Group to assume a contract structure that would be appropriate to use over a range of operating profiles. The timing of LTSA payments (and major maintenance events) depends on plant operations as measured typically through factored fired starts (“FFS”) or factored fired hours (“FFH”).³⁷ For simple-cycle plants, LTSA costs are typically determined on a starts basis as a function of FFS. For combined-cycle plants, LTSA costs may be either starts-based or hours-based depending on how much the plant is cycling. Based on guidance from Wood Group about one type of typical contract structure, we assume that if the plant cycles frequently with the FFH:FFS ratio ≤ 27 , then all LTSA costs would be assessed on an starts basis. If the plant cycle less frequently with long duty cycles and an FFH:FFS ratio > 27 then the LTSA would be hours-based.

Table 36
Variable O&M and LTSA Costs

CONE Area	Gas CT		Gas CC		
	VOM	LTSA	VOM	LTSA	LTSA
	(\$/MWh)	(\$/FFS)	(\$/MWh)	(\$/FFS)	(\$/FFH)
1 Eastern MAAC	\$0.91	\$19,846	\$0.85	\$10,370	\$311
2 Southwest MAAC	\$0.91	\$17,501	\$0.85	\$9,144	\$274
3 Rest of RTO	\$0.91	\$18,565	\$0.85	\$9,700	\$291
4 Western MAAC	\$0.91	\$16,968	\$0.85	\$8,866	\$266
5 Dominion	\$0.87	\$16,887	\$0.85	\$8,823	\$265

Sources and Notes:

For additional details see Wood Group report in Appendix C.

All LTSA costs would be hours-based if FFH:FFS > 30 , or all starts-based otherwise.

VI. FINANCIAL ASSUMPTIONS

A. INFLATION

Inflation rates affect our net CONE estimates by forming the basis for projected increases in several FOM costs over time. We also use the inflation rate as cost escalation rate in our level-real CONE estimate as discussed in Section VII.C. We estimated future inflation rates based on bond market data and consensus U.S. economic projections. Table 37 shows that the implied inflation rate from Treasuries is 2.3% over 5 years, 2.6% over 10 years, and 2.8% over 20 years as of late April 2011. Figure 3 shows the historical nominal and inflation protected yields, as well as the implied inflation since 2008. Since 2011, implied inflation averaged approximately 2.5%.

These implied rates are consistent with consensus projections. The monthly Blue Chip Economic Indicators report compiles analyst forecasts from various financial institutions and has

³⁷ FFS and FFH account for the number of starts or the number of fire-hours experienced, but also consider other factors that will contribute to requiring maintenance to be scheduled earlier. Two examples of these factors include whether the starts were on gas or oil and whether the unit has tripped, although a full account of these factors can be obtained from the turbine manufacturer, see Appendix C.


consensus forecasts for various economic variables. The consensus ten-year average consumer price index (“CPI”) forecast through 2022 is 2.4%.³⁸ Based on these two sources, we chose an estimated average long-term inflation rate of 2.5%.

Table 37
Implied Inflation from Treasury Yields

	5-year (%)	10-year (%)	20-year (%)
Nominal Yield	2.2%	3.5%	4.3%
Inflation Protected Yield	-0.1%	0.9%	1.5%
Implied Inflation	2.3%	2.6%	2.8%

Sources and Notes:
Yields as of April 25, 2011.
Bloomberg (2011).

Figure 3
Implied Inflation Since 2008



Sources and Notes:
Bloomberg (2011).

³⁸ Blue Chip Economic Indicators (2011), p. 15.

B. INCOME TAX AND DEPRECIATION SCHEDULE

All corporations with an income above \$18.3 million have a marginal federal tax rate of 35%.³⁹ We estimate that the gas CT or CC plant will need to earn at least approximately twice that amount in net annual income to be economically viable as determined in Section VII.C, placing it in the highest corporate tax bracket. In addition, the plants will be subject to a state-specific income tax rate as summarized in Table 38.

Table 38
State Corporate Income Tax Rates

CONE Area	State	Tax Rate (%)
1 Eastern MAAC	New Jersey	9%
2 Southwest MAAC	Maryland	8.25%
3 Rest of RTO	Illinois	9.5%
4 Western MAAC	Pennsylvania	9.99%
5 Dominion	Virginia	6%

Sources and Notes:

Tax Foundation (2011)

NJ corporate tax rate is for income greater than \$100,000. All other states are for income greater than \$0.

The Federal tax code allows generating companies to use a Modified Accelerated Cost Recovery System (“MACRS”) of 15 years for a Gas CT plant and 20 years for a Gas CC plant.⁴⁰ Table 39 shows this depreciation schedule as a function of the operating year.

³⁹ IRS (2010a).

⁴⁰ Asset classes 49.13 and 49.15, see IRS (2010b).

Table 39
MACRS Depreciation Schedule

Year	Gas CT (%)	Gas CC (%)
1	8.75%	6.56%
2	9.13%	7.00%
3	8.21%	6.48%
4	7.39%	6.00%
5	6.65%	5.55%
6	5.99%	5.13%
7	5.90%	4.75%
8	5.91%	4.46%
9	5.90%	4.46%
10	5.91%	4.46%
11	5.90%	4.46%
12	5.91%	4.46%
13	5.90%	4.46%
14	5.91%	4.46%
15	5.90%	4.46%
16	0.74%	4.46%
17		4.46%
18		4.46%
19		4.46%
20		4.46%
21		0.57%
Sum	100.0%	100.0%

Sources and Notes:
IRS (2010b), Table A-2.

C. COST OF CAPITAL

The financing assumptions and cost of capital we used in developing CONE are consistent with a merchant generation project that is balance-sheet financed by a larger corporate entity. To inform our cost of capital estimate, we calculated the after-tax weighted-average cost of capital (“ATWACC”) for a portfolio of publicly-traded merchant generation companies. We also considered ATWAAC estimates from equity analysts and fairness opinions rendered in recent merger and acquisition transactions as summarized in Section VI.C.2. After considering each of these pieces of information, we developed a recommended estimate of the ATWACC as reported in Section VI.C.2.

1. Estimated Cost of Capital for a Portfolio of Merchant Generation Companies

In calculating a cost of capital estimate, we examined a value-weighted portfolio and the five publicly-traded merchant generation companies: NRG, Calpine, Dynege, GenOn Energy

(formerly known as RRI Energy), and GenOn Energy Holdings (formerly known as Mirant).⁴¹ Table 40 shows the market capitalization of these companies. For each of these companies, we estimated the return on equity, cost of debt, debt-to-equity ratio, and ATWAAC.

Table 40
Market Capitalization of Merchant Generation Companies

	Market Capitalization (\$m)
NRG Energy, Inc.	\$5,163
GenOn Energy Inc (fka RRI Energy)	\$1,467
Calpine Corp.	\$6,861
GenOn Energy Holdings Inc (fka Mirant)	\$1,271
Dynegy, Inc.	\$696

Source: Bloomberg (2011).

a. Return on Equity

We estimate the return on equity (ROE), the return that stockholders require to invest in a company, using the Capital Asset Pricing Model (“CAPM”) for each merchant generation company as shown in Table 41. The ROE for each company is the risk free rate for U.S. treasuries plus a risk premium, defined as a company’s beta multiplied by the market premium.⁴²

We calculate the risk free rate of 4.3% using a 15-day average of 20-year U.S. treasuries as of April 2011.⁴³ We estimate a market risk premium of 6.5% based on an average of long-term equity risk premia of 6.7% and 6.3% from Ibbotson and Credit Suisse.⁴⁴ The company beta describes a company’s correlation with the market; we calculate each company’s beta using the S&P 500 over the last five years.⁴⁵

⁴¹ Mirant and RRI merged in December 2010 to form GenOn. Our analysis spans the time period before and after the merger, prior to which RRI and Mirant are tracked as separate companies and after which our reported results reflect the performance of the merged company. See GenOn (2010).

⁴² Brealey, *et al.* (2011), p. 193.

⁴³ Treasury yields of 4/27/2011 from Bloomberg (2011).

⁴⁴ Ibbotson (2011), Table A-1 and Dimson, *et al.* (2010), Table 10.

⁴⁵ The security’s beta is measured as the covariance of the stock price and market index divided by the variance of the market index. A beta of 1 implies that, on average, when the market moves 1%, the company’s stock moves 1% as well. A company with a beta of 2 is more volatile because, on average, its share price moves 2% with a 1% move in the market. We calculated betas for each company by averaging 5-year weekly betas starting Mondays, Wednesdays, and Fridays .

Table 41
Merchant Generation Company Return on Equity

Merchant Generation Company	Risk Free Rate (%) [1]	Market Risk Premium (%) [2]	Beta [3]	Return on Equity (%) [4]
NRG Energy, Inc.	4.3%	6.5%	1.10	11.4%
GenOn Energy Inc (fka RRI Energy)	4.3%	6.5%	1.73	15.6%
Calpine Corp.	4.3%	6.5%	1.29	12.7%
GenOn Energy Holdings Inc (fka Mirant)	4.3%	6.5%	1.08	11.3%
Dynegy, Inc.	4.3%	6.5%	1.55	14.4%
Value-weighted Portfolio Average	4.3%	6.5%	1.23	12.3%

Sources and Notes:

- [1] 15-day average yield of 20-year U.S. Treasury Rate as of 4/25/2011 from Bloomberg (2011).
- [2] Average of long-term equity risk premia of 6.7% and 6.3% from Ibbotson⁴⁶ and Credit Suisse,⁴⁷ respectively.
- [3] Five year average of Monday, Wednesday, and Friday weekly betas from Bloomberg (2011). RRI Energy and Mirant betas are as of 4/9/2010, one week before merger announcement. Dynegy beta is as of 8/6/2010, one week before Blackstone's tender offer.
- [4] $[1] + [2] \times [3]$.

b. Cost of Debt

We estimated the cost of debt by compiling the unsecured senior credit ratings for each of the five merchant generation companies and examining bond yields associated with those credit ratings. In Standard and Poor's ("S&P") credit ratings, a company receives a higher rating based on its ability to meet its financial commitments, with "AAA" being the highest rating and "D" being the lowest.⁴⁸ Table 42 shows the S&P credit rating, 5-year average long-term debt, and the corporate bond yield implied by the credit rating for each merchant generation company. The credit rating for four of the companies is "B" while NRG has a rating of "BB," implying that these companies are more risky and vulnerable to adverse business, financial, and economic conditions than are top-rated companies. We calculate the industry bond yield of 8.1% by weighting each company's bond yield by its 5-year average long-term debt.

⁴⁶ Ibbotson (2011), Table A-1.

⁴⁷ Dimson, *et al.* (2010), Table 10.

⁴⁸ Standard & Poor's (2011)

Table 42
Standard & Poor's Credit Ratings for Merchant Generation Companies

Merchant Generation Company	S&P Credit Rating	5-Year Average Long-Term Debt (\$m)	Corporate Bond Yield (%)
	[1]	[2]	[3]
NRG Energy, Inc.	BB	\$8,847	7.0%
GenOn Energy Inc (fka RRI Energy)	B	\$2,683	8.5%
Calpine Corp.	B	\$10,062	8.5%
GenOn Energy Holdings Inc (fka Mirant)	B	\$2,848	8.5%
Dynegy, Inc.	B	\$5,149	8.5%
Value-weighted Portfolio Average			8.1%

Sources and Notes:

[1] – [3] Credit ratings, average long-term debt, and corporate bond yield as of 4/25/2011 from Bloomberg (2011).

c. Debt-to-Equity Ratio

Table 43 shows the 5-year average debt-to-equity ratio for each merchant generation company that we examine, as reported in each company's annual 10-K report.

Table 43
5-Year Average Debt-to-Equity Ratios

	Debt/Equity Ratio
NRG Energy Inc	59/41
GenOn Energy Inc (fka RRI Energy)	41/59
Calpine Corp	67/33
GenOn Energy Holdings Inc (fka Mirant)	38/62
Dynegy Inc	66/34
Value-weighted Portfolio Average	56/44

Sources and Notes:

5-year average debt-to-equity ratio from annual 10-K reports, and downloaded from Bloomberg (2011).

d. Estimated After-Tax Weighted-Average Cost of Capital

We estimate the ATWAAC using ROE and cost of debt estimated for each company in Sections VI.C.1.a – b, as well as the debt-to-equity ratio and corporate tax rate reported by each company. The cost of capital is the weighted average of the cost of equity and the cost of debt.⁴⁹ To calculate ATWACC, interest is a tax deductible expense for corporations so the after-tax cost is discounted by (1- tax rate). Table 44 shows a summary of these results for each of the merchant generating companies we examined along with the value-weighted average across the portfolio. Table 44 also shows the average and median of ATWAAC values.

⁴⁹ Brealey, *et al.* (2011), p. 216.

Table 44
Cost of Capital Summary for Merchant Generation Companies

Company	S&P Credit Rating	Equity Beta	Cost of Equity (%)	Debt-to- Equity Ratio	Cost of Debt (%)	Corporate Income Tax Rate (%)	ATWACC (%)
	[1]	[2]	[3]	[4]	[5]	[6]	[7]
NRG Energy, Inc.	BB	1.10	11.4%	59/41	7.0%	40.0%	7.2%
GenOn Energy Inc (fka RRI Energy)	B	1.73	15.6%	41/59	8.5%	40.0%	11.2%
Calpine Corp.	B	1.29	12.7%	67/33	8.5%	40.0%	7.6%
GenOn Energy Holdings Inc (fka Mirant)	B	1.08	11.3%	38/62	8.5%	40.0%	8.9%
Dynegy, Inc.	B	1.55	14.4%	66/34	8.5%	40.0%	8.3%
Average							8.6%
Median							8.3%
Value-weighted Portfolio Average		1.23	12.3%		8.0%	40.0%	8.1%

Sources and Notes:

Bloomberg (2011).

[1] S&P unsecured senior credit ratings as of April 2011 from Bloomberg (2011).

[2] Five-year average of Monday, Wednesday, and Friday weekly betas from Bloomberg (2011).

RRI Energy and Mirant betas are as of 4/9/2010, one week before merger announcement.

Dynegy beta is as of 8/6/2010, one week before Blackstone's tender offer.

[3] From Table 41.

[4] 5-year average debt-to-equity ratio from annual 10-K reports, and downloaded from Bloomberg (2011).

[5] Table 24.

[6] KPMG (2010), p. 26.

[6] $[3] \times [4] + [5] \times [4] \times (1 - [6])$, Brealey, *et al.* (2011), p. 216.

2. Cost-of-Capital Estimates from Industry Analysts and Fairness Opinions

We compared our estimates of ATWACC to industry analysts and fairness opinions for the companies in our portfolio, as well as other merchant generation segments of publically-traded companies. Analyst estimates range from 7.1% to 12% ATWACC, with most estimates within 8.0% to 9.0%. These numbers are in line with our value-weighted portfolio average of 8.1%. Table 45 shows the industry analysts and fairness opinions by company.

Table 45
ATWACC Estimates from Industry Analysts/Fairness Opinions

		ATWACC Estimates [1]
NRG Energy Inc	[1]	7.1%
GenOn Energy Inc (fka RRI Energy)	[2]	8.5% - 9.5%
Calpine Corp	[3]	7.5%
GenOn Energy Holdings Inc (fka Mirant)	[4]	8.5% - 9.5%
Dynegy Inc	[5]	8.0% - 12.0%
FirstEnergy Merchant Generation	[6]	8.0% - 9.0%
Allegheny Merchant Generation	[7]	8.0% - 8.5%
Duke's Merchant Generation	[8]	8.2% - 9.2%

Sources and Notes:

- [1] Cohen, Jonathan, and Greg Gordon (2010a), p. 7.
- [2] Mirant Corp. And RRI Energy (2010), p. 42.
- [3] Cohen, Jonathan, and Greg Gordon (2010b), p. 7.
- [4] Mirant Corp. And RRI Energy (2010), p. 48.
- [5] Dynegy Inc. (2010), p. 48.
- [6] FirstEnergy Corp. and Allegheny Energy (2010), p. 85.
- [7] FirstEnergy Corp. and Allegheny Energy (2010), p. 84.
- [8] Duke Energy Corporation (2011), p. 102.

3. After-Tax Weighted-Average Cost of Capital Estimate

We considered both the value-weighted portfolio and recent ATWACC estimates in order to calculate ATWACC for the CONE study. We chose a ATWACC of 8.5%, 40 basis points higher than the value-weighted portfolio average that reflects a 50/50 debt-to-equity ratio, a 12.5% return on equity, and a 7.5% return on debt. The ATWACC of our recommendation has a slightly higher expected rate of return when compared to the value-weighted portfolio average, which reflects the business risk of the entire portfolio of contracts and the entire generation fleet of different technologies, fuel types, and locations. Table 46 shows a summary of the merchant generation companies, as well as our recommendation for ATWACC of 8.5%, which is consistent with the median of the ATWACC estimates (including the midpoints of the Analysts' ranges) reported in the bottom half of Table 46.

Table 46
Summary of Recommended Financial Parameters

Merchant Generation Company	S&P Credit Rating	Brattle Estimates				Analyst ATWACC Estimates
		Cost of Equity	Cost of Debt	Debt-to- Equity Ratio	ATWACC	
		(%)	(%)		(%)	(%)
	[1]	[2]	[3]	[4]	[5]	[6]
Comparable Merchant Power Generation Companies						
NRG Energy Inc	BB	11.4%	7.0%	59/41	7.2%	7.1%
Genon Energy Inc (fka RRI Energy)	B	15.6%	8.5%	41/59	11.2%	8.5% - 9.5%
Calpine Corp	B	12.7%	8.5%	67/33	7.6%	7.5%
Genon Energy Holdings Inc (fka Mirant)	B	11.3%	8.5%	38/62	8.9%	8.5% - 9.5%
Dynegy Inc	B	14.4%	8.5%	66/34	8.3%	8.0% - 12.0%
Merchant Generation Segments of Publicly Traded Companies						
FirstEnergy Merchant Generation						8.0% - 9.0%
Allegheny Merchant Generation						8.0% - 8.5%
Duke's Merchant Generation						8.2% - 9.2%
Average					8.6%	
Median					8.3%	
Value-weighted Portfolio Average		12.3%	8.0%	56.2%	8.1%	
Brattle Recommended Financial Parameters		12.5%	7.5%	50.0%	8.5%	

Sources and Notes:

- [1] Table 42
- [2] Table 41
- [3] Table 42
- [4] Table 43
- [5] Table 44
- [6] Table 45

D. INTEREST DURING CONSTRUCTION

Because the construction of a CC or a CT power plant takes a few years, the interest on debt used to fund the power plant construction is required by tax law to be capitalized (*i.e.*, added to the depreciable cost basis) prior to energy production, and amortized over time once production starts. The IDC can be computed on the actual interest expenses traceable to the construction of the power plant, or the interest on a theoretical amount of debt that would have been avoidable but for the construction project. For modeling purposes, we assume that the power plant construction would be funded at the same debt ratio (50%) and debt cost (7.5%) as in the operation phase.

VII. SUMMARY OF CAPITAL, FIXED, AND LEVELIZED COSTS

In this Section, we summarize capital and fixed annual operating costs developed in Sections IV and V, reporting the resulting total plant costs. Based on these costs and the financial assumptions developed in Section VI, we report our resulting level-real and level-nominal CONE estimates. We report these levelized CONE estimates for each CONE Area for the selected reference technology as well as for select sensitivity cases regarding plant technology.

A. TOTAL CAPITAL COSTS

Table 47 and Table 48 contain a summary of the total plant capital costs estimated in Section IV for the simple-cycle and combined-cycle reference plants respectively for a June 1, 2015 on-line date. We report these numbers as overnight costs as well as total capital costs after accounting for interest during construction (“IDC”).

Table 47
Simple-Cycle Capital Costs for 2015/16

	CONE Area					CONE Area				
	1	2	3	4	5	1	2	3	4	5
	EMAAC (\$m)	SWMAAC (\$m)	RTO (\$m)	WMAAC (\$m)	DOM (\$m)	EMAAC (\$/kW)	SWMAAC (\$/kW)	RTO (\$/kW)	WMAAC (\$/kW)	DOM (\$/kW)
Plant Proper Costs										
EPC Contract	\$130.6	\$105.0	\$113.6	\$123.0	\$104.0	\$335.1	\$269.5	\$291.5	\$315.8	\$265.3
Owner Furnished Equipment	\$114.5	\$114.5	\$111.5	\$114.5	\$93.0	\$293.9	\$293.9	\$286.2	\$293.9	\$237.2
OFE and EPC Sales Tax	\$10.4	\$8.9	\$9.8	\$8.9	\$6.5	\$26.6	\$22.8	\$25.2	\$22.8	\$16.5
Owner's Costs										
Land	\$3.9	\$3.6	\$2.4	\$2.7	\$3.5	\$9.9	\$9.2	\$6.2	\$6.9	\$9.0
Emissions Reduction Credits	\$0.7	\$0.7	\$0.7	\$0.6	\$0.0	\$1.7	\$1.7	\$1.7	\$1.5	\$0.0
Gas Interconnection	\$16.0	\$16.0	\$16.0	\$16.0	\$16.0	\$41.1	\$41.1	\$41.1	\$41.1	\$40.8
Electric Interconnection	\$11.0	\$11.0	\$11.0	\$11.0	\$11.0	\$28.2	\$28.2	\$28.2	\$28.2	\$28.1
Net Start-up Fuel Costs	\$2.2	\$3.9	\$4.1	\$3.9	\$3.9	\$5.7	\$10.0	\$10.4	\$10.0	\$10.0
Mobilization and Start-up	\$1.2	\$1.1	\$1.1	\$1.1	\$1.0	\$3.0	\$2.8	\$2.9	\$2.8	\$2.5
Project Development	\$6.0	\$6.0	\$6.0	\$6.0	\$6.0	\$15.4	\$15.4	\$15.4	\$15.4	\$15.3
Financing Fees	\$3.0	\$2.7	\$2.8	\$2.9	\$2.4	\$7.6	\$6.9	\$7.1	\$7.4	\$6.2
Owner's Contingency	\$9.0	\$8.2	\$8.4	\$8.7	\$7.4	\$23.0	\$21.0	\$21.5	\$22.4	\$18.9
Total Overnight Costs	\$308	\$282	\$287	\$299	\$255	\$791	\$723	\$737	\$768	\$650
Interest During Construction	\$14.0	\$12.7	\$10.9	\$13.5	\$11.5	\$36.0	\$32.6	\$27.8	\$34.5	\$29.4
Total Capital Costs	\$322	\$294	\$298	\$313	\$266	\$827	\$755	\$765	\$803	\$679

Sources and Notes:

Plant proper costs estimated by CH2M HILL Engineers, Inc. (2011).

Owner's costs estimated in Section IV.B

Table 48
Combined-Cycle Capital Costs for 2015/16

	CONE Area					CONE Area				
	1	2	3	4	5	1	2	3	4	5
	EMAAC (\$m)	SWMAAC (\$m)	RTO (\$m)	WMAAC (\$m)	DOM (\$m)	EMAAC (\$/kW)	SWMAAC (\$/kW)	RTO (\$/kW)	WMAAC (\$/kW)	DOM (\$/kW)
Plant Proper Costs										
EPC Contract	\$356.2	\$274.6	\$334.9	\$333.4	\$274.4	\$543.3	\$418.8	\$510.8	\$508.6	\$418.5
Owner Furnished Equipment	\$176.0	\$176.0	\$173.0	\$176.0	\$176.0	\$268.4	\$268.4	\$263.9	\$268.4	\$268.4
OFE and EPC Sales Tax	\$18.8	\$16.1	\$18.3	\$16.1	\$13.4	\$28.7	\$24.5	\$27.8	\$24.6	\$20.4
Owner's Costs										
Land	\$5.2	\$4.8	\$3.2	\$3.6	\$4.7	\$7.9	\$7.3	\$4.9	\$5.5	\$7.2
Emissions Reduction Credits	\$1.6	\$1.3	\$1.6	\$1.4	\$0.0	\$2.4	\$2.0	\$2.5	\$2.1	\$0.0
Gas Interconnection	\$16.0	\$16.0	\$16.0	\$16.0	\$16.0	\$24.4	\$24.4	\$24.4	\$24.4	\$24.4
Electric Interconnection	\$15.5	\$15.5	\$15.5	\$15.5	\$15.5	\$23.6	\$23.6	\$23.6	\$23.6	\$23.6
Net Start-up Fuel Costs	-\$2.7	\$1.7	\$2.6	\$1.7	\$1.7	-\$4.0	\$2.5	\$3.9	\$2.5	\$2.5
Mobilization and Start-up	\$2.9	\$2.7	\$2.8	\$2.6	\$2.6	\$4.4	\$4.1	\$4.2	\$4.0	\$4.0
Project Development	\$8.0	\$8.0	\$8.0	\$8.0	\$8.0	\$12.2	\$12.2	\$12.2	\$12.2	\$12.2
Financing Fees	\$6.0	\$5.2	\$5.8	\$5.7	\$5.1	\$9.1	\$7.9	\$8.8	\$8.8	\$7.8
Owner's Contingency	\$18.1	\$15.7	\$17.4	\$17.4	\$15.5	\$27.6	\$23.9	\$26.6	\$26.5	\$23.7
Total Overnight Costs	\$621	\$537	\$599	\$597	\$533	\$948	\$820	\$914	\$911	\$813
Interest During Construction	\$37.0	\$31.9	\$35.4	\$35.2	\$31.5	\$56.4	\$48.6	\$53.9	\$53.7	\$48.0
Total Capital Costs	\$658	\$569	\$634	\$633	\$564	\$1,004	\$868	\$968	\$965	\$861

Sources and Notes:

Plant proper costs estimated by CH2M HILL Engineers, Inc. (2011).
Owner's costs estimated in Section IV.B

B. TOTAL FIXED O&M COSTS

Table 47 and Table 48 contain a summary of the fixed ongoing annual plant costs estimated in Section V for the simple-cycle and combined-cycle reference plants respectively. The costs reported here are the first-year FOM costs for the first operating year starting in 2014/15. Each of these costs increases with inflation over the economic life of the plant.

Table 49
Simple-cycle Fixed O&M Costs

	CONE Area					CONE Area				
	1	2	3	4	5	1	2	3	4	5
	EMAAC (\$m/y)	SWMAAC (\$m/y)	RTO (\$m/y)	WMAAC (\$m/y)	DOM (\$m/y)	EMAAC (\$/kW-y)	SWMAAC (\$/kW-y)	RTO (\$/kW-y)	WMAAC (\$/kW-y)	DOM (\$/kW-y)
Property Tax	\$0.2	\$0.4	\$0.0	\$0.1	\$0.0	\$0.4	\$0.9	\$0.1	\$0.3	\$0.0
Insurance	\$1.8	\$1.8	\$1.8	\$1.8	\$1.8	\$4.5	\$4.5	\$4.5	\$4.5	\$4.5
O&M Services	\$2.7	\$2.5	\$2.6	\$2.5	\$2.5	\$7.0	\$6.5	\$6.7	\$6.4	\$6.4
Asset Management	\$1.5	\$1.5	\$1.5	\$1.5	\$1.5	\$3.9	\$3.9	\$3.9	\$3.9	\$3.8
Total Fixed O&M Costs	\$6.1	\$6.2	\$5.9	\$5.9	\$5.7	\$15.7	\$15.8	\$15.2	\$15.1	\$14.7

Sources and Notes:

Property tax, insurance, and asset management costs estimated in Section V.
O&M services estimated by Wood Group (2011).

Table 50
Combined-cycle Fixed O&M Costs

	CONE Area					CONE Area				
	1	2	3	4	5	1	2	3	4	5
	EMAAC (\$/m/y)	SWMAAC (\$/m/y)	RTO (\$/m/y)	WMAAC (\$/m/y)	DOM (\$/m/y)	EMAAC (\$/kW-y)	SWMAAC (\$/kW-y)	RTO (\$/kW-y)	WMAAC (\$/kW-y)	DOM (\$/kW-y)
Property Tax	\$0.2	\$0.6	\$0.1	\$0.2	\$0.0	\$0.3	\$0.9	\$0.1	\$0.3	\$0.0
Insurance	\$3.8	\$3.8	\$3.8	\$3.8	\$3.8	\$5.7	\$5.7	\$5.7	\$5.7	\$5.7
O&M Services	\$5.4	\$5.0	\$5.2	\$4.9	\$4.9	\$8.3	\$7.7	\$7.9	\$7.5	\$7.4
Asset Management	\$1.5	\$1.5	\$1.5	\$1.5	\$1.5	\$2.3	\$2.3	\$2.3	\$2.3	\$2.3
Total Fixed O&M Costs	\$10.9	\$10.9	\$10.5	\$10.4	\$10.1	\$16.7	\$16.6	\$16.0	\$15.8	\$15.4

Sources and Notes:

Property tax, insurance, and asset management costs estimated in Section V.
O&M services estimated by Wood Group (2011).

C. LEVELIZED COST OF NEW ENTRY

As discussed in Section IV.A.3 of our concurrently prepared 2011 RPM performance review (“2011 RPM Report”),⁵⁰ translating investment costs into annualized costs for the purpose of setting annual capacity prices requires an assumption about how net revenues are received over time to recover capital and annual fixed costs. Level-nominal cost recovery assumes that net revenues will be constant in nominal terms (*i.e.*, decreasing in real dollar, inflation-adjusted terms) over the 20-year economic life of the plant. A level-real cost recovery path starts at a lower level then increases at the rate of inflation (*i.e.*, constant in real dollar terms). As we explain in our 2011 RPM Report, we find that level real is more consistent with our expected trajectory of operating margins from future capacity and net E&AS revenues.⁵¹

As discussed in the 2011 RPM Report, we recommend that PJM and its stakeholders transition toward using a level-real CONE for MOPR purposes, and we conditionally recommend the same for defining the VRR curve. We recommend maintaining level nominal for the VRR curve until our recommendations to increase the VRR curve cap and calibrate the administrative E&AS offset are adopted. Until then, using the higher level-nominal CONE will help mitigate some of the RPM performance risks we identified.

Table 51 and Table 52 show summaries of our capital costs, annual fixed costs, and levelized CONE estimates for the gas CT and CC reference plants for the 2015/16 delivery year. Our levelization calculation, after accounting for financing costs, depreciation, and IDC, results in a capital charge rate of 11.9% to 12.2% for the CC on a level-real basis (14.8% to 15.0% level nominal) AND 12.9% to 13.1% for the CT on level-real basis (15.8% to 16.0% level nominal).⁵² For comparison, the tables also report the results of the CONE studies used as the basis for PJM’s current parameters after escalating at inflation to a 2015/16 delivery year. We also report the most recent 2014/15 PJM administrative CONE parameters, inflation-adjusted for the 2015/16 delivery year.

⁵⁰ See Pfeifenberger and Newell, *et al.* (2011).

⁵¹ Historically, the average CT cost inflation exceeded CPI by 60 basis points while heatrate improvements saved approximately 50 basis points, for a net growth rate in net operating revenues approximately equal to general inflation. *Id.*

⁵² The capital charge rate is defined as the levelized CONE (without FOM) divided by the overnight capital costs.

The Eastern Mid-Atlantic Area Council (“MAAC”) and Western MAAC regions have the highest CONE estimates at \$112/kW-year (\$307/MW-day) and \$109/kW-year (\$298/MW-day) respectively on a level real basis. The Southwest MAAC and Rest of RTO Areas are somewhat lower, both at \$103/kW-year (\$283/MW-day), primarily because of non-union labor availability in Southwest MAAC and avoidance of dual-fuel capability in the Rest of RTO region. The lowest CONE estimate is in Dominion at \$93/kW-year (\$254/MW-day), which has relatively lower costs because of non-union labor as well as the assumption that the plant can be operated without an SCR.

For comparison, we also present estimates provided by Power Project Management (“PPM”) in their 2008 CONE study. After escalating with inflation to 2015 dollars, the PPM level-nominal estimates are \$19-23/kW-year (\$53-62/MW-day) higher than our estimates in the three CONE Areas reported. The lower capital costs in our study are related primarily to reductions in equipment, materials, and labor costs since 2008, as well as the substantially larger size of the GE 7FA.05 turbine now available compared to the previous GE7FA.03 turbine model. Finally, Table 51 also shows the CONE value PJM has applied in its recent auction for the 2014/15 delivery year, escalated for one year of inflation to represent 2015/16 dollar values.

Table 51
Recommended CONE for Gas CT Plants in 2015/16

CONE Area	Total Plant Capital Cost (\$M)	Net Summer ICAP (MW)	Overnight Cost (\$/kW)	Fixed O&M (\$/kW-y)	After-Tax WACC (%)	Levelized Gross CONE		PJM 2014/15 CT CONE (\$/kW-y)
						Level Real (\$/kW-y)	Level Nominal (\$/kW-y)	
Brattle 2011 Estimate								<i>Escalated at CPI</i>
<i>June 1, 2015 Online Date (2015\$)</i>								<i>for 1 Year</i>
1 Eastern MAAC	\$308.3	390	\$791.2	\$15.7	8.47%	\$112.0	\$134.0	\$142.1
2 Southwest MAAC	\$281.5	390	\$722.6	\$15.8	8.49%	\$103.4	\$123.7	\$131.4
3 Rest of RTO	\$287.3	390	\$737.3	\$15.2	8.46%	\$103.1	\$123.5	\$135.0
4 Western MAAC	\$299.3	390	\$768.2	\$15.1	8.44%	\$108.6	\$130.1	\$131.4
5 Dominion	\$254.7	392	\$649.8	\$14.7	8.54%	\$92.8	\$111.0	\$131.5
Power Project Management, LLC 2008 Update								
<i>June 1, 2008 Online Date (Escalated at CPI from 2008\$ to 2015\$)</i>								
1 Eastern MAAC	\$350.3	336	\$1,042.2	\$17.2	8.07%	n/a	\$154.4	n/a
2 Southwest MAAC	\$322.1	336	\$958.4	\$17.5	8.09%	n/a	\$142.8	n/a
3 Rest of RTO	\$332.5	336	\$989.4	\$15.3	8.11%	n/a	\$146.1	n/a

As shown in Table 52, Eastern MAAC has the highest CC CONE at \$141/kW-year (\$385/MW-day) on a level-real basis, while Rest of RTO and Western MAAC are a bit lower, both at \$135/kW-year (\$370/MW-day). Southwest MAAC and Dominion have the lowest CONE estimates at \$123/kW-year (\$338/MW-day) and \$120/kW-year (\$329/MW-day) respectively, due primarily to non-union labor rates in those locations. Our estimates are \$6 to 12/kW-year (\$17 to 32/MW-day) below the inflation-adjusted Pasteris Energy CONE estimates on a level-nominal basis primarily due to a higher ICAP rating and lower equipment, materials, and labor costs since 2008 relative to inflation. Our higher plant ICAP rating is due to the larger size of the GE 7FA.05 turbine compared to the GE7FA.04 turbine model examined by Pasteris, as well as the greater duct-firing capability in the plant we examined and lower equipment, materials, and labor costs since 2008. Table 52 also shows the CC CONE value PJM has utilized for the 2014/15 delivery year, inflation-adjusted to 2015/16 dollar values.

Table 52
Recommended CONE for Gas CC Plants in 2015/16

CONE Area	Total Plant Capital Cost (\$M)	Net Summer ICAP (MW)	Overnight Cost (\$/kW)	Fixed O&M (\$/kW-y)	After-Tax WACC (%)	Levelized Gross CONE		PJM 2014/15 CC CONE (\$/kW-y)
						Level Real (\$/kW-y)	Level Nominal (\$/kW-y)	
Brattle 2011 Estimate								<i>Escalated at CPI</i>
<i>June 1, 2015 Online Date (2015\$)</i>								<i>for 1 Year</i>
1 Eastern MAAC	\$621.4	656	\$947.8	\$16.7	8.47%	\$140.5	\$168.2	\$179.6
2 Southwest MAAC	\$537.4	656	\$819.6	\$16.6	8.49%	\$123.3	\$147.6	\$158.7
3 Rest of RTO	\$599.0	656	\$913.7	\$16.0	8.46%	\$135.5	\$162.2	\$168.5
4 Western MAAC	\$597.4	656	\$911.2	\$15.8	8.44%	\$135.2	\$161.8	\$158.7
5 Dominion	\$532.9	656	\$812.8	\$15.4	8.54%	\$120.2	\$143.8	\$158.7
Pasteris 2011 Update								
<i>June 1, 2014 Online Date (Escalated at CPI from 2014\$ to 2015\$)</i>								
1 Eastern MAAC	\$710.9	601	\$1,183.1	\$18.5	8.07%	n/a	\$179.6	n/a
2 Southwest MAAC	\$618.7	601	\$1,029.5	\$18.8	8.09%	n/a	\$158.7	n/a
3 Rest of RTO	\$678.0	601	\$1,128.3	\$16.9	8.11%	n/a	\$168.5	n/a

In addition to our recommended CC and CT CONE estimates in the previous tables, we also developed CONE estimates for select sensitivity cases. Table 53 shows a summary of these CONE estimates for alternative configurations of plants we considered. For both the CT and CC plants in the Rest of RTO, we estimated alternative dual-fuel cases. Adding dual-fuel capability adds \$19 million in costs for the CT and \$18 million for the CC. For the CT we also developed sensitivity estimates with an SCR in Dominion (increasing costs by \$24 million) and without an SCR in the other CONE Areas (decreasing costs by \$23-27 million).

Table 53
Additional Sensitivity Case CONE Estimates for 2015/16

Cone Area	Total Plant Capital Cost (\$M)	Net Summer ICAP (MW)	Overnight Cost (\$/kW)	Fixed O&M (\$/kW-y)	After-Tax WACC (%)	Levelized Gross CONE	
						Level Real (\$/kW-y)	Level Nominal (\$/kW-y)
Gas CT - No SCR - Dual Fuel							
1 Eastern MAAC	\$281.1	392	\$717.0	\$15.6	8.47%	\$102.9	\$123.2
2 Southwest MAAC	\$258.1	392	\$658.4	\$15.7	8.49%	\$95.6	\$114.4
3 Rest of RTO	\$279.2	392	\$712.1	\$15.1	8.46%	\$101.7	\$121.7
4 Western MAAC	\$272.4	392	\$694.8	\$15.0	8.44%	\$99.7	\$119.3
Gas CT - With SCR - Dual Fuel							
3 Rest of RTO	\$306.2	390	\$786.0	\$15.2	8.46%	\$110.7	\$132.5
5 Dominion	\$279.0	390	\$716.1	\$14.7	8.54%	\$100.8	\$120.6
Gas CT - No SCR - Single Fuel							
3 Rest of RTO	\$260.6	392	\$664.9	\$15.1	8.46%	\$94.5	\$113.2
Gas CC - With SCR - Dual Fuel							
3 Rest of RTO	\$616.7	656	\$940.6	\$16.0	8.46%	\$138.9	\$166.3

BIBLIOGRAPHY

- Bay Area Air Quality Management District (2010) Authority to Construct for Permit Application No. 18404, Plant No. 19169. August 31, 2010. Retrieved from http://www.baaqmd.gov/~media/Files/Engineering/Public%20Notices/2010/18404/NOF_D_Authority%20to%20Construct%20083110/083110_Authority_to_Construct.ashx?la=en
- Bayonne Delivery Lateral Project (2009). Docket No. CP09, Application For Certificate of Public Convenience and Necessity. Filed: May 22, 2009.
- Bayonne Permits Obtained (2011). Copies of Permits Obtained. February 14, 2011. Retrieved from <http://documents.dps.state.ny.us/public/Common/ViewDoc.aspx?DocRefId={101CD9F9-8CF5-405A-9F47-3C70BAC4A7EA}>
- Bloomberg (2011). Bloomberg Professional Service. Data downloaded over January - August, 2011.
- Blue Chip Economic Indicators (2011). Blue Chip Economic Indicators, Top Analysts' Forecasts of the U.S. Economic Outlook for the Year Ahead. March 10, 2011. New York: Aspen Publishers.
- Brealey, Richard, Stuart C. Myers, and Franklin Allen (2011). *Principles of Corporate Finance*. New York: McGraw-Hill/Irwin.
- CH2M HILL Engineers, Inc (2011). Cost and performance estimates provided for this study, January – August, 2011.
- Cohen, Jonathan, and Greg Gordon (2010a). Morgan Stanley Analyst Report NRG Energy, Inc., Published 10/6/2010.
- Cohen, Jonathan, and Greg Gordon (2010b). Morgan Stanley Analyst Report Calpine Corp., Inc., Published 10/6/2010.
- Columbia Gas (2001). Docket No. CP01-439-000, Abbreviated Application of Columbia Gas Transmission Corporation for a Certificate of Public Convenience and Necessity. Filed 8/31/2001.
- Delta Permits Obtained (2005). Emissions Permits Obtained. July 15, 2005. Retrieved from <http://www.pabulletin.com/secure/data/vol35/35-44/1986c.html>
- Dimson, Elroy, Paul Marsh, and Mike Stauton (2010). *Credit Suisse Global Investment Returns Sourcebook 2010*. Zurich: Credit Suisse Research Institute.
- Duke Energy Corporation (2011). Duke Energy Corporation Form S-4 Registration Statement, Filed with SEC on 3/17/2011.
- Duke Energy Indiana, Inc (2010). Application of Duke Energy Indiana, Inc. For Certificate of Public Convenience and Necessity and Blanket Certificate. Filed November 10, 2010.

Delta Lateral Project (2009). Docket No. CP09, Applicatoin For Certificate of Public Convenience and Necessity. Filed: April 30, 2009.

Dynergy Inc (2010). Dynergy Inc. Schedule 14A Definitive Proxy Statement, Filed with SEC on 10/4/2010.

Environmental Protection Agency (2011a). Nonattainment Status for Each County by Year by State. Retreived from http://www.epa.gov/oaqps001/greenbk/anay_ak.html

Environmental Protection Agency (2011b). RACT/BACT/LAER Clearinghouse Basic Information. Retrieved August 20, 2011 from <http://epa.gov/ttn/catc/rblc/htm/welcome.html>

Environmental Protection Agency (2011c). Regulatory Actions: Ozone Standards. Retrieved August 20, 2011 from <http://www.epa.gov/air/ozonepollution/actions.html#dec10s>

Environmental Protection Agency (2011d). Cross-State Air Pollution Rule (CSAPR). Retrieved August 20, 2011 from <http://www.epa.gov/airtransport/>

Environmental Protection Agency (2011e). Nonattainment NSR Basic Information. Retreived August 20, 2011 from <http://www.epa.gov/nsr/naa.html>

Evolution Markets (2011). Emission Reduction Credit Ratios. Retreived July 15, 2011 from http://new.evomarkets.com/index.php?page=Emissions_Markets-Markets-Emission_Reduction_Credits

FirstEnergy Corp. and Allegheny Energy (2010). Form S-4 for Proposded Merger Between FirstEnergy Corp. and Allegheny Energy, Filed with SEC on 7/16/2010.

Gas Turbine World (2010). *Gas Turbine World 2010 GTW Handbook*. Fairfield, CT: Pequot Publishing Inc.

General Electric (2009). *The 7FA Gas Turbine: "A Classic Reimagined"*. GE Gas Turbine Technology Symposium. Greenville, SC. Russ Martin and Jim Donohue. October 2009.

General Electric (2011a). About the New 7FA. Retrieved from <http://www.ge-7fa.com/businesses/ge-7fa/en/about-7FA.html>

GenOn (2010). Mirant and RRI Energy Complete Merger. Assessed 8/1/2011, from http://www.genon.com/docs/GenOn%20Energy%20Day%20One%20PR_final.pdf

Google Maps (2011). Map of United States, Retrieved from <http://maps.google.com/>

Gulfstream (2006). Docket No. CP07-51-000, Abbreviated Application for a Certificate of Public Convenience and Necessity and for Related Authorizations. Filed 12/22/2006.

Ibbotson (2011). *Ibbotson SBBi 2011 Valuation Yearbook*, Chicago: Morningstar.

Illinois Assessment Records (2011). Will County Assessment Records Search. Retrieved from http://www.willcountysoa.com/search_address.aspx

Illinois Department of Revenue (2011). The Illinois Property Tax System: A general guide to the local property tax cycle. Retrieved from <http://tax.illinois.gov/publications/localgovernment/ptax1004.pdf>

IRS (2010a). 2010 Instructions for Form 1120, U.S. Corporation Income Tax Return. Retrieved from <http://www.irs.gov/pub/irs-pdf/i1120.pdf>

IRS (2010b). Publication 946, How to Depreciate Property. Retrieved from <http://www.irs.gov/pub/irs-pdf/p946.pdf>

KPMG (2010). KPMG's Corporate and Indirect Tax Survey 2010. Retrieved from <http://www.kpmg.com/GE/en/IssuesAndInsights/ArticlesPublications/Documents/Corp-and-Indirect-Tax-Oct12-2010.pdf>

LoopNet (2011). Commercial Real Estate Listings. Retrieved from <http://www.loopnet.com/>

MarkWest (2007). Docket No. CP08-1-000, Prior Notice Request of MarkWest New Mexico, L.P. For Authorization to Construct and Operate Mainline Natural Gas Facilities. Filed 10/1/2007.

Maryland Assessment Records (2011). Charles County Assessment Records Search. Retrieved from http://sdatcert3.resiusa.org/rp_rewrite/.

Mirant Corp. And RRI Energy (2010). Schedule 14A for Proposed Merger Between Mirant Corp. and RRI Energy, Filed with SEC on 9/14/2010.

New Jersey Assessment Records (2011). Middlesex County Assessment Records Search. Retrieved from http://tax1.co.monmouth.nj.us/cgi-bin/prc6.cgi?&ms_user=monm&passwd=data&srch_type=0&adv=0&out_type=0&district=1200;

New Jersey State Department of Environmental Protection (2011). Control and Prohibition of Air Pollution from Oxides of Nitrogen, Title 7, Chapter 27. Retrieved from <http://www.nj.gov/dep/aqm/Sub19.pdf>

Ozone Transport Commission (2011). What is the Ozone Transport Commission? Retrieved from <http://www.otcair.org/about.asp>

Ozone Transport Commission (2010). Control of Natural Gas and Oil Fired HEDD Turbine NOx Emissions, November 2010. Retrieved from <http://www.google.com/url?sa=t&source=web&cd=2&ved=0CCAQFjAB&url=http%3A%2F%2Fwww.otcair.org%2Fupload%2FDocuments%2FMeeting%2520Materials%2FOTC%2520Model%2520Rule%2520-%2520HEDD%2520Turbines%2520%2809-10-10%29.doc&rct=j&q=otcair.org%20Control%20of%20Natural%20Gas%20and%20Oil%20Fired%20HEDD%20Turbine%20NOx%20Emissions&ei=1P8VTofXCNOtgQftpMkC&usg=AFQjCNF0gYsk-Nsk-g3UF3VKmTiyYyEYTw&sig2=rq3jvlR1fiUtEIYcTvKezg&cad=rja>

- Pasteris Energy (2011). Cost of New Entry Combined Cycle Power Plant Revenue Requirements for PJM Interconnection, LLC. Filed February 11, 2011. Retrieved from <http://www.pjm.com/~media/documents/ferc/2011-filings/20110211-er11-2875-000.ashx>
- Pennsylvania Assessment Records (2011). Northampton County Assessment Records Search. Retrieved from <http://www.ncpub.org/Search/Disclaimer2.aspx?FromUrl=../Search/GenericSearch.aspx?mode=address>
- Pfeifenberger, Johannes, Kathleen Spees, and Adam Schumacher. (2009). "A Comparison of PJM's RPM with Alternative Energy and Capacity Market Designs." Prepared for PJM Interconnection, Inc. September 2009. Retrieved from <http://www.brattle.com/documents/UploadLibrary/Upload807.pdf>
- Pfeifenberger, Johannes, Samuel Newell, Kathleen Spees, Attila Hajos, and Kamen Madjarov (2011) *Second Performance Assessment of PJM's Reliability Pricing Model: Market Results 2007/08 through 2014/15*. Prepared for PJM Interconnection, LLC. August 26, 2011. Available: www.brattle.com
- PJM Interconnection, L.L.C (2008). 2008 High Voltage Transmission Infrastructure Map.
- PJM Interconnection, L.L.C (2011a). Data provided for this study over January - August, 2011.
- PJM Interconnection, L.L.C (2011b). Open Access Transmission Tariff. Accessed 7/1/2011 from <http://www.pjm.com/~media/documents/agreements/tariff.ashx>
- PJM Interconnection, L.L.C (2011c). Map of PJM Territory Served. Accessed 8/1/2011 from <http://pjm.com/about-pjm/how-we-operate/~media/about-pjm/pjm-zones.ashx>
- PJM Interconnection, L.L.C (2011d). FERC Settlement Filing. Filed 2/9/2009. Retrieved from <http://www.pjm-miso.com/documents/ferc/documents/2009/20090209-er05-1410-000.pdf>
- Platts (2011). North American Natural Gas Supply Map. McGraw-Hill Companies, 2011.
- Power Project Management (2008). 2008 Update of Cost of New Entry Combustion Turbine Power Plant Revenue Requirements for PJM Interconnection, LLC. Retrieved from <http://www.pjm-miso.com/documents/ferc/documents/2008/20081212-er09-xxx-000.pdf>
- Federal Reserve Bank of St. Louis (2011). Implicit Price Deflator. Accessed 8/1/2011, from <http://research.stlouisfed.org/fred2/series/GDPDEF?&cid=18>.
- Standard & Poor's (2011). Credit Ratings Definitions & FAQs. Accessed 4/27/2011 from <http://www.standardandpoors.com/ratings/definitions-and-faqs/en/us>
- Tax Foundation (2011). State Corporate Income Tax Rates, 2000-2011. Accessed 4/27/2011 from <http://www.taxfoundation.org/taxdata/show/230.html>

Texas Eastern Transmission Co (2007). Docket No. CP07-411-000, Abbreviated Application for a Certificate of Public Convenience and Necessity. Filed 6/29/2007.

Ventyx (2011). Energy Velocity Suite. Data Downloaded over January - August, 2011.

Virginia Assessment Records (2011). Charles County Assessment Records Search. Retrieved from <http://www.fauquiercounty.gov/government/departments/commrev/index.cfm?action=realstatetaxform>

Wood Group (2011). Cost and performance estimates provided for this study, January – August, 2011.

York Energy Center Permits Obtained (2005). Emissions Permits Obtained. July 15, 2005. Retrieved from <http://www.pabulletin.com/secure/data/vol35/35-44/1986c.html>

LIST OF ACRONYMS

ATWACC	After-Tax Weighted-Average Cost Of Capital
CAPM	Capital Asset Pricing Model
BACT	Best Available Control Technology
BOP	Balance of Plant
CC	Combined Cycle
CONE	Cost of New Entry
CPI	Consumer Price Index
CSAPR	Cross-State Air Pollution Rule
CT	Combustion Turbine
E&AS	Energy and Ancillary Services
EPC	Engineering, Procurement, and Construction
FERC	Federal Energy Regulatory Commission
FFS	Factored Fired Starts
FFH	Factored Fired Hours
fka	Formerly Known As
FOM	Fixed Operation and Maintenance
GSU	Generator Step-Up
HHV	Higher Heating Value
HRSG	Heat Recovery Steam Generator
ICAP	Installed Capacity
IDC	Interest During Construction
LAER	Lowest Achievable Emissions Rate
LHV	Lower Heating Value
LTSA	Long-Term Service Agreement
MAAC	Mid-Atlantic Area Council
MACRS	Modified Accelerated Cost Recovery System
MOPR	Minimum Offer Price Rule
MW	Megawatts
MWh	Megawatt-Hours
NAAQS	National Ambient Air Quality Standards
NNSR	Non-Attainment New Source Review
NSR	New Source Review

OATT	Open Access Transmission Tariff
O&M	Operation and Maintenance
OFR	Owner-Furnished Equipment
PJM	PJM Interconnection, LLC
PPA	Power Purchase Agreement
PPM	Power Project Management
PSD	Prevention of Significant Deterioration
RPM	Reliability Pricing Model
SCR	Selective Catalytic Reduction
VOM	Variable Operation and Maintenance
VRR	Variable Resource Requirement

APPENDIX A. CH2M HILL SIMPLE-CYCLE COST ESTIMATES

CH2M HILL's detailed engineering cost estimates for plant proper costs including both EPC contractor costs and owner-furnished equipment costs are contained in this appendix for each simple-cycle plant configuration examined. A summary report describing detailed plant specifications and summary cost results for each CT configuration in each CONE Area is contained in CH2M HILL's summary report in Appendix A.1. Plant layout drawings, project schedules, cost estimate details, and cash flow schedules were also provided for each CT location and configuration. Appendices A.2 through A.5 contain this detailed supporting information for one of the CONE Area 1 plant configuration, which is a dual-fuel plant with an SCR.

APPENDIX A.1. SIMPLE-CYCLE PLANT PROPER COST ESTIMATE REPORT

APPENDIX A.2. LAYOUT DRAWING FOR DUAL-FUEL CT WITH SCR

APPENDIX A.3. PROJECT SCHEDULE FOR DUAL-FUEL CT WITH SCR

APPENDIX A.4. COST DETAIL FOR CT WITH SCR IN CONE AREA 1

APPENDIX A.5. CASH FLOW SCHEDULE FOR CT WITH SCR IN CONE AREA 1

APPENDIX A.1. SIMPLE-CYCLE PLANT PROPER COST ESTIMATE REPORT



Simple Cycle Cost Estimate 2 x 0 GE 7FA Reference Plant

Brattle Group PJM Estimating Support

Prepared By CH2M HILL
Project No. 421147
Rev. C
August 2011



TABLE OF CONTENTS

1.0	Executive Summary	2
2.0	Development Approach.....	4
	2.1 Estimating Process.....	4
	2.2 Owner Costs.....	5
	2.3 EPC Cost Estimate.....	6
3.0	Plant Scope.....	10
	3.1 General Description	10
	3.2 Owner Furnished Equipment.....	10
	3.3 EPC Scope.....	12
4.0	Power Plant General Arrangement	14
5.0	Project Schedule	22
6.0	Capital Cost Estimates.....	16
7.0	Cash Flow.....	17

Revision	Description	Date
A	Issued for Review	July 1, 2011
B	Comments Incorporated	August 2, 2011
C	Final	August 23, 2011

1.0 Executive Summary

CH2M HILL Engineers, Inc. was engaged by the Brattle Group, Inc to provide capital cost estimates for gas fuel only and dual fuel (oil & natural gas) GE Frame 7FA.05 gas turbine simple cycle power plants at multiple sites, each capable of generating approximately 420 MW. The plant configurations each will consist of two (2) GE Frame 7FA.05 combustion turbine generators (CTGs), and all necessary Balance of Plant (BOP) equipment. Each plant will be capable of producing approximately 420 MW. Cost estimates were provide for simple cycle plants both with and without SCR in the combustion turbine exhausts.

Dual Fuel Combustion Turbines

As a basis for the dual fuel combustion turbine estimates CH2M HILL developed the following information:

- Capital costs for five (5) geographical areas (New Jersey, Maryland, Illinois, Pennsylvania, and Virginia)
- A General Arrangement drawing for a representative simple cycle power plant
- A Level One Project schedule
- A basic monthly cash flow tabulation

The capital cost estimates for the dual fuel combustion turbine (without SCRs) alternative for each geographical area are included in the table below. The details of the cost breakdown for each location are included in Section 6. Note these costs are exclusive of the change in cash flows at assignment of OFE and NTP to EPC contractor.

No SCR

Geographical Area	Labor Type	EPC Costs \$	Owner Costs \$	Total Installed Capital Cost - \$
New Jersey	Union	126,012,137	102,043,367	228,055,504
Maryland	Non-Union	104,153,617	100,742,702	204,896,319
Illinois	Union	123,709,817	102,042,993	225,752,810
Pennsylvania	Union	118,716,860	100,752,855	219,469,715
Virginia	Non-Union	103,989,281	99,452,320	203,441,601

The capital cost estimates for the dual fuel combustion turbine with SCR alternative for each geographical area are included in the table below. The details of the cost breakdown for each location are included in Section 6. Note these costs are exclusive of the change in cash flows at assignment of OFE and NTP to EPC contractor.

With SCR

Geographical Area	Labor Type	EPC Costs \$	Owner Costs \$	Total Installed Capital Cost - \$
New Jersey	Union	130,552,074	124,864,072	255,416,146
Maryland	Non-Union	104,991,119	123,371,532	228,362,651
Illinois	Union	128,276,002	124,863,686	253,139,688
Pennsylvania	Union	123,045,308	123,384,930	246,430,238
Virginia	Non-Union	104,760,187	121,893,014	226,653,201

Gas Fuel Only Combustion Turbines

As a basis for the gas fuel only combustion turbine estimate CH2M HILL developed the following information:

- Capital cost for the Will County, Illinois location
- A General Arrangement drawing for a representative simple cycle power plant
- A Level One Project schedule
- A basic monthly cash flow tabulation

The capital cost estimate for the natural gas fuel combustion turbine without SCR for Will County, Illinois is included in the table below. The detail of the cost breakdown for this location is included in Section 6. Note these costs are exclusive of the change in cash flows at assignment of OFE and NTP to EPC contractor.

No SCR

Geographical Area	Labor Type	EPC Costs \$	Owner Costs \$	Total Installed Capital Cost - \$
Illinois	Union	109,437,632	98,513,712	207,951,344

The capital cost estimate for the gas fuel only combustion turbine with SCR for Will County, Illinois is included in the table below. The detail of the cost breakdown for this location is included in Section 6. Note these costs are exclusive of the change in cash flows at assignment of OFE and NTP to EPC contractor.

With SCR

Geographical Area	Labor Type	EPC Costs \$	Owner Costs \$	Total Installed Capital Cost - \$
Illinois	Union	113,572,247	121,323,142	234,895,389

2.0 Development Approach

2.1 Estimating Process

For the development of the capital cost estimate, CH2M HILL utilized our Power Plant Indicative Cost Estimating Methodology which is based upon the plant specific configuration, location specific productivity and labor cost factors, and our extensive current cost data base for equipment and material. These factors are processed using our proprietary Indicative Estimating Software Model to produce a detailed analysis of the cost elements for the project that are then compared to recently completed similar projects.

Project Configurations

CH2M HILL's experience with various plant configurations is extensive. The combustion turbines shown in the table below have been designed and installed in combined cycle, simple cycle and cogeneration modes.

- 1 X LMS 100 simple cycle
- 2 X F-class simple cycle
- 4 X LM 6000 simple cycle
- 12 X FT-8 Twin Pack simple cycle
- 1 X 1 F-class combined cycle
- 2 X 1 F-class combined cycle
- 3 X 1 E-class combined cycle

CH2M HILL's estimating team retains standard plant layout configurations that have been imported into the estimating data base for use in this study. The design basis for this study is a 2 x 0 - 7F class simple cycle plant, the details for which are defined in Sections 3.0 - Plant Scope and Section 4.0 - General Arrangement of this report.

Variability by Location

The US construction industry has the most variability in productivity and execution strategy by location than any other country in the world. Project execution ranges from strong union locations such as New York City, Chicago, San Francisco and St. Louis to lower cost, merit shop locations such as the Gulf Coast and Southeast US. CH2M HILL's historical database tracks and updates labor productivity by location. CH2M HILL's "base" productivity location is the Gulf Coast, like many national contractors. At that location, the base productivity for each discipline trade is considered a 1.0 productivity factor and is considered the most efficient location to perform work based on worker skills and efficiency. That 1.0 productivity factor is then adjusted to reflect union labor, local labor rules and other historical data.

Variability of Estimates for Material and Equipment

Certain material and equipment costs are more volatile in the heavy industrial market than others. As examples, high temperature- high pressure pipe, electrical transformers and copper wire are high in demand in the oil & gas market as well as the power market. When both

industries are busy, costs increase dramatically due to not only material and manufacturing costs, but also due to greater demand than supply. Market conditions sometimes make it nearly impossible to assess with any certainty the proper amount of escalation to apply to some materials and equipment. This is compounded by the extended time from estimate development to project implementation. CH2M HILL's constant activity in bidding and procuring material and equipment provides more accurate costs that reflect current market conditions than available by other means.

CH2M HILL's Indicative Estimating Software Model

CH2M HILL has taken over 20 years of data from our involvement in the power industry and developed an indicative database to aid in estimating future projects. The "Power Indicative Estimating Program" derives project costs based on information that is input on various worksheets within the program from a series of inputs, multiple logic functions and iterations, and a preliminary Indicative Estimate is produced which can be reviewed and modified as necessary.

Power Indicative Estimating Program Output

Once a project configuration, location, schedule and execution model is defined, the indicative estimator works with a Power Project Engineer to reflect other project properties unique to the project. The estimator inputs the specific project data into the model and then reviews with experienced construction managers and engineers to confirm alignment. The program produces an estimating basis and a series of outputs. Some of these outputs include:

- Quantities of concrete, structural steel, pipe, conduit, cable and insulation
- Equipment required by system
- Work-hours for labor by discipline
- Engineering hours
- Construction supervision hours
- Startup and testing hours
- Indirect labor and equipment

The program allows the estimator to input the latest labor rates, productivity, which is then tabulated in the program to develop the final cost of the plant. The results of these analyses are contained in Section 6.0 of this report.

2.2 Owner Cost Estimates

Pricing for the Combustion Turbine Generators (CTGs), is based on GE Power Island information obtained from similar plants CH2M HILL has constructed and proposed. Note that GE's scope includes the Continuous Emissions Monitoring System (CEMS), Packaged Electrical and Electronic Control Cab (PEECC), the Plant Distributed Control System (DCS) and the CTGs auxiliary equipment. For plants with SCR, budgetary quotes were received from major SCR system suppliers and one representative design was used for pricing data.

These components (Owner Furnished Equipment or OFE) are procured by the Owner at project start, prior to EPC contract NTP. They are assigned to the EPC contractor at that time. Estimates of Owner costs that are in addition to the EPC contract cost are tabulated in Section 6.0.

2.3 EPC Cost Estimate

Pricing for the major Balance of Plant equipment including the generator step-up transformers were obtained from actual pricing and budgetary quotes received from vendors for similar recent projects and proposals. The plant construction cost estimates were developed based on data from recent EPC projects. Labor rates and productivity factors for the following five (5) geographical areas were verified and used to develop the direct and indirect costs.

- 1) Middlesex County, New Jersey
- 2) Charles County, Maryland
- 3) Will County, Illinois
- 4) Northampton County, Pennsylvania
- 5) Fauquier County, Virginia

The construction cost estimates are based on direct labor hire (concrete, steel, piping, electrical and instrumentation) and specialty subcontract union (locations 1, 3, and 4) and merit shop craft labor (locations 2 and 5). Quantities for bulks were determined from plants similar in size and configuration. Historical data was utilized to provide an overall parametric check of account values of the completed estimate.

Labor

Locations 1, 3, and 4: Union craft labor rates were determined from prevailing wages for the area. Rates were built-up including the base rate, fringes and legalities. The estimate is based on a 50 hour craft work week. A labor factor of 1.1 was applied to the CSA accounts, 1.3 for the piping accounts, and 1.2 on all other accounts and based on various factors including location, working in an existing facility, congestion, local labor conditions, weather and schedule.

Locations 2 and 5: Merit shop craft labor rates were determined from prevailing wages for the area. Rates were built-up including the base rate, fringes and legalities. The estimate is based on a 50 hour craft work week. A labor factor of 1.0 was applied to all accounts based on various factors. A \$50 per day per diem has been included.

Escalation

The cost estimates are provided in June 2011 dollars and escalation was included based on the following schedules.

- Craft labor was escalated at 4.0% for 2011 and beyond.
- Engineered equipment and bulk materials were escalated at 6% for 2011 and beyond.
- Professional labor and construction indirect expenses were escalated at 3% for 2011 and 4% for 2012 and beyond.
- Specialty subcontracts were escalated at 5% for 2011 and beyond.

Contingency & Gross Margin

Contingency was included at:

- 5% for Professional Labor, Material and Construction Equipment
- 7% for Craft Labor
- 6% for Specialty Subcontracts
- 2% for the CTGs and STG
- 3% for the HRSGs
- 3% for Engineered Equipment

A gross margin of 10% was applied with 5% assignment fee applied to the Owner Furnished Equipment.

Project Indirects

Project indirects include:

- Builders Risk insurance
- General and excess liability insurance
- Performance and payment bonds
- Construction permits
- Sales tax (not including OFE) to roll up through markups then taken out at bottom line
- Letter of credit in lieu of retention
- Warranty
- Bonus pool

Scope - Inclusions

- Structural and civil works
- Mechanical, electrical, and control equipment
- Electrical Power Distribution Center (pre-assembled & tested)
- Heavy haul (allowance)
- Operator training
- O&M manuals
- Escalation
- Bulks including piping and instrumentation
- Contractor's construction supervision
- Temporary facilities
- Construction equipment, small tools and consumables
- Start-up spare parts and start-up craft labor
- Construction permits allowance (\$100,000)
- First fills
- Insurances
- Gross margin
- 5% Letter of Credit in lieu of retention

- Construction power, water and natural gas consumption
- Performance and Payment Bond
- Builders All Risk Insurance (costs broken out from EPC estimate for reference – see Estimate Basis Section 17.0)

Scope - Exclusions

- Soils remediation, moving of underground appurtenances or piping
- Dewatering except for runoff during construction
- Wetland mitigation
- Fuel gas compression
- Noise mitigation measures or study (unless otherwise noted)
- Piling
- Geotechnical investigation and survey (shown separately from EPC estimate as an Owners cost)
- Sales Tax (shown separately from EPC estimates as an Owners cost)
- Permitting/ Environmental permits (shown separately from EPC estimates as an Owners cost)
- Fuel oil and natural gas consumption during startup (shown separately from EPC estimate as an Owners cost)
- Switchyard

Scope - Assumptions & Clarifications

- Assumes flat, level and cleared site.
- Assumes free and clear access to work areas.
- This site does not contain any EPA defined hazardous or toxic wastes or any archeological finds that would interrupt or delay the project.
- Spread footings are assumed for all equipment.
- All excavated material is suitable for backfill/compaction.
- Rock excavation is not required.
- Temporary power and water will be available at site boundary as required to support construction at no cost to Contractor.
- An ample supply of skilled craft is available to the site.
- TA services are owner provided as part of their equipment supply.
- Craft bussing is not required.
- Ample space (provided by owner) for craft parking, temporary facilities, laydown and storage is available adjacent to site.
- Field Erected Storage Tanks are carbon steel with internal high build epoxy coatings.
- Access road modifications and improvements (beyond the site boundary battery limit) will be performed by others.
- Roads for heavy haul are suitable for transportation and contain no obstructions for delivery of heavy/oversized equipment.
- Heavy haul is assumed to be from a rail siding within one mile of the plant to setting on foundations.
- Equipment is supplied with manufacturer's standard finish paint.

- Natural gas is delivered at an adequate pressure and no gas compression is required.
- Gas metering station is by others.
- The electrical equipment will be housed in pre-fabricated building.
- The electrical scope concludes at the high side of the Generator Step-up (GSU) transformers. Transmission line and substation costs are by others.
- Heat tracing has not been included for large, above ground process piping where system pumps can be operated to prevent freezing, or where the system can be drained during extended cold weather outages.
- Rental demineralized water treatment trailers.

3.0 Plant Scope

3.1 General Description

The proposed simple cycle power plant has a nominal generating capacity of 420MW at 59 °F outdoor ambient temperature when operating on gas fuel. The major components of the project include two (2) GE Frame 7FA.05 Combustion Turbine Generators (CTGs), air pollution controls and associated auxiliary and control systems. The CTGs will be equipped with inlet evaporative coolers to increase power output at high ambient temperature. The plant (dual fuel CT option) will operate both on natural gas and distillate fuel oil. The CTGs will be equipped with dry-low NOx combustors (gas fuel operation) to reduce NOx emissions. The CTGs will be equipped with water injection for NOx control when operating on distillate fuel (dual fuel option).

The termination points for the power facility are at the battery limits of the facility and include the following:

- High Pressure natural gas supply downstream of the gas metering station (by others) at the power facility boundary
- Water from the municipal water supply at the power facility boundary
- Waste to the municipal sewer at the power facility boundary
- Electrical connection is at the high side of the generator step-up transformers

The facility is assumed to be located on a Greenfield site. There will be one building included in the plant layout: an integrated administration/control room/warehouse/maintenance building. Buildings are of pre-fabricated construction. Layout of the plant shall be in accordance with the General Arrangement drawing included in Section 4.0.

General performance parameters are tabulated below. Predicted emissions data is also provided based on generic data for CTG and SCR performance using estimated stack emissions concentrations and rates.

General Performance

Simple Cycle Plant With SCR/CO

	GAS			
	Evaporative Cooling			
	1x0	2x0	1x0	2x0
Plant configuration	1x0	2x0	1x0	2x0
CTG Load Point	100%	100%	100%	100%
Ambient Temperature, oF	59	59	92	92
Relative Humidity, %	60	60	53	53
Evaporative Cooling	ON	ON	ON	ON
Fuel Heating Value, Btu/Lb (LHV)	21,515	21,515	21,515	21,515

CT Generators terminal power, kW	213,280	426,560	198,989	397,978
Total Fuel Input, Btu/Hr	1,902,884,160	3,805,768,320	1,814,381,700	3,628,763,400
Gross Plant Heat Rate, Btu/kWH (LHV)	8,922	8,922	9,118	9,118
Plant Auxiliary Loads, kW	4,399	8,798	4,185	8,370
Net Plant Power, kW	208,881	417,762	194,804	389,608
Net Plant Heat Rate, Btu/kWH (LHV)	9,110	9,110	9,314	9,314

	FUEL OIL			
	Evaporative Cooling			
	1x0	2x0	1x0	2x0
Plant configuration	1x0	2x0	1x0	2x0
CTG Load Point	100%	100%	100%	100%
Ambient Temperature, oF	59	59	92	92
Relative Humidity, %	60	60	53	53
Evaporative Cooling	ON	ON	ON	ON
Fuel Heating Value, Btu/Lb (LHV)	18,300	18,300	18,300	18,300

CT Generators terminal power, kW	218,780	437,560	211,867	423,734
Total Fuel Input, Btu/Hr	2,102,700,000	4,205,400,000	2,058,287,900	4,116,575,800
Gross Plant Heat Rate, Btu/kWH (LHV)	9,611	9,611	9,715	9,715
Plant Auxiliary Loads, kW	4,482	8,963	4,378	8,756
Net Plant Power, kW	214,298	428,597	207,489	414,978
Net Plant Heat Rate, Btu/kWH (LHV)	9,812	9,812	9,920	9,920

Simple Cycle Plant No SCR/CO

	GAS			
	Evaporative Cooling			
Plant configuration	1x0	2x0	1x0	2x0
CTG Load Point	100%	100%	100%	100%
Ambient Temperature, oF	59	59	92	92
Relative Humidity, %	60	60	53	53
Evaporative Cooling	ON	ON	ON	ON
Fuel Heating Value, Btu/Lb (LHV)	21,515	21,515	21,515	21,515

CT Generators terminal power, kW	213,280	426,560	198,989	397,978
Total Fuel Input, Btu/Hr	1,902,884,160	3,805,768,320	1,814,381,700	3,628,763,400
Gross Plant Heat Rate, Btu/kWH (LHV)	8,922	8,922	9,118	9,118
Plant Auxiliary Loads, kW	3,199	6,398	2,985	5,970
Net Plant Power, kW	210,081	420,162	196,004	392,008
Net Plant Heat Rate, Btu/kWH (LHV)	9,058	9,058	9,257	9,257

	FUEL OIL			
	Evaporative Cooling			
Plant configuration	1x0	2x0	1x0	2x0
CTG Load Point	100%	100%	100%	100%
Ambient Temperature, oF	59	59	92	92
Relative Humidity, %	60	60	53	53
Evaporative Cooling	ON	ON	ON	ON
Fuel Heating Value, Btu/Lb (LHV)	18,300	18,300	18,300	18,300

CT Generators terminal power, kW	218,780	437,560	211,867	423,734
Total Fuel Input, Btu/Hr	2,102,700,000	4,205,400,000	2,058,287,900	4,116,575,800
Gross Plant Heat Rate, Btu/kWH (LHV)	9,611	9,611	9,715	9,715
Plant Auxiliary Loads, kW	3,282	6,563	3,178	6,356
Net Plant Power, kW	215,498	430,997	208,689	417,378
Net Plant Heat Rate, Btu/kWH (LHV)	9,757	9,757	9,863	9,863

Predicted Emissions

GE 7FA.05						
OPERATING CONDITION		N. Gas	Fuel Oil			
Ambient DBT Deg F		59	59			
Relative Humidity %		60	60			
Gas Turbine Unit Exhaust						
Flow Rate	lbs/hr	4,132,000	4,151,000			
Temperature	deg F	1113	1147			
Argon	% VOL	0.88	0.84			
Nitrogen	% VOL	74.18	70.7			
Oxygen	% VOL	12.26	10.68			
Carbon Dioxide	% VOL	3.85	5.74			
Water	% VOL	8.83	12.04			
Gas turbine Emissions						
NOx corrected to 15% O2	ppmvd	9	42			
NOx as NO2	lbs/hr	69	370			
CO corrected to 15% O2	ppmvd	9	20			
CO	lbs/hr	33	72			
UHC	ppmvd	7	7			
UHC	lbs/hr	16	16			
PM10 particulates	lbs/hr	9	17			

With SCR

	Gas CT	
	N.G (ppmvd)	F.O. (ppmvd)
NO _x	2	5
VOC	5	5
CO	5	11
PM _{2.5}	--	--
SO ₂	Note A	Note B

Gas CT		
	N.G (lb/hr)	F.O. (lb/hr)
NO _x	15.6	44.5
VOC	13.5	15.5
CO	23.7	59.5
PM _{2.5}	9	17
SO ₂	2.7	3.4

Gas CT		
	N.G (lb/MMBtu)	F.O. (lb/MMBtu)
NO _x	8.20E-03	2.12E-02
VOC	7.09E-03	7.37E-03
CO	1.25E-02	2.83E-02
PM _{2.5}	4.73E-03	8.08E-03
SO ₂	1.43E-03	1.64E-03

	Gas CT 1X0	
	Natural Gas	Fuel oil
Heat input (MMBtu/hr)	1,903	2,103
Fuel Heating Value Btu/Lb (LHV)	21,515	18,300

Notes

A - 0.5 grains/100 scf

B - 15 ppm on a mass basis for fuel oil

c - Assumed heating value of natural gas of 1000 Btu/scf

3.2 Owner Furnished Equipment (OFE)

The following paragraphs describe the equipment for which the Owner is responsible to purchase.

Combustion Turbine Generators (Power Island Scope) - The combustion turbine generators (CTG's) operate to produce electrical power and waste heat. The plant will include two (2) General Electric 7FA.05 combustion turbine-generators packaged for outdoor installation.

Depending upon the site the combustion turbines will be equipped for gas fuel only operation or dual fuel (distillate fuel & natural gas) fuel operation. Units equipped for distillate fuel operation will require a water injection system for NOx emissions control. The CTG equipment package includes the following accessory systems:

- DLN Combustion System (Natural Gas and Distillate fuel oil)
- Water Injection System (for distillate fuel operation)
- Lube Oil System
- Hydraulic Control Oil Systems
- Water Wash System
- Exhaust System
- Inlet Air Filtration System (with noise abatement)
- Inlet Air Cooling System (evaporative)
- Starting System (with turning gear)
- Dual Fuel Control Systems (gas and distillate fuels)
- Variable Inlet Guide Vane (IGV) System
- Mark VI (TMR) Turbine Control & Protection System
- Packaged Electric and Electronic Control Cab (PEECC)

Distributed Control System (Power Island Scope) - The Distributed Control System (DCS) will be a GE MARK VI Triple Modular Redundant (TMR) control system provided by GE as part of the power island package. The DCS shall provide for the supervisory control of the Combustion Turbine Generators. In addition the DCS shall provide for the control and protection of the Balance of Plant (BOP) equipment, excepting those systems that are better suited for local control such as the Water Treatment System, Instrument Air Dryers, CEMs, and miscellaneous sumps. Where local controls are used, common trouble alarms and supervisory control functions shall be provided by the DCS. Human Machine Interfaces (HMIs) shall be located in the Central Control Room and locally at each major piece of equipment.

Continuous Emissions Monitoring System (Power Island Scope) - A fully certified Continuous Emissions Monitoring System (CEMS) shall be provided (by GE) for each CTG to continuously monitor the emissions from each CTG. A Data Acquisition and Handling System (DAHS) shall be provided capable of logging and reporting emissions as required by the Air Quality Permit. The CEMS and DAHS equipment shall be housed in a temperature and humidity controlled CEMS shelter.

Selective Catalytic Reduction (SCR) - For plants with SCR, the proposed plant includes one SCR assembly with NOx and CO catalyst, ammonia injection system, two tempering air fans, and stack, per turbine.

3.3 EPC Scope

The following paragraphs describe the equipment for which the EPC contractor shall be responsible for procurement.

3.3.1 Gas Fuel Only - Combustion Turbines

Auxiliary Cooling Water System - The auxiliary cooling water system is a closed loop cooling water system supplying cooling water to the gas turbine generator coolers, steam turbine & gas turbine lube oil coolers and other auxiliary equipment. The major equipment includes the following:

- Two (2) 100% Pumps
- Two (2) 50 % Fin - Fan Coolers
- Surge Tank
- Chemical Addition Tank

Auxiliary Electrical System - The auxiliary electrical system provides a means of stepping-down the generator terminal voltage to deliver power to the plant auxiliaries at a reduced voltage.

Typical major equipment includes:

- Auxiliary cable and/or bus
- Station unit auxiliary transformers (UAT)
- 5 kV switchgear
- 5kV medium voltage motor controller gear (MVMC)
- Station service transformers (SST)
- secondary unit substations (SUS)
- 480 V motor control centers (MCC)

Cathodic Protection System - The cathodic protection system function to mitigate galvanic action and prevent corrosion on the underground natural gas piping. The major equipment includes:

- Sacrificial anodes
- Cable
- Test boxes for potential measurement
- Insulating flanges.

DC Power System - The DC power system functions to provide a reliable source of motive and control power for critical equipment, the emergency shutdown of the plant, and the egress of plant personnel during blackout conditions. These loads typically include control power for power circuit breakers, switchgear, protective relaying, and power for the Uninterruptible Power Supply (UPS). The major equipment includes:

- A bank of lead acid storage battery
- Two 100% capacity battery chargers
- A DC power distribution switchboard

Emergency Diesel Generator - The emergency diesel generator provides for the supply of essential AC auxiliary power during an electrical system (grid) black-out to permit a safe and orderly shutdown of the plant equipment. The major equipment includes:

- 500 kW diesel generator w/load bank
- 6,000 gallon diesel storage tank

Demineralized Water System - The demineralized water system functions to provide a supply of demineralized make-up water to the CT evaporative cooling system, the CT water injection system (NOx control on distillate fuel), and for some the CT wash water solutions. During operation on distillate fuel oil and/or when operating the CT evaporative cooling system a rental water treatment trailer must be brought in to keep up with the demineralized water demands of the CTs. Major equipment that makes up the demineralized water system includes the following:

- A 2,200,000 gallon demineralized water storage tank for dual fuel CTs
- A 150,000 gallon demineralized water storage tank for gas fuel only CTs
- Two (2) 100% capacity demineralized water transfer pumps
- Water treatment trailers (rental by Owner)

Facility Low Voltage Electrical System - The low voltage electrical system conditions and distributes electrical power at various voltage levels for lighting, receptacles and small loads (motors, HVAC, etc.) as required for all buildings and site support facilities. The major equipment of this system includes:

- Transformers
- Distribution panel boards
- Disconnect switches
- Separately mounted motor starters
- General-purpose receptacles
- Welding receptacles
- Lighting

Fuel Gas Condition Skid- The fuel gas skid functions to filter and heat the natural gas supplied for use as fuel by the combustion turbine. A skid is provided for each CTG. Fuel gas heating is performed during startup and normal operation by an electric heater to provide the superheat necessary to prevent the formation of liquid hydrocarbons in the fuel. The major equipment for each skid includes the following:

- Two (2) 100% coalescing filter/separators
- One (1) 100% scrubber
- One (1) fuel gas electric heater

Fuel Gas Pressure Regulating Skid - A dual train fuel gas pressure regulating skid shall be provided to filter and regulate the supply pressure of the natural gas to the facility to satisfy the operational requirements of the CTGs. The major pressure regulation skid equipment includes the following:

- One (1) emergency shutdown valve
- Two (2) 100% capacity coalescing filter/separators
- Two (2) 100% capacity pressure reducing trains each equipped with the following:
 - * One (1) automatic inlet isolation valve per train
 - * One (1) startup pressure reducing valve per train

- * One (1) primary pressure reducing valve per train
- One (1) safety relief valve with vent stack
- One (1) fuel gas condensate drains tank

Fire Protection System - The fire protection system provides standpipes and hose stations, fire extinguishers, independent fire detection systems, and fixed carbon dioxide suppression systems to protect personnel, plant buildings and equipment from the hazards of fire. The system consists of the following:

- Low-pressure carbon dioxide fire suppression system
- Fire detection systems
- Portable fire extinguishers
- Manual fire alarm systems
- Manual pull stations in the buildings
- Fire Protection Control Panel for alarm, indication of system status, and actuation of fire protection equipment.
- One (1) 100% electric driven fire pump
- One (1) 100% diesel driven fire pump with diesel day tank.
- One (1) jockey pump
- 100,000 gallons of fire water reserve within the raw water storage tank
- Piping and valves, stand pipes and hose stations
- Fire pump building

Grounding System - The grounding system function to provide protection for personnel and equipment from the hazards that can occur during power system faults and lightning strikes. System design shall include the ability to detect system ground faults. The grounding system shall typically consist of copper-clad ground rods, bare and insulated copper cable, copper bus bars, copper wire mesh, exothermic connections, and air terminals.

Generation (High Voltage) Electrical System- The generation electrical system functions to deliver generator power to the Substation, and provides power for the auxiliary electrical system. One set of the following equipment shall be provided for each the three (3) generating unit).

- Generator main leads
- Generator breaker
- Generator step-up (GSU) transformer (230 kV), (345kV Location 3 Only)
- Auxiliary transformer

Oily Waste System - The Oily Waste system collects oil-contaminated wastewater in the plant drains system. The oil waste system is gravity feed throughout the plant to an oil water separator. The solids and oil collected in this system will be collected for offsite disposal at a suitable, licensed, hazardous waste facility. The effluent from the oil/water separator will be discharged to the local sewer system.

Plant Instrument and Service Air System - The plant instrument and service air system function to supply clean, dry, oil-free air at the required pressure and capacity for all pneumatic controls,

transmitters, instruments and valve operators, and clean compressed air for non-essential plant service air requirements. The plant instrument and service air system includes the following components:

- Two (2) full capacity, air cooled, single stage, rotary screw type air compressors, each complete with controls, instrument panel, intercooler, lubrication system, aftercooler, moisture separator, intake filter-silencer, air/oil separator system and an unloading valve.
- Two (2) full capacity air receivers
- Two (2) full capacity, dual tower, heaterless type desiccant air dryers
- Two (2) full capacity pre-filters
- Two (2) full capacity after-filters
- Associated header and distribution piping and valves

Plant Communication System - The plant communication system functions to provide the plant external communication system through the use of the public telephone system. The administration building, control room, maintenance and storage areas will be equipped with telephone jacks. The Owner shall provide any internal plant communication systems including, but not limited to, two-way radios.

Plant Security - The plant security system provides protection to the property and personnel. A security system consisting of card readers, intercoms, motor operated gate and fencing will be provided.

Potable Water - The potable water system serves as a water source for drinking and personnel hygiene needs. Potable water also serves as a water source for eyewash and safety shower stations. Potable Water will be supplied from the local water utility.

Raw Water System - The raw water system provides utility water for general plant use. The water will be provided by the local water utility. The raw water system will supply water for miscellaneous non-potable plant uses including demineralized water treatment system supply, plant equipment wash-downs, general service water and fire water. The major equipment includes the following:

- One (1) 200,000 gallon raw water/fire water storage tank
- Two (2) 100% capacity raw water pumps

Sanitary Waste System - The sanitary waste system collects sanitary wastes from the plant and transports to the city sewer system.

Uninterruptible Power Supply (UPS) - The uninterruptible power supply functions to provide reliable, regulated low voltage ac power to critical equipment during normal and emergency operating conditions. The typical loads that are considered for connection to the UPS include the Distributed Control System (DCS), CEMS, critical instruments, emergency shutdown networks, and critical vendor supplied control panels. The UPS system consists of the following components:

- Static inverter
- Static transfer switch
- Alternate source transformer and line voltage regulator
- Manual make-before-break bypass switch
- Two ac circuit breakers (alternate input, and bypass source)
- One dc circuit breaker
- Vital 120 V ac distribution panel with fused disconnects
- Controls, indicating lights, meters and alarms to control the UPS

3.3.2 Dual Fuel - Combustion Turbines

The following equipment is required to support dual fuel (distillate fuel & natural gas fuel) operation of the combustion turbines. It is in addition to the equipment listed above for gas fuel operation of the combustion turbines:

Fuel Oil System - The fuel oil system receives, stores, regulates and transports distillate oil for use as backup fuel in the combustion turbine. The major equipment includes:

- One (1) 2,000,000 gallon fuel oil storage tank with steel containment
- Two (2) fuel unloading stations
- Two (2) 100% capacity fuel forwarding pumps
- Two (2) 100% capacity fuel transfer pumps
- Interconnecting power and instrument cable, piping valves, filters and accessories

Demineralized Water System - The size of the demineralized water storage tank must be increased to 2,200,000 gallons for the dual fuel combustion turbines to support water injection for NOx control.

3.3.3 Selective Catalytic Reduction (SCR)

The following additional equipment is required to support SCR operation, if SCR is installed with the plant:

Ammonia System - The aqueous ammonia system stores and delivers ammonia to the Selective Catalytic Reduction (SCR) system for the reduction of NOx emissions. The major equipment consists of the following:

- Two (2) 100% ammonia forwarding pumps
- One (1) nominal 20,000 gallon horizontal storage tank
- One (1) evaporator
- Tank truck unloading area

4.0 Power Plant General Arrangement

- Gas Fuel Only Combustion Turbine Arrangement, G-PP-003, revision A
- Dual Fuel Combustion Turbine Arrangement, G-PP-011, revision A

5.0 Project Schedules

Single Fuel Option:

A 23 month overall schedule (NTP-COD) was assumed which includes a 17 month construction/startup schedule through COD.

Project Start	January 1, 2013
NTP and Start of detailed engineering	July 1, 2013
Start of construction	January 1, 2014
COD	June 1, 2015

Single Fuel Option w/SCR:

A 23 month overall schedule (NTP-COD) was assumed which includes a 17 month construction/startup schedule through COD.

Project Start	January 1, 2013
NTP and Start of detailed engineering	July 1, 2013
Start of construction	January 1, 2014
COD	June 1, 2015

Dual Fuel Option:

A 26 month overall schedule (NTP-COD) was assumed which includes a 20 month construction/startup schedule through COD.

Project Start	September 17, 2012
NTP and Start of detailed engineering	April 1, 2013
Start of construction	October 2, 2013
COD	June 1, 2015

Dual Fuel Option w/SCR:

A 26 month overall schedule (NTP-COD) was assumed which includes a 20 month construction/startup schedule through COD.

Project Start	September 17, 2012
NTP and Start of detailed engineering	April 1, 2013
Start of construction	October 2, 2013
COD	June 1, 2015

Prior to the NTP the Owner must obtain all the necessary environmental and local permits that are required as a prerequisite to commence construction. Procurement of OFE starts with project start and is complete for assignment to EPC contractor at NTP.

6.0 Capital Cost Estimate

EPC Contractor

- Estimate Basis, Rev F/H Supplemental

For Locations 1-5, Dual Fuel and for Location 3 Single Fuel:

- Estimate Summary and Details, revision F (no SCR)
- Estimate Summary and Details, revision H (with SCR)

Owner

For Locations 1-5, Dual Fuel and for Location 3 Single Fuel:

- Owner Cost tabulations no SCR
- Owner Cost tabulations with SCR

Fuel consumption and power generation during commissioning and testing (estimated) for the Simple Cycle plant is as follows:

operating hours	1200	hrs		
duration	50	days		
duration	7	weeks		
generation	215,000	MWhrs		
average load	179	MW		
fuel gas	2,000,000	Dth		
fuel oil	540,000	gals		

7.0 Cash Flow

EPC cash flow is based on the project cost excluding the OFE portion paid by Owner prior to assignment but including the OFE portion after assignment. The percentages of OFE costs to be used are identified in the Owners cost tabulations in Section 6.0. There are no monthly charges until NTP and assignment.



Owner cash flow is based on the OFE portion paid prior to assignment and all sales taxes and runs from project start thru end of project. The percentages of OFE costs to be used are identified in the Owners cost tabulations in Section 6.0. Owner does not make OFE payments after assignment at NTP.

These two percentages cannot be added together to get total monthly cash flows. They have to be converted to cash first, and then added.


- Simple Cycle - Gas Fuel Only Cash Flow, revision F Supplemental (no SCR)
- Simple Cycle - Dual Fuel Cash Flow, revision F Supplemental (no SCR)

- Simple Cycle - Gas Fuel Only Cash Flow, revision H Supplemental (with SCR)
- Simple Cycle - Dual Fuel Cash Flow, revision H Supplemental (with SCR)

APPENDIX A.2. LAYOUT DRAWING FOR DUAL-FUEL CT WITH SCR



EQUIPMENT LEGEND		
ITEM	EOPT TAG NO	DESCRIPTION
1		7FA CTG (COMBUSTION TURBINE GENERATOR)
2		TURBINE EXHAUST DUCT
3		EXHAUST STACK
4		FIN FAN COOLER
5		PARKING
6		CTG INLET AIR FILTER
7		CTG ROTOR PULL SPACE
8		CEMS (CONTINUOUS EMISSIONS MONITORING)
9		PEEC
10		CO2 FIRE PROTECTION SYSTEM
11		GSU
12		GENERATOR BREAKER
13		FUEL GAS CONDITIONING SKIDS
14		PLANT/INSTRUMENT AIR COMPRESSORS
15		ISO PHASE BUS
16		DEMINEALIZED WATER STORAGE TANK
17		RAW/FIRE WATER STORAGE TANK
18		FIRE PROTECTION PUMP PACKAGE
19		WATER TREATMENT BUILDING
20		SWITCHYARD FENCE LINE
21		SWITCHYARD
22		SWITCHYARD CONTROL HOUSE
23		WAREHOUSE & MAINTENANCE BUILDING
24		ADMINISTRATION BUILDING & CONTROL ROOM
25		FUEL GAS METERING & REGULATING STATION
26		EXCITATION TRANSFORMER
27		FUEL OIL STORAGE TANKS
28		FUEL OIL UNLOADING & FORWARDING
29		FOAM FIRE PROTECTION SYSTEM
30		-
31		-
32		-
33		-
34		-
35		-
36		-
37		-
38		-
39		-
40		-



NO.	DATE	REVISION	BY	CHK	REVISION APPROVAL		REV A		DATE 08/23/11		STATUS							
					DISCIPLINE	REVIEWED	DISCIPLINE	REVIEWED	ISSUED	REV	DATE	DM	SDE	PEM				
P1	06/29/11	ISSUED FOR INTERNAL REVIEW	TBJ		ELECTRICAL		ELECTRICAL											
A	08/23/11	ISSUED FOR FINAL REPORT	TBJ		CIVIL		ELECTRICAL											
					STRUCTURAL		INST & CNTRL											
					MECHANICAL		ARCHITECTURAL											
					PROCESS		PLANT LAYOUTS											
					PIPING													

The Brattle Group
 PJM Interconnect Study
 Northeast U.S.

PROJECT NO. 421147

CH2MHILL
 CH2MHILL Engineers, Inc.


GENERAL ARRANGEMENT
 DUAL FUEL
 SIMPLE CYCLE
 PLOT PLAN

DWG. NO. G-PP-011 REV. A

BAR IS ONE INCH ON ORIGINAL DRAWING.

REUSE OF DOCUMENTS: THIS DOCUMENT AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CH2M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL. © CH2M HILL

APPENDIX A.3. PROJECT SCHEDULE FOR DUAL-FUEL CT WITH SCR



█ Actual Work
█ Remaining Work
█ Critical Remaining Work

APPENDIX A.4. COST DETAIL FOR CT WITH SCR IN CONE AREA 1

Description	Quantity	UM	HRS / UM	Professional Labor		Self Perform Craft Labor		Subcontract Labor		Specialty Sub.	Total Craft	Material			Const.	Specialty	Other	Total	% Of Direct	% Of Project	% Of Project	
				Hours	Labor Amount	Hours	Labor Amount	Hours	Labor Amount	Hours	Hours	Eng. Equip	Bulk	Sub.	Equip.	Sub					Total	Total Revenue
INDIRECT COSTS																						
PROJECT MANAGEMENT																						
	17,597	HRS																				
Home Office Professional (PM/CM)			190.56	3,986h	759,566													759,566	1.0%	0.6%	0.3%	
Project Support Professional (Safe/QC/PC/DocC/Est)			136.29	8,928h	1,216,882													1,216,882	1.5%	0.9%	0.5%	
Clerical			57.90	4,683h	271,127													271,127	0.3%	0.2%	0.1%	
Expenses																	167,205	167,205	0.2%	0.1%	0.1%	
ENGINEERING																						
	30,860	HRS																				
Home Office Professional			107.48	29,060h	3,123,317													3,123,317	4.0%	2.4%	1.3%	
Field Professional (Site Support Engineering)			109.71	1,800h	197,473													197,473	0.2%	0.2%	0.1%	
Value Center Engineering																		-	0.0%	0.0%	0.0%	
Clerical																		-	0.0%	0.0%	0.0%	
Expenses																	283,000	283,000	0.4%	0.2%	0.1%	
PROCUREMENT																						
	7,300	HRS																				
Home Office Professional			110.00	7,300h	803,000													803,000	1.0%	0.6%	0.3%	
Field Professional																		-	0.0%	0.0%	0.0%	
Clerical																		-	0.0%	0.0%	0.0%	
Expenses																	30,000	30,000	0.0%	0.0%	0.0%	
SITE MANAGEMENT																						
	82,850	HRS																				
Field Professional			110.87	65,314h	7,241,459													7,241,459	9.2%	5.5%	3.0%	
Clerical			33.20	17,537h	582,192													582,192	0.7%	0.4%	0.2%	
Expenses																	383,816	383,816	0.5%	0.3%	0.2%	
STARTUP MANAGEMENT																						
	14,180	HRS																				
Home Office Professional			136.50	500h	68,250													68,250	0.1%	0.1%	0.0%	
Field Professional			98.28	13,680h	1,344,516													1,344,516	1.7%	1.0%	0.5%	
Clerical																		-	0.0%	0.0%	0.0%	
Expenses																	93,500	93,500	0.1%	0.1%	0.0%	
SUBTOTAL MANGEMENT COST				152,787h	15,607,782	361,088h	30,568,341	7,334h	948,043	38,240h	406,661h	17,422,158	8,720,892	-	1,785,456	12,358,525	8,164,750	95,575,948	121.0%	73.2%	39.0%	95,575,948
CONTINGENCY																						
Percentage				5.0%		7.0%		7.0%				13.7%	5.0%		5.0%	6.0%					Cont. & Escal.	
Dollars				780,389		2,139,784		66,363				2,382,665	436,045		89,273	741,512		6,636,030	8.4%	5.1%	2.7%	20,038,730
ESCALATION																						
Percentage				12.3%		13.8%		10.3%				19.7%	17.3%		12.9%	15.3%	1.4%					
Dollars				1,915,500		4,211,700		97,600				3,431,400	1,508,500		230,800	1,891,600	115,600	13,402,700	17.0%	10.3%	5.5%	
RISK																						
PROJECT SUBTOTAL				152,787h	18,303,671	361,088h	36,919,825	7,334h	1,112,006	38,240h	406,661h	23,236,223	10,665,436	-	2,105,529	14,991,637	8,280,350	115,614,678	146.3%	88.6%	47.2%	115,614,678

Project Name 429 MW 2x0 SC Plant - GE 7241FA.05
 Client The Brattle Group
 Project Description Middlesex County, New Jersey

Location 1: Dual Fuel w/ SCR

Data Date
 Print Date 28-Jul-11
 Rev: H



Description	Quantity	UM	HRS / UM	Professional Labor		Self Perform Craft Labor		Subcontract Labor		Specialty Sub.	Total Craft	Material			Const.	Specialty	Other	Total	% Of Direct Total	% Of Project Total Revenue	% Of Project Total	
				Hours	Labor Amount	Hours	Labor Amount	Hours	Labor Amount	Hours	Hours	Eng. Equip	Bulk	Sub.	Equip.	Sub						
GENERAL OVERHEAD & ADMINISTRATION																						G&A & Margin
Percentage					0.0%		0.0%		0.0%			0.0%	0.0%		0.0%	0.0%	0.0%					17,286,468
Dollars					-		-		-			-	-		-	-	-					0.0%
MARGIN																						
Percentage					10.0%		10.0%		10.0%			10.0%	10.0%		10.0%	10.0%	10.0%					
Dollars					1,830,367		3,691,983		111,201			2,323,622	1,066,544		210,553	1,499,164	828,035					11,561,468
POWER BLOCK MARGIN																						
Percentage												0.0%										
Dollars												-										0.0%
Assignment Fee For Owner Supplied Equipment																						
Percentage												5.0%										0.0%
Dollars												5,725,000										5,725,000
PROJECT COST W/MARKUPS				152,787h	20,134,038	361,088h	40,611,808	7,334h	1,223,207	38,240h	406,661h	31,284,845	11,731,980	-	2,316,082	16,490,801	9,108,385					132,901,145
Sales Tax Deduction																						
Management Adjustments																						
PROJECT TOTAL REVENUE				152,787h	20,134,038	361,088h	40,611,808	7,334h	1,223,207	38,240h	406,661h	31,284,845	11,731,980	-	2,316,082	16,490,801	9,108,385					130,552,074
OWNER FURNISHED EQUIPMENT																						
CTGs												93,000,000										
HOT SCRs												21,500,000										
												-										
												-										
												-										
												-										
												-										
												-										
												-										
PROJECT TOTAL				152,787h	20,134,038	361,088h	40,611,808	7,334h	1,223,207	38,240h	406,661h	145,784,845	11,731,980	-	2,316,082	16,490,801	9,108,385					245,052,074

245,052,000

APPENDIX A.5. CASH FLOW SCHEDULE FOR CT WITH SCR IN CONE AREA 1

The Brattle Group
429 MW 2x0 SC Plant - GE 7241FA.05

EPC Cashflow

08/15/11

MONTH	Dual Fuel: w/ SCR	Rev	H
		%	%
			CUMULATIVE
1	Sep-12	0.000%	0.000%
2	Oct-12	0.000%	0.000%
3	Nov-12	0.000%	0.000%
4	Dec-12	0.000%	0.000%
5	Jan-13	0.000%	0.000%
6	Feb-13	0.000%	0.000%
7	Mar-13	0.000%	0.000%
8	Apr-13	4.920%	4.920%
9	May-13	2.419%	7.338%
10	Jun-13	2.691%	10.029%
11	Jul-13	2.863%	12.892%
12	Aug-13	2.790%	15.682%
13	Sep-13	2.572%	18.254%
14	Oct-13	4.619%	22.873%
15	Nov-13	3.200%	26.073%
16	Dec-13	5.383%	31.456%
17	Jan-14	3.846%	35.302%
18	Feb-14	5.933%	41.235%
19	Mar-14	3.936%	45.171%
20	Apr-14	12.460%	57.630%
21	May-14	3.404%	61.034%
22	Jun-14	3.070%	64.104%
23	Jul-14	4.088%	68.192%
24	Aug-14	3.708%	71.901%
25	Sep-14	4.499%	76.399%
26	Oct-14	4.568%	80.967%
27	Nov-14	3.422%	84.389%
28	Dec-14	4.060%	88.449%
29	Jan-15	2.800%	91.249%
30	Feb-15	2.275%	93.524%
31	Mar-15	1.367%	94.891%
32	Apr-15	1.391%	96.282%
33	May-15	0.866%	97.148%
34	Jun-15	2.852%	100.000%

The Brattle Group
429 MW 2x0 SC Plant - GE 7241FA.05

Owner Cash Flow

08/15/11

MONTH	Dual Fuel: w/ SCR	Rev	H
		%	%
			Monthly
			CUMULATIVE
1		0.00%	0.00%
2		0.00%	0.00%
3		34.78%	34.78%
4		0.00%	34.78%
5		17.39%	52.17%
6		0.00%	52.17%
7		0.00%	52.17%
8		1.17%	53.33%
9		1.20%	54.54%
10		1.23%	55.77%
11		1.26%	57.03%
12		1.29%	58.32%
13		17.41%	75.73%
14		2.39%	78.12%
15		1.38%	79.51%
16		2.52%	82.03%
17		1.45%	83.48%
18		2.52%	86.00%
19		1.64%	87.64%
20		5.59%	93.23%
21		1.13%	94.36%
22		0.49%	94.85%
23		0.57%	95.41%
24		0.62%	96.04%
25		0.46%	96.50%
26		0.54%	97.04%
27		0.43%	97.47%
28		0.35%	97.82%
29		0.30%	98.12%
30		0.20%	98.32%
31		0.20%	98.53%
32		0.16%	98.69%
33		0.11%	98.80%
34		1.20%	100.00%

APPENDIX B. CH2M HILL COMBINED-CYCLE COST ESTIMATES

CH2M HILL's detailed engineering cost estimates for plant proper costs including both EPC contractor costs and owner-furnished equipment costs are contained in this appendix for each combined-cycle plant configuration examined. A summary report describing detailed plant specifications and summary cost results for each CC configuration in each CONE Area is contained in CH2M HILL's summary report in Appendix B.1. Plant layout drawings, project schedules, cost estimate details, and cash flow schedules were also provided for each CC location and configuration. Appendices C.2 through C.5 contain this detailed supporting information for one of the CONE Area 1 plant configuration, which is a dual-fuel plant.

APPENDIX B.1. COMBINED-CYCLE PLANT PROPER COST ESTIMATE REPORT

APPENDIX B.2. LAYOUT DRAWING FOR DUAL-FUEL CC

APPENDIX B.3. PROJECT SCHEDULE FOR DUAL-FUEL CC

APPENDIX B.4. COST DETAIL FOR CC IN CONE AREA 1

APPENDIX B.5. CASH FLOW SCHEDULE FOR CC IN CONE AREA 1

APPENDIX B.1. COMBINED-CYCLE PLANT PROPER COST ESTIMATE REPORT



Combined Cycle Cost Estimate 2 x 1 GE 7FA Reference Plant

Brattle Group PJM Estimating Support

Prepared By CH2M HILL
Project No. 421147
Rev. C
August 2011



TABLE OF CONTENTS

1.0	Executive Summary	2
2.0	Development Approach.....	4
3.0	Plant Scope.....	10
4.0	Power Plant General Arrangement	24
5.0	Project Schedule	25
6.0	Capital Cost Estimate	26
7.0	Cash Flow.....	27

Revision	Description	Date
A	Issued for Review	July 1, 2011
B	Comments Incorporated	August 2, 2011
C	Final	August 23, 2011

1.0 Executive Summary

CH2M HILL Engineers, Inc. was engaged by the Brattle Group, Inc to provide capital cost estimates for gas fuel only and dual fuel (oil & natural gas) GE 7FA.05 gas turbine combined cycle power plants at multiple sites, each capable of generating approximately 701 MW. The plant configurations each consist of two (2) GE Frame 7FA.05 combustion turbine generators (CTGs), two (2) duct fired three pressure reheat Heat Recovery Steam Generators (HRSGs), one (1) condensing reheat Steam Turbine Generator (STG), surface condenser and all necessary Balance of Plant (BOP) equipment.

Dual Fuel Combustion Turbines

As a basis for the dual fuel combustion turbine estimates CH2M HILL developed the following information:

- Capital costs for five (5) geographical areas (New Jersey, Maryland, Illinois, Pennsylvania, and Virginia)
- A General Arrangement drawing for a representative combined cycle power plant
- A Level One Project schedule
- A basic monthly cash flow tabulation

The capital cost estimates for each geographical area are summarized in the table below. The details of the cost breakdown for each location are included in Section 6.0.

Geographical Area	Labor Type	EPC Costs \$	Owner Costs \$	Total Installed Capital Cost -\$
New Jersey	Union	356,186,888	194,785,565	547,444,257
Maryland	Non-Union	274,566,035	192,061,631	466,627,666
Illinois	Union	348,377,452	194,784,480	543,161,932
Pennsylvania	Union	333,447,565	192,106,147	525,553,712
Virginia	Non-Union	274,373,867	189,384,692	463,758,559

Gas Fuel Only Combustion Turbines

As a basis for the gas fuel only combustion turbine estimate CH2M HILL developed the following information:

- Capital cost for the Will County, Illinois location
- A General Arrangement drawing for a representative simple cycle power plant
- A Level One Project schedule
- A basic monthly cash flow tabulation

The capital cost estimate for the natural gas fuel combustion turbine for Will County, Illinois is summarized in the table below. The details of the cost breakdown for this location are included in Section 6.

Geographical Area	Labor Type	EPC Costs \$	Owner Costs \$	Total Installed Capital Cost -\$
Illinois	Union	334,931,825	191,257,369	526,189,194

2.0 Development Approach

2.1 Estimating Process

For the development of the capital cost estimate, CH2M HILL utilized our Power Plant Indicative Cost Estimating Methodology which is based upon the plant specific configuration, location specific productivity and labor cost factors, and our extensive current cost data base for equipment and material. These factors are processed using our proprietary Indicative Estimating Software Model to produce a detailed analysis of the cost elements for the project that are then compared to recently completed similar projects.

Project Configurations

CH2M HILL's experience with various plant configurations is extensive. The combustion turbines shown in the table below have been designed and installed in combined cycle, simple cycle and cogeneration modes.

- 1 X LMS 100 simple cycle
- 2 X F-class simple cycle
- 4 X LM 6000 simple cycle
- 12 X FT-8 Twin Pack simple cycle
- 1 X 1 F-class combined cycle
- 2 X 1 F-class combined cycle
- 3 X 1 E-class combined cycle

CH2M HILL's estimating team retains standard plant layout configurations that have been imported into the estimating data base for use in this study. The design basis for this study is a 2 x 1 - 7F class combined cycle, the details for which are defined in Sections 3.0 - Plant Scope and Section 4.0 - General Arrangement of this report.

Variability by Location

The US construction industry has the most variability in productivity and execution strategy by location than any other country in the world. Project execution ranges from strong union locations such as New York City, Chicago, San Francisco and St. Louis to lower cost, merit shop locations such as the Gulf Coast and Southeast US. CH2M HILL's historical database tracks and updates labor productivity by location. CH2M HILL's "base" productivity location is the Gulf Coast, like many national contractors. At that location, the base productivity for each discipline trade is considered a 1.0 productivity factor and is considered the most efficient location to perform work based on worker skills and efficiency. That 1.0 productivity factor is then adjusted to reflect union labor, local labor rules and other historical data.

Variability of Estimates for Material and Equipment

Certain material and equipment costs are more volatile in the heavy industrial market than others. As examples, high temperature- high pressure pipe, electrical transformers and copper

wire are high in demand in the oil & gas market as well as the power market. When both industries are busy, costs increase dramatically due to not only material and manufacturing costs, but also due to greater demand than supply. Market conditions sometimes make it nearly impossible to assess with any certainty the proper amount of escalation to apply to some materials and equipment. This is compounded by the extended time from estimate development to project implementation. CH2M HILL's constant activity in bidding and procuring material and equipment provides more accurate costs that reflect current market conditions than available by other means.

CH2M HILL's Indicative Estimating Software Model

CH2M HILL has taken over 20 years of data from our involvement in the Power industry and developed an indicative database to aid in estimating future projects. The "Power Indicative Estimating Program" derives project costs based on information that is input on various worksheets within the program from a series of inputs, multiple logic functions and iterations, and a preliminary Indicative Estimate is produced which can be reviewed and modified as necessary.

Power Indicative Estimating Program Output

Once a project configuration, location, schedule and execution model is defined, the indicative estimator works with a Power Project Engineer to reflect other project properties unique to the project. The estimator inputs the specific project data into the model and then reviews with experienced construction managers and engineers to confirm alignment.

The program produces an estimating basis and a series of outputs. Some of these outputs include:

- Quantities of concrete, structural steel, pipe, conduit, cable and insulation
- Equipment required by system
- Work-hours for labor by discipline
- Engineering hours
- Construction supervision hours
- Startup and testing hours
- Indirect labor and equipment

The program allows the estimator to input the latest labor rates, productivity, which is then tabulated in the program to develop the final cost of the plant. The results of these analyses are contained in Section 6.0 of this report.

2.2 Owner Cost Estimates

Pricing for the three major components, the Combustion Turbine Generators (CTGs), the Heat Recovery Steam Generators (HRSGs) and the Steam Turbine Generator (STG), is based on GE Power Island information obtained from similar plants CH2M HILL has constructed and proposed. Note that GE's scope includes the Continuous Emissions Monitoring Systems (CEMS), Packaged Electrical and Electronic Control Cabs (PEECC), the Plant Distributed Control System (DCS) and the CTGs and STG auxiliary equipment.

These components (Owner Furnished Equipment or OFE) are procured by the Owner at project start, prior to EPC contract NTP. They are assigned to the EPC contractor at that time. Estimates of Owner costs that are in addition to the EPC contract cost are tabulated in Section 6.0.

2.3 EPC Cost Estimate

Pricing for the major Balance of Plant equipment including the ST surface condenser, cooling tower and generator step-up transformers were obtained from actual pricing and budgetary quotes received from vendors for similar recent projects and proposals.

The plant construction cost estimates were developed based on data from recent EPC projects. Labor rates and productivity factors for the following five (5) geographical areas were verified and used to develop the direct and indirect costs.

- 1) Middlesex County, New Jersey
- 2) Charles County, Maryland
- 3) Will County, Illinois
- 4) Northampton County, Pennsylvania
- 5) Fauquier County, Virginia

The construction cost estimates are based on direct labor hire (concrete, steel, piping, electrical and instrumentation) and specialty subcontract union (locations 1, 3, and 4) and merit shop craft labor (locations 2 and 5). Quantities for bulks were determined from plants similar in size and configuration. Historical data was utilized to provide an overall parametric check of account values of the completed estimate.

Labor

Locations 1, 3, and 4: Union craft labor rates were determined from prevailing wages for the area. Rates were built-up including the base rate, fringes and legalities. The estimate is based on a 50 hour craft work week. A labor factor of 1.1 was applied to the CSA accounts, 1.3 for the piping accounts, and 1.2 on all other accounts and based on various factors including location, working in an existing facility, congestion, local labor conditions, weather and schedule.

Locations 2 and 5: Merit shop craft labor rates were determined from prevailing wages for the area. Rates were built-up including the base rate, fringes and legalities. The estimate is based on a 50 hour craft work week. A labor factor of 1.0 was applied to all accounts based on various factors. A \$50 per day per diem has been included.

Escalation

The cost estimates are provided in June 2011 dollars and escalation was included based on the following schedules.

- Craft labor was escalated at 4.0% for 2011 and beyond.

- Engineered equipment and bulk materials were escalated at 6% for 2011 and beyond. Professional labor and construction indirect expenses were escalated at 3% for 2011 and 4% for 2012 and beyond.
- Specialty subcontracts were escalated at 5% for 2011 and beyond.

Contingency & Gross Margin

Contingency was included at:

- 5% for Professional Labor, Material and Construction Equipment
- 7% for Craft Labor
- 6% for Specialty Subcontracts
- 2% for the CTGs and STG
- 3% for the HRSGs
- 3% for Engineered Equipment

A gross margin of 10% was applied with 5% assignment fee applied to the Owner Furnished Equipment.

Project Indirects

Project indirects include:

- Builders Risk insurance
- General and excess liability insurance
- Performance and payment bonds
- Construction permits
- Sales tax (not including OFE) to roll up through markups then taken out at bottom line
- Letter of credit in lieu of retention
- Warranty
- Bonus pool

Scope - Inclusions

- Structural and civil works
- Mechanical, electrical, and control equipment
- Electrical Power Distribution Center (pre-assembled & tested)
- Heavy haul (allowance)
- Operator training
- O&M manuals
- Escalation
- Bulks including piping and instrumentation
- Contractor's construction supervision
- Temporary facilities
- Construction equipment, small tools and consumables

- Start-up spare parts and start-up craft labor
- Construction permits allowance (\$100,000)
- First fills
- Insurances
- Gross margin
- 5% Letter of Credit in lieu of retention
- Construction power, water and natural gas consumption
- Performance and Payment Bond
- Builders All Risk Insurance (costs broken out from EPC estimate for reference – see Estimate Basis Section 17.0)

Scope - Exclusions

- Soils remediation, moving of underground appurtenances or piping
- Dewatering except for runoff during construction
- Wetland mitigation
- Fuel gas compression
- Noise mitigation measures or study (unless otherwise noted)
- Piling
- Geotechnical investigation and survey (shown separately from EPC estimate as an Owners cost)
- Sales Tax (shown separately from EPC estimates as an Owners cost)
- Permitting/ Environmental permits (shown separately from EPC estimates as an Owners cost)
- Fuel oil and natural gas consumption during startup (shown separately from EPC estimate as an Owners cost)
- Switchyard

Scope - Assumptions & Clarifications

- Assumes flat, level and cleared site.
- Assumes free and clear access to work areas.
- This site does not contain any EPA defined hazardous or toxic wastes or any archeological finds that would interrupt or delay the project.
- Spread footings are assumed for all equipment.
- All excavated material is suitable for backfill/compaction.
- Rock excavation is not required.
- Temporary power and water will be available at site boundary as required to support construction at no cost to Contractor.
- An ample supply of skilled craft is available to the site.
- TA services are owner provided as part of their equipment supply.
- Craft bussing is not required.
- Ample space (provided by owner) for craft parking, temporary facilities, laydown and storage is available adjacent to site.
- Field Erected Storage Tanks are carbon steel with internal high build epoxy coatings.

- Access road modifications and improvements (beyond the site boundary battery limit) will be performed by others.
- Roads for heavy haul are suitable for transportation and contain no obstructions for delivery of heavy/oversized equipment.
- Heavy haul is assumed to be from a rail siding within one mile of the plant to setting on foundations.
- Equipment is supplied with manufacturer's standard finish paint.
- Natural gas is delivered at an adequate pressure and no gas compression is required
- Gas metering station is by others
- The electrical equipment and water treatment equipment will be housed in pre-fabricated building
- The electrical scope concludes at the high side of the Generator Step-up (GSU) transformers. Transmission line and substation costs are by others.
- Heat tracing has not been included for large above ground process piping where system pumps can be operated to prevent freezing, or where the system can be drained during extended cold weather outages.

3.0 Plant Scope

3.1 General Description

The proposed combined cycle power plant has a nominal generating capacity of approximately 701 MW at 59 °F outdoor ambient temperature when operating on gas fuel. The major components of the project include two (2) GE Frame 7FA.05 Combustion Turbine Generators (CTGs) each with a dedicated reheat Heat Recovery Steam Generator (HRSG), one (1) shared reheat Steam Turbine Generator (STG), surface condenser, cooling tower, air pollution controls and associated auxiliary and control systems. The CTGs will be equipped with inlet evaporative coolers to increase power output at high ambient temperature. The HRSGs will generate steam at three pressure levels and will be equipped with natural gas fired duct burners to provide additional steam to augment power output. The plant (dual fuel CT option) will operate both on natural gas and distillate fuel oil. The CTGs will be equipped with dry-low NO_x combustors (gas fuel operation) and the HRSGs with Selective Catalytic Reduction (SCR) control systems to reduce NO_x emissions. The HRSGs will also be equipped with oxidation catalyst systems to reduce CO and VOC emissions. The CTGs will be equipped with water injection for NO_x control when operating on distillate fuel (dual fuel option).

The termination points for the power facility are at the battery limits of the facility and include the following:

- High Pressure natural gas supply downstream of the gas metering station (by others) at the power facility boundary
- Water from the municipal water supply at the power facility boundary
- Waste to the municipal sewer at the power facility boundary
- Electrical connection is at the high side of the generator step-up transformers

The facility is assumed to be located on a Greenfield site. There will be three buildings included in the plant layout: an integrated administration/control room/warehouse/maintenance building, an electrical/water treatment building, and a STG building. Buildings are of pre-fabricated construction with the exception of the STG building. Layout of the plant shall be in accordance with the General Arrangement drawing included in Section 4.0.

General performance parameters are tabulated below for the (2x1) combined cycle plant. Predicted emissions data is also provided based on generic data for CTG and SCR performance using estimated stack emissions concentrations and rates.

	GAS			
	Evaporative Cooling			
Plant configuration	2x1	2x1	2x1	2x1
CTG Load Point	100%	100%	100%	100%
Ambient Temperature, oF	59	59	92	92
Relative Humidity, %	60	60	53	53
Evaporative Cooling	ON	ON	ON	ON
Duct Burner Status	OFF	ON	OFF	ON
Fuel Heating Value, Btu/Lb (LHV)	21,515	21,515	21,515	21,515

CT Generators terminal power, kW	426,560	426,560	397,978	397,978
ST Generator terminal power, kW	223,440	300,120	207,320	281,440
Gross Plant Power, kW	650,000	726,680	605,298	679,418
Gas Turbine Fuel Input, Btu/Hr	3,805,768,320	3,805,768,320	3,628,763,400	3,628,763,400
Duct Burner Fuel Input, Btu/Hr	0	570,000,000	0	570,000,000
Total Fuel Input, Btu/Hr	3,805,768,320	4,375,768,320	3,628,763,400	4,198,763,400
Gross Plant Heat Rate, Btu/kWH (LHV)	5,855	6,022	5,995	6,180
Plant Auxiliary Loads, kW	22,750	25,434	21,185	23,780
Net Plant Power, kW	627,250	701,246	584,113	655,638
Net Plant Heat Rate, Btu/kWH (LHV)	6,067	6,240	6,212	6,404

	FUEL OIL			
	Evaporative Cooling			
Plant configuration	2x1	2x1	2x1	2x1
CTG Load Point	100%	100%	100%	100%
Ambient Temperature, oF	59	59	92	92
Relative Humidity, %	60	60	53	53
Evaporative Cooling	ON	ON	ON	ON
Duct Burner Status	OFF	ON	OFF	ON
Fuel Heating Value, Btu/Lb (LHV)	18,300	18,300	18,300	18,300

CT Generators terminal power, kW	437,560	437,560	423,734	423,734
ST Generator terminal power, kW	221,300	289,240	210,530	275,180
Gross Plant Power, kW	658,860	726,800	634,264	698,914
Gas Turbine Fuel Input, Btu/Hr	4,205,466,000	4,205,466,000	4,116,575,810	4,116,575,810
Duct Burner Fuel Input, Btu/Hr	0	460,000,000	0	460,000,000
Total Fuel Input, Btu/Hr	4,205,466,000	4,665,466,000	4,116,575,810	4,576,575,810
Gross Plant Heat Rate, Btu/kWH (LHV)	6,383	6,419	6,490	6,548
Plant Auxiliary Loads, kW	23,060	25,438	22,199	24,462
Net Plant Power, kW	635,800	701,362	612,065	674,452
Net Plant Heat Rate, Btu/kWH (LHV)	6,614	6,652	6,726	6,786

GE 7FA.05						
OPERATING CONDITION		N. Gas	Fuel Oil			
Ambient DBT Deg F		59	59			
Relative Humidity %		60	60			
Gas Turbine Unit Exhaust						
Flow Rate	lbs/hr	4,132,000	4,151,000			
Temperature	deg F	1113	1147			
Argon	% VOL	0.88	0.84			
Nitrogen	% VOL	74.18	70.7			
Oxygen	% VOL	12.26	10.68			
Carbon Dioxide	% VOL	3.85	5.74			
Water	% VOL	8.83	12.04			
Gas turbine Emissions						
NOx corrected to 15% O2	ppmvd	9	42			
NOx as NO2	lbs/hr	69	370			
CO corrected to 15% O2	ppmvd	9	20			
CO	lbs/hr	33	72			
UHC	ppmvd	7	7			
UHC	lbs/hr	16	16			
PM10 particulates	lbs/hr	9	17			

After HRSG/SCR

	Gas CC	
	N.G (ppmvd)	F.O. (ppmvd)
NO _x	2	5
VOC	5	5
CO	5	11
PM _{2.5}	--	--
SO ₂	Note A	Note B

Gas CC		
	N.G (lb/hr)	F.O. (lb/hr)
NO _x	15.6	44.5
VOC	13.5	15.5
CO	23.7	59.5
PM _{2.5}	9	17
SO ₂	5.4	6.9

Gas CC		
	N.G (lb/MMBtu)	F.O. (lb/MMBtu)
NO _x	4.10E-03	1.06E-02
VOC	3.55E-03	3.69E-03
CO	6.23E-03	1.41E-02
PM _{2.5}	2.36E-03	4.04E-03
SO ₂	1.43E-03	1.64E-03

	Gas CC 2X1	
	Natural Gas	Fuel oil
Heat input (MMBtu/hr)	3,806	4,205
Fuel Heating Value Btu/Lb (LHV)	21,515	18,300

Notes

A - 0.5 grains/100 scf

B - 15 ppm on a mass basis for fuel oil

c - Assumed heating value of natural gas of 1000 Btu/scf

3.2 Owner Furnished Equipment (OFE)

The following paragraphs describe the equipment for which the Owner is responsible to procure.

Combustion Turbine Generators (Power Island Scope) - The combustion turbine generators (CTG's) operate to produce electrical power and waste heat. The plant will include two (2) General Electric 7FA.05 combustion turbine-generators packaged for outdoor installation. Depending upon the site the combustion turbines will be equipped for gas fuel only operation or dual fuel (distillate fuel & natural gas) fuel operation. Units equipped for distillate fuel operation will require a water injection system for NO_x emissions control. The CTG equipment package includes the following accessory systems:

- DLN Combustion System (Natural Gas and Distillate fuel oil)
- Water Injection System (for distillate fuel operation)
- Lube Oil System
- Hydraulic Control Oil Systems
- Water Wash System
- Exhaust System
- Inlet Air Filtration System (with noise abatement)
- Inlet Air Cooling System (evaporative)
- Starting System (with turning gear)
- Dual Fuel Control Systems (gas and distillate fuels)
- Variable Inlet Guide Vane (IGV) System
- Mark VI (TMR) Turbine Control & Protection System

Distributed Control System (Power Island Scope) - The Distributed Control System (DCS) will be a GE MARK VI Triple Modular Redundant (TMR) control system provided by GE as part of the power island package. The DCS shall provide for the supervisory control of the Combustion Turbine Generators and Steam Turbine Generator. In addition the DCS shall provide for the control and protection of the HRSGs and all Balance of Plant (BOP) equipment, excepting those systems that are better suited for local control such as the Water Treatment System, Instrument Air Dryers, CEMs, BMS and miscellaneous sumps. Where local controls are used, common trouble alarms and supervisory control functions shall be provided by the DCS. Human Machine Interfaces (HMIs) shall be located in the Central Control Room and locally at each major piece of equipment.

Continuous Emissions Monitoring System (Power Island Scope) - A fully certified Continuous Emissions Monitoring System (CEMS) shall be provided (by GE) for each CTG to continuously monitor the emissions from each CTG and HRSG duct burner. A Data Acquisition and Handling System (DAHS) shall be provided capable of logging and reporting emissions as required by the Air Quality Permit. The equipment shall be housed in a temperature and humidity controlled CEMS shelter.

Heat Recovery Steam Generator (Power Island Scope) - The Heat Recovery Steam Generators (HRSG) function to generate high-quality, superheated steam utilizing exhaust heat from the combustion turbine. Steam is generated at three (3) pressure levels for admission into the steam turbine. One HRSG will be supplied for each CTG as part of the Power Island purchase. The major components of each HRSG are as follows:

- Ductwork from combustion turbine
- Three pressure drums
- Low Pressure (LP) Economizer
- Low Pressure (LP) Evaporator
- Low Pressure (LP) Superheater
- Intermediate Pressure (IP) Economizer
- Intermediate Pressure (IP) Evaporator
- Intermediate Pressure (IP) Superheater
- High Pressure (HP) Evaporator
- High Pressure (HP) Economizer
- High Pressure (HP) Superheater
- High Pressure Reheater
- Main Steam Attemporator
- Reheat Steam Attemporator
- Natural Gas fired duct burner
- Ductwork to stack
- 150 foot high, 18'6" diameter stack
- SCR system utilizing 19% aqueous ammonia
- CO Catalyst
- N2 blanket connections

Steam Turbine Generator (Power Island Scope) - A single steam turbine generator produces electrical power from steam produced by the two (2) HRSGs. This steam turbine is a multistage, reheat, condensing type turbine. The turbine will have a downward exhaust with an expansion joint between the condenser and turbine. The major components include:

- Turbine Sections - HP, IP and LP
- Generator
- Stop/Control Valves
- Reheat Intercept/Stop Valves
- High Pressure Control Oil System
- Lube Oil System
- Steam seal and exhaustor system
- Turning Gear
- Mark VI (TMR) Turbine Control System

3.3 EPC Scope

The following paragraphs describe the equipment for which the EPC contractor shall be responsible for procurement.

3.3.1 Gas Fuel Only – Combustion Turbines

Ammonia System - The aqueous ammonia system stores and delivers ammonia to the HRSG's Selective Catalytic Reduction (SCR) system for the reduction of NOx emissions. The major equipment consists of the following:

- Two (2) 100% ammonia forwarding pumps
- One (1) nominal 20,000 gallon horizontal storage tank
- One (1) evaporator
- Tank truck unloading area

Auxiliary Steam Boiler - The auxiliary steam boiler is used to maintain the steam turbine shell and rotor metal temperatures hot during shutdown and to provide sealing steam to the steam turbine to enable more rapid startups. The major equipment consists of the following:

- One (1) 77,000 lb/hr Packaged Auxiliary Boiler
- Stack
- Deaerator
- Two (2) 100% capacity boiler feedpumps
- Instruments, valves and controls

Auxiliary Cooling Water System - The auxiliary cooling water system is a closed loop cooling water system supplying cooling water to the gas turbine generator coolers, steam turbine & gas turbine lube oil coolers and other auxiliary equipment. The major equipment includes the following:

- Two (2) 100% Pumps
- Two (2) 100% Plate and Frame Heat Exchangers
- Surge Tank
- Chemical Addition Tank

Auxiliary Electrical System - The auxiliary electrical system provides a means of stepping-down the generator terminal voltage to deliver power to the plant auxiliaries at a reduced voltage. Typical major equipment includes:

- Auxiliary cable and/or bus
- Station unit auxiliary transformers (UAT)
- 5 kV switchgear
- 5kV medium voltage motor controller gear (MVMC)
- Station service transformers (SST)
- secondary unit substations (SUS)
- 480 V motor control centers (MCC)

Boiler Blowdown System - The boiler blowdown system collects the blowdown streams from the HRSGs and directs them to the blowdown tank for draining to plant drains. Additionally,

startup blowdown, blow-offs, and other high temperature drains can be collected in the blowdown tank. The service water cools the streams prior to flowing to the plant drains. The major equipment includes one (1) blowdown tank per HRSG provided with the power island equipment supplied (by GE).

Circulating Water System - The plant circulating water system provides cooling water for the condenser and for auxiliary cooling system. Makeup water for the circulating water system is provided by the city and blowdown is sent to the municipal sewer system. The major equipment includes:

- Two (2) 50% circulating water pumps
- Multiple cell, mechanical draft cooling tower with pump basin
- Tower basin screens
- Level control valves
- Piping, valves and instrumentation

Condensate System - The condensate system receives turbine exhaust steam, turbine bypass steam and other miscellaneous steam drains then transports condensate from the hot well to the low-pressure drum of the HRSG for de-aeration. The condenser also provides a storage volume for other plant steam drains and the low-pressure, intermediate-pressure and high-pressure (cascading) steam turbine bypasses. The bypasses shall be designed for the steam turbine rapid startup and shutdown requirements. The major equipment includes the following:

- Three (3) 50% capacity Condensate Pumps with Motor Drives
- Steam Condenser
- Gland Seal Condenser (provided with STG)
- Two (2) 100% capacity liquid ring mechanical vacuum pumps
- Control Valves and Instrumentation

Chemical Feed System - The purpose of the chemical feed system is to protect the HRSG from corrosion and scale formation, and to provide protection of the circulating water from scaling, bio-fouling and controlling pH. The major equipment includes:

- HRSG - Two (2) phosphate chemical feed skids each with one (1) 100% HP & one (1) 100% IP injection pumps, day tank if required, piped, prewired and including necessary components and accessories for a complete functional feed skid.
- HRSG - Two (2) feed water chemical feed skids each with two (2) 100% injection pumps (oxygen scavenger & amine), day tanks if required, piped, prewired and including necessary components and accessories for a complete functional feed skid.
- Circulating Water - One (1) acid chemical feed skid with two (2) 100% injection pumps, day tank, piped, pre-wired and including necessary components and accessories for a complete functional feed skid.

- Circulating Water - One (1) biocide chemical feed skid with two (2) 100% injection pumps, piped, prewired and including necessary components and accessories for a complete functional feed skid.

Cathodic Protection System - The cathodic protection system function to mitigate galvanic action and prevent corrosion on the underground natural gas piping. The major equipment includes:

- Sacrificial anodes
- Cable
- Test boxes for potential measurement
- Insulating flanges.

DC Power System - The DC power system functions to provide a reliable source of motive and control power for critical equipment, the emergency shutdown of the plant, and the egress of plant personnel during blackout conditions. These loads typically include control power for power circuit breakers, switchgear, protective relaying, and DC power source for the Uninterruptible Power Supply (UPS). The major equipment includes:

- A bank of lead acid storage battery
- Two 100% capacity battery chargers
- Two (2) DC power distribution switchboard

Emergency Diesel Generator - The emergency diesel generator provides for the supply of essential AC auxiliary power during an electrical system (grid) black-out to permit a safe and orderly shutdown of the plant equipment. The major equipment includes:

- 1,000 kW diesel generator w/load bank
- 6,000 gallon diesel storage tank

Demineralized Water System - The demineralized water system functions to provide a supply of demineralized make-up water to the ST condenser hotwell, the CT evaporative cooling system, the CT water injection (NOx control on distillate), and for some the CT wash water solutions. The demineralized water system is sized to handle make-up when the plant is normally operating on natural gas fuel. During back-up operation on distillate fuel oil a rental trailer must be brought in to keep up with the water injection demand of the CTs. Major equipment that makes up the demineralized water treatment system includes the following:

- Multimedia filters for pre-filtration,
- Sodium bi-sulfite feed system
- Antiscalant chemical feed system
- Reverse Osmosis (RO) system
- Electro deionization (EDI) polishing
- Two (2) 100% capacity demineralized water transfer pumps
- A 200,000 gallon demineralized water storage tank

Facility Low Voltage Electrical System - The low voltage electrical system conditions and distributes electrical power at various voltage levels for lighting, receptacles and small loads (motors, HVAC, etc.) as required for all buildings and site support facilities. The major equipment of this system includes:

- Transformers
- Distribution panel boards
- Disconnect switches
- Separately mounted motor starters
- General-purpose receptacles
- Welding receptacles
- Lighting

Fuel Gas Condition Skid- The fuel gas skid functions to filter and heat the natural gas supplied for use as fuel by the combustion turbine and HRSG duct burner. A skid is provided for each CTG. Fuel gas heating is performed during startup by an electric heater to provide the superheat necessary to prevent the formation of liquid hydrocarbons in the fuel. During normal operation the fuel gas is heated by a performance heater using high temperature boiler feedwater to enhance the thermal performance of the CTG. The major equipment for each skid includes the following:

- Two (2) 100% coalescing filter/separators
- One (1) 100% scrubber
- One (1) fuel gas performance heater
- One (1) fuel gas electric startup heater

Fuel Gas Pressure Regulating Skid - A dual train fuel gas pressure regulating skid shall be provided to filter and regulate the supply pressure of the natural gas to the facility to satisfy the operational requirements of the CTGs. The major pressure regulation skid equipment includes the following:

- One (1) emergency shutdown valve
- Two (2) 100% capacity coalescing filter/separators
- Two (2) 100% capacity pressure reducing trains each equipped with the following:
 - * One (1) automatic inlet isolation valve per train
 - * One (1) startup pressure reducing valve per train
 - * One (1) primary pressure reducing valve per train
- One (1) safety relief valve with vent stack
- One (1) fuel gas condensate drains tank

Fire Protection System - The fire protection system provides standpipes and hose stations, fire extinguishers, independent fire detection systems, and fixed carbon dioxide suppression

systems to protect personnel, plant buildings and equipment from the hazards of fire. The system consists of the following:

- Low-pressure carbon dioxide fire suppression system
- Fire detection systems
- Portable fire extinguishers
- Manual fire alarm systems
- Manual pull stations in the buildings
- Fire Protection Control Panel for alarm, indication of system status, and actuation of fire protection equipment.
- One (1) 100% electric driven fire pump
- One (1) 100% diesel driven fire pump with diesel day tank.
- One (1) jockey pump
- 300,000 gallons of fire water reserve within the raw water storage tank
- Piping and valves, stand pipes and hose stations
- Fire pump building

Boiler Feedwater System - The boiler feedwater system functions to pressurize and transfer de-aerated condensate from the HRSG low-pressure drum to the high and intermediate pressure steam drums. The feedwater system also provides water to the MS and RH steam atomizers, and the steam bypass desuperheating stations associated with the ST steam bypass to the condenser. The major components of the feedwater system for each HRSG include the following:

- Two (2) 100% boiler feed pumps per HRSG
- Two (2) automatic pump minimum flow recirculation control valves per HRSG
- One (1) HP and one (1) IP feedwater control valve per HRSG

Grounding System - The grounding system function to provide protection for personnel and equipment from the hazards that can occur during power system faults and lightning strikes. System design shall include the ability to detect system ground faults. The grounding system shall typically consist of copper-clad ground rods, bare and insulated copper cable, copper bus bars, copper wire mesh, exothermic connections, and air terminals.

Generation (High Voltage) Electrical System- The generation electrical system functions to deliver generator power to the Substation, and provides power for the auxiliary electrical system. One set of the following equipment shall be provided for each the three (3) generating unit).

- Generator main leads
- Generator breaker
- Generator step-up (GSU) transformer (230 kV), (345kV Location 3 Only)
- Auxiliary transformer

Main Steam System - The main steam (MS) system functions to convey high pressure steam to the HP steam turbine section. During normal operation steam flows from each HRSG through the main steam headers into the steam turbine. The major equipment includes:

- Flow measuring equipment for steam flow
- Isolation valves
- Piping, valves and accessories

Hot Reheat and Cold Reheat Steam Systems - The hot reheat (HR) and cold reheat (CR) steam systems function to convey intermediate pressure steam to the intermediate pressure section of the steam turbine. During normal operation (CR) steam flows from the HP turbine exhaust to the HRSG reheater, and from the HRSG reheater steam flows through the HR steam system to the IP turbine inlet. The major equipment includes:

- Isolation valves
- Piping, valves and accessories

Oily Waste System - The Oily Waste system collects oil-contaminated wastewater in the plant drains system. The oil waste system is gravity feed throughout the plant to an oil water separator. The solids and oil collected in this system will be collected for offsite disposal at a suitable, licensed, hazardous waste facility. The effluent from the oil/water separator will be discharged to the local sewer system.

Plant Instrument and Service Air System - The plant instrument and service air system function to supply clean, dry, oil-free air at the required pressure and capacity for all pneumatic controls, transmitters, instruments and valve operators, and clean compressed air for non-essential plant service air requirements. The plant instrument and service air system includes the following components:

- Two (2) full capacity, air cooled, single stage, rotary screw type air compressors, each complete with controls, instrument panel, intercooler, lubrication system, aftercooler, moisture separator, intake filter-silencer, air/oil separator system and an unloading valve.
- Two (2) full capacity air receivers
- Two (2) full capacity, dual tower, heaterless type desiccant air dryers
- Two (2) full capacity pre-filters
- Two (2) full capacity after-filters
- Associated header and distribution piping and valves

Plant Communication System - The plant communication system functions to provide the plant external communication system through the use of the public telephone system. The administration building, control room, maintenance and storage areas will be equipped with telephone jacks. The Owner shall provide any internal plant communication systems including, but not limited to, two-way radios.

Plant Security - The plant security system provides protection to the property and personnel. A security system consisting of card readers, intercoms, motor operated gate and fencing will be provided.

Potable Water - The potable water system serves as a water source for drinking and personnel hygiene needs. Potable water also serves as a water source for eyewash and safety shower stations. Potable Water will be supplied from the local water utility.

Raw Water System - The raw water system provides utility water for general plant use. The water will be provided by the local water utility. The raw water system will supply water for miscellaneous non-potable plant uses including demineralized water system supply, plant equipment wash-downs, makeup to the circulating water system, general service water and fire water. The major equipment includes the following:

- One (1) 500,000 gallon raw water/fire water storage tank
- Two (2) 100% capacity raw water pumps

Steam & Water Sample System - The steam and water sample system functions to collect, cool, condense, draw and analyze the feedwater supply stream, blowdown from the HRSG drum, and the HP steam to the steam turbine. A sample system is provided for each HRSG. The major equipment includes:

- One new sample panel/sink
- Sample coolers
- Analyzers
- Sample tubing, valves, fittings & supports
- Insulation and freeze protection
- Lab facilities necessary to provide analysis required herein

Sanitary Waste System - The sanitary waste system collects sanitary wastes from the plant and transports to the city sewer system.

Uninterruptible Power Supply (UPS) - The uninterruptible power supply functions to provide reliable, regulated low voltage ac power to critical equipment during normal and emergency operating conditions. The typical loads that are considered for connection to the UPS include the Distributed Control System (DCS), CEMS, the turbine supervisory instrumentation, transducer power supplies, burner management systems (BMS), critical instruments, emergency shutdown networks, and critical vendor supplied control panels. The UPS system consists of the following components:

- Static inverter
- Static transfer switch
- Alternate source transformer and line voltage regulator
- Manual make-before-break bypass switch
- Two ac circuit breakers (alternate input, and bypass source)
- One dc circuit breaker

- Vital 120 V ac distribution panel with fused disconnects
- Controls, indicating lights, meters and alarms to control the UPS

3.3.2 Dual Fuel - Combustion Turbines

The following additional equipment is required to support dual (distillate fuel & natural gas fuel) operation of the combustion turbines. It is in addition to the equipment listed above for gas fuel operation of the combustion turbines:

Fuel Oil System - The fuel oil system receives, stores, regulates and transports distillate oil for use as backup fuel in the combustion turbine. The major equipment includes:

- One (1) 2,000,000 gallon fuel oil storage tank with steel containment (over 1 day storage).
- Two (2) fuel unloading stations
- Two (2) 100% capacity fuel forwarding pumps
- Two (2) 100% capacity fuel transfer pumps
- Interconnecting power and instrument cable, piping valves, filters and accessories

Fire Protection System - The fire protection system will be expanded to include the distillate fuel unloading area and the distillate fuel storage tanks.

Demineralized Water System - The demineralized water system will be expanded to support dual fuel operation of the CTs. This include the addition of demineralized water piping to the CTs water injection system and interconnecting piping, foundation and power feeds required to support operation of a trailer mounted water treatment system. In addition the storage capacity of the demineralized water storage tank will be increased to 2,250,000 gallons.

4.0 Power Plant General Arrangement

- Gas Fuel Only Combustion Turbine Arrangement, G-PP-002, revision A
- Dual Fuel Combustion Turbine Arrangement, G-PP-010, revision A

5.0 Project Schedule

A 32 month overall schedule (NTP-COD) was assumed which includes a 28 month construction/startup schedule through COD.

Project Start	April 2, 2012
NTP and Start of detailed engineering	October 1, 2012
Start of construction	January 14, 2013
COD	June 1, 2015

The overall schedule is essentially the same whether gas fuel only or dual fuel.

Prior to the NTP the Owner must obtain all the necessary environmental and local permits that are required as a prerequisite to commence construction. Procurement of OFE starts with project start and is complete for assignment to EPC contractor at NTP.

6.0 Capital Cost Estimate

EPC Contractor

- Estimate Basis, revision F

For Locations 1-5, Dual Fuel and Location 3 Single Fuel:

- Estimate Summary and Details, revision F

Owner

For Locations 1-5, Dual Fuel and Location 3 Single Fuel:

- Owner Cost tabulations

Fuel consumption and power generation during commissioning and testing (estimated) for the Combined Cycle plant is as follows:

operating hours	2847	hrs		
duration	119	days		
duration	17	weeks		
generation	546788	MWhrs	includes STG	
average load	192	MW		
fuel gas	4138657	Dth		
fuel oil	540,000	gals		

7.0 Cash Flow


EPC cash flow is based on the project cost excluding the OFE portion paid by Owner prior to assignment but including the OFE portion after assignment. The percentages of OFE costs to be used are identified in the Owners cost tabulations in Section 6.0. There are no monthly charges until NTP and assignment.

Owner cash flow is based on the OFE portion paid prior to assignment and all sales taxes and runs from project start thru end of project. The percentages of OFE costs to be used are identified in the Owners cost tabulations in Section 6.0. Owner does not make OFE payments after assignment at NTP.


These two percentages cannot be added together to get total monthly cash flows. They have to be converted to cash first, and then added.

- Combined Cycle - Gas Fuel Only Cash Flow, revision F
- Combined Cycle - Dual Fuel Cash Flow, revision F

APPENDIX B.2. LAYOUT DRAWING FOR DUAL-FUEL CC




EQUIPMENT LEGEND	
ITEM	DESCRIPTION
1	7FA CTG (COMBUSTION TURBINE GENERATOR)
2	HRSG W/ SCR
3	HRSG STACK
4	AMMONIA UNLOADING & STORAGE
5	D-11 STG (STEAM TURBINE GENERATOR)
6	PIPE/ELECTRICAL RACK
7	OVERHEAD BRIDGE CRANE
8	PARKING
9	CTG INLET AIR FILTER
10	CTG ROTOR PULL SPACE
11	CEMS (CONTINUOUS EMISSIONS MONITORING)
12	BOILER FEEDWATER PUMPS
13	PEEC
14	CO2 FIRE PROTECTION SYSTEM
15	GSU
16	GENERATOR BREAKER
17	COOLING TOWER
18	CIRCULATING COOLING WATER PUMPS
19	AUXILIARY COOLING WATER PUMP
20	COOLING TOWER CHEMICAL FEED ENCLOSURE
21	PDC (POWER DISTRIBUTION CENTER)
22	STATION SERVICE TRANSFORMERS
23	STG BUILDING
24	FUEL GAS CONDITIONING SKIDS
25	HRSG VAPORIZER SKID
26	HRSG CHEMICAL FEED SKID
27	PLANT/INSTRUMENT AIR COMPRESSORS
28	HRSG BLOWDOWN TANK
29	ISO PHASE BUS
30	MAIN STEAM CONDENSER
31	DEMINERALIZED WATER STORAGE TANK
32	RAW/FIRE WATER STORAGE TANK
33	FIRE PROTECTION PUMP PACKAGE
34	WATER TREATMENT BUILDING
35	HO/LO SUMPS
36	SWITCHYARD FENCE LINE
37	SWITCHYARD
38	SWITCHYARD CONTROL HOUSE
39	WAREHOUSE & MAINTENANCE BUILDING (GROUND FLR)
40	ADMINISTRATION BUILDING & CONTROL ROOM (2nd FLR)
41	EXCITATION TRANSFORMER
42	FUEL GAS METERING & REGULATING STATION
43	FUEL OIL STORAGE TANKS
44	FUEL OIL UNLOADING & FORWARDING
45	FOAM FIRE PROTECTION SYSTEM
46	
47	
48	
49	
50	
51	
52	
53	
54	
55	
56	
57	
58	
59	
60	
61	
62	
63	
64	
65	
66	
67	
68	
69	
70	
71	
72	
73	
74	
75	
76	
77	
78	
79	
80	



RESPONSIBLE ENGINEER	NO.	DATE	REVISION	BY	CHK	REVISION APPROVAL	REV A	DATE 08/23/11	STATUS				The Brattle Group PJM Interconnect Study Northeast U.S.	GENERAL ARRANGEMENT DUAL FUEL 2 x 1 COMBINED CYCLE PLOT PLAN			
	P1	06/29/11	ISSUED FOR INTRNAL REVIEW	TBJ		DISCIPLINE REVIEWED	DISCIPLINE	REVIEWED	ISSUED	REV	DATE	DM				SDE	PEM
	A	08/23/11	ISSUED FOR FINAL REPORT	TBJ		CIVIL			PRELIMINARY	P1	06/29/11						
						STRUCTURAL			FOR REVIEW AND APPROVAL								
						MECHANICAL			APPROVED FOR CONSTRUCTION								
								REVISIED & APPROVED FOR CONSTRUCTION									
						PROCESS		PLANT LAYOUTS									
						PIPING											
									SCALE	1" = 60'-0"			CH2MHILL CH2MHILL Engineers, Inc.	DWG. NO.	G-PP-010	REV. A	
														PROJECT NO.	421147		

APPENDIX B.3. PROJECT SCHEDULE FOR DUAL-FUEL CC



█ Actual Work
█ Remaining Work
█ Critical Remaining Work

APPENDIX B.4. COST DETAIL FOR CC IN CONE AREA 1



Description	Quantity	UM	HRS / UM	Professional Labor		Self Perform Craft Labor		Subcontract Labor		Specialty Sub.	Total Craft	Material			Const.	Specialty	Other	Total	% Of Direct	% Of Project	% Of Project				
				Hours	Labor Amount	Hours	Labor Amount	Hours	Labor Amount	Hours	Hours	Eng. Equip	Bulk	Sub.	Equip.	Sub				Total	Total	Total Revenue	Total		
INDIRECT COSTS																									
PROJECT MANAGEMENT	32,140	HRS																			4,224,367				
Home Office Professional (PM/CM)			186.36	7,279h	1,356,425													1,356,425	0.6%	0.4%	0.3%				
Project Support Professional (Safe/QC/PC/DocC/Est)			128.17	14,422h	1,848,494													1,848,494	0.8%	0.5%	0.3%				
Clerical			56.81	10,440h	593,102													593,102	0.3%	0.2%	0.1%				
Expenses																	426,347	426,347	0.2%	0.1%	0.1%				
ENGINEERING	149,700	HRS																			16,097,528				
Home Office Professional			96.91	143,300h	13,887,657													13,887,657	6.1%	3.9%	2.6%				
Field Professional (Site Support Engineering)			109.71	6,400h	702,127													702,127	0.3%	0.2%	0.1%				
Value Center Engineering																		-	0.0%	0.0%	0.0%				
Clerical																		-	0.0%	0.0%	0.0%				
Expenses																	1,507,744	1,507,744	0.7%	0.4%	0.3%				
PROCUREMENT	14,000	HRS																			1,600,000				
Home Office Professional			110.00	14,000h	1,540,000													1,540,000	0.7%	0.4%	0.3%				
Field Professional																		-	0.0%	0.0%	0.0%				
Clerical																		-	0.0%	0.0%	0.0%				
Expenses																	60,000	60,000	0.0%	0.0%	0.0%				
SITE MANAGEMENT	172,247	HRS																			16,550,609				
Field Professional			109.73	133,710h	14,671,638													14,671,638	6.4%	4.1%	2.8%				
Clerical			32.72	38,537h	1,260,828													1,260,828	0.6%	0.4%	0.2%				
Expenses																	618,143	618,143	0.3%	0.2%	0.1%				
STARTUP MANAGEMENT	38,472	HRS																			3,937,483				
Home Office Professional			110.00	552h	60,720													60,720	0.0%	0.0%	0.0%				
Field Professional			93.70	37,920h	3,553,096													3,553,096	1.6%	1.0%	0.7%				
Clerical																		-	0.0%	0.0%	0.0%				
Expenses																	323,667	323,667	0.1%	0.1%	0.1%				
SUBTOTAL MANGEMENT COST				406,560h	39,474,087	1,153,932h	98,267,414	13,090h	1,692,192	97,697h	1,264,719h	37,546,237	35,874,535	-	5,151,584	31,574,065	21,269,721	270,849,835	118.6%	76.0%	50.9%	270,849,835			
CONTINGENCY																					Cont. & Escal.				
Percentage					5.0%		7.0%		7.0%			12.3%	5.0%		5.0%	6.0%					50,834,214				
Dollars					1,973,704		6,878,719		118,453			4,636,387	1,793,727		257,579	1,894,444					17,553,014	7.7%	4.9%	3.3%	
ESCALATION																									
Percentage					10.3%		12.2%		7.5%			16.7%	15.5%		11.3%	13.9%	1.4%								
Dollars					4,074,800		11,976,300		126,200			6,282,400	5,549,000		584,000	4,395,400	293,100					33,281,200	14.6%	9.3%	6.3%
RISK																									
PROJECT SUBTOTAL				406,560h	45,522,592	1,153,932h	117,122,433	13,090h	1,936,846	97,697h	1,264,719h	48,465,024	43,217,262	-	5,993,163	37,863,909	21,562,821	321,684,048	140.8%	90.3%	60.4%	321,684,048			

Description	Quantity	UM	HRS / UM	Professional Labor		Self Perform Craft Labor		Subcontract Labor		Specialty Sub.	Total Craft	Material			Const.	Specialty	Other	Total	% Of Direct Total	% Of Project Total Revenue	% Of Project Total	
				Hours	Labor Amount	Hours	Labor Amount	Hours	Labor Amount	Hours	Hours	Eng. Equip	Bulk	Sub.	Equip.	Sub						
GENERAL OVERHEAD & ADMINISTRATION																						G&A & Margin
Percentage					0.0%		0.0%		0.0%			0.0%	0.0%		0.0%	0.0%	0.0%					40,968,405
Dollars					-		-		-			-	-		-	-	-					0.0%
MARGIN																						
Percentage					10.0%		10.0%		10.0%			10.0%	10.0%		10.0%	10.0%	10.0%					
Dollars					4,552,259		11,712,243		193,685			4,846,502	4,321,726		599,316	3,786,391	2,156,282					32,168,405
POWER BLOCK MARGIN																						
Percentage												0.0%										
Dollars												-										0.0%
Assignment Fee For Owner Supplied Equipment																						
Percentage												5.0%										0.0%
Dollars												8,800,000										8,800,000
PROJECT COST W/MARKUPS				406,560h	50,074,851	1,153,932h	128,834,676	13,090h	2,130,530	97,697h	1,264,719h	62,111,526	47,538,988	-	6,592,479	41,650,299	23,719,103					362,652,453
Sales Tax Deduction																						
Management Adjustments																						
PROJECT TOTAL REVENUE				406,560h	50,074,851	1,153,932h	128,834,676	13,090h	2,130,530	97,697h	1,264,719h	62,111,526	47,538,988	-	6,592,479	41,650,299	23,719,103					356,186,888
OWNER FURNISHED EQUIPMENT																						
CTGs												93,000,000										93,000,000
												-										-
HRSGs												41,000,000										41,000,000
STG												42,000,000										42,000,000
												-										-
												-										-
												-										-
												-										-
PROJECT TOTAL				406,560h	50,074,851	1,153,932h	128,834,676	13,090h	2,130,530	97,697h	1,264,719h	238,111,526	47,538,988	-	6,592,479	41,650,299	23,719,103					532,186,888

532,187,000

APPENDIX B.5. CASH FLOW SCHEDULE FOR CC IN CONE AREA 1

The Brattle Group

701 MW 2x1 CC Plant - GE 7241FA.05

EPC Cashflow

08/15/11		Rev.	F - Supplemental
Dual Fuel		Monthly	CUMULATIVE
MONTH		%	%
1	Apr-12	0.000%	0.000%
2	May-12	0.000%	0.000%
3	Jun-12	0.000%	0.000%
4	Jul-12	0.000%	0.000%
5	Aug-12	0.000%	0.000%
6	Sep-12	0.000%	0.000%
7	Oct-12	4.434%	4.434%
8	Nov-12	3.212%	7.646%
9	Dec-12	1.666%	9.312%
10	Jan-13	1.931%	11.243%
11	Feb-13	3.474%	14.718%
12	Mar-13	2.785%	17.502%
13	Apr-13	2.975%	20.478%
14	May-13	3.100%	23.578%
15	Jun-13	4.729%	28.307%
16	Jul-13	3.447%	31.753%
17	Aug-13	4.344%	36.097%
18	Sep-13	3.914%	40.011%
19	Oct-13	6.914%	46.925%
20	Nov-13	4.689%	51.615%
21	Dec-13	2.696%	54.310%
22	Jan-14	3.734%	58.045%
23	Feb-14	3.856%	61.900%
24	Mar-14	3.186%	65.086%
25	Apr-14	3.736%	68.823%
26	May-14	4.039%	72.862%
27	Jun-14	4.039%	76.902%
28	Jul-14	3.521%	80.423%
29	Aug-14	3.339%	83.762%
30	Sep-14	3.247%	87.009%
31	Oct-14	2.759%	89.768%
32	Nov-14	2.150%	91.918%
33	Dec-14	1.571%	93.489%
34	Jan-15	1.327%	94.816%
35	Feb-15	1.022%	95.839%
36	Mar-15	0.992%	96.831%
37	Apr-15	0.748%	97.579%
38	May-15	0.230%	97.809%
39	Jun-15	2.191%	100.000%

The Brattle Group

701 MW 2x1 CC Plant - GE 7241FA.05

Owner Cash Flow

08/15/11		Rev.	F - Supplemental
Dual Fuel		Monthly	CUMULATIVE
MONTH		%	%
1		0.00%	0.00%
2		31.63%	31.63%
3		0.00%	31.63%
4		0.00%	31.63%
5		25.79%	57.42%
6		15.82%	73.24%
7		0.03%	73.27%
8		0.59%	73.87%
9		1.86%	75.72%
10		0.90%	76.63%
11		0.92%	77.54%
12		1.69%	79.23%
13		1.00%	80.23%
14		0.99%	81.23%
15		1.07%	82.30%
16		1.58%	83.88%
17		1.12%	85.00%
18		1.15%	86.15%
19		1.17%	87.32%
20		2.81%	90.13%
21		1.59%	91.72%
22		0.60%	92.32%
23		0.59%	92.91%
24		0.54%	93.44%
25		0.64%	94.08%
26		0.64%	94.72%
27		0.61%	95.33%
28		0.51%	95.84%
29		0.55%	96.39%
30		0.50%	96.89%
31		0.45%	97.34%
32		0.42%	97.76%
33		0.27%	98.03%
34		0.23%	98.25%
35		0.20%	98.45%
36		0.19%	98.64%
37		0.16%	98.80%
38		0.11%	98.92%
39		1.08%	100.00%

APPENDIX C. WOOD GROUP O&M COST ESTIMATES

Wood Group cost estimates for each simple-cycle and combined-cycle plant fixed and variable operations and maintenance costs are included in this Appendix. These costs are reported in their components related to an annual facility fees as well as the costs of a long-term service agreement.

**Wood Group GTS
Power Plant Services**



August 5, 2011

Kathleen Spees
The Brattle Group
44 Brattle Street
Cambridge, MA 02138

Re: The Brattle Group Plant Evaluations

Kathleen:

We have estimated here the variable and fixed costs associated with operating CT and CC plants of several configurations. These costs are presented in two components:

1. Life Cycle Operations and Maintenance (O&M) Fees
2. Long-term Service Agreement (LTSA) Costs

We look forward to discussing this and answering any of your questions.

Sincerely yours,

Ted Kowalski
Vice President, Product Management
Wood Group Power Plant Services, Inc.
Office: (678) 242-0226 Ext 104

Assumptions

- **Equipment Descriptions**

We have developed cost estimates for three plant configurations, one combined cycle configuration, and two simple cycle configurations as listed below. The simple cycle configurations are identical except that one is fitted with Selective Catalytic Reduction (SCR), and the other is not. In all cases these estimates are consistent with a dual fuel plant that uses distillate fuel oil as a backup fuel under emergency conditions. The numbers we report here for Will County, IL can be used for either a dual fuel or a non-dual fuel plant.

Plant Characteristic	Simple Cycle	Combined Cycle
Turbine Model	GE 7FA.05	GE 7FA.05
Configuration	2 x 0	2 x 1
Net Plant Power Rating	With SCR: 418 MW at 59 °F Without SCR: 420 MW at 59 °F	Baseload (w/o Duct Firing): 627 MW at 59 °F Maximum Load (w/ Duct Firing): 701 MW at 59 °F
Cooling System	n/a	Cooling Tower
Power Augmentation	Evaporative Cooling	Evaporative Cooling
Blackstart Capability	None	None
On-Site Gas Compression	None	None

- **Location and Labor Type**

For each plant configuration, we have estimated costs in each of five locations with labor rates consistent with union or non-union labor as listed.

CONE Area	Plant Location	Labor
1 Eastern MAAC	Middlesex, NJ	Union
2 Southwest MAAC	Charles, MD	Non-Union
3 Rest of RTO	Will, IL	Union
4 Western MAAC	Northampton, PA	Union
5 Dominion	Fauquier, VA	Non-Union

Life Cycle Costs

We report here the life cycle operating costs for each plant configuration, including pre-mobilization costs and ongoing annual fees for a plant with an online date of June 1, 2015. For all years after the five years we report, these fees would be escalated at a 2.5% inflation rate. For year 1, we have reported the breakdown between fixed costs and variable costs included in these fees. The proportion of cost breakdown would be constant over the plant life assuming the same number of hours and starts reported here. These variable costs are additive with the variable costs reported for the LTSA.

This does not include Owner's costs such as property tax, plant insurance, or asset management.

Will County, IL Simple Cycle without SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC Power Facility located in Will County, IL



Pre Operation - Mobilization	US\$
<i>12 Month Period - Jun 1, 2014 to May 31, 2015</i>	
Facility Labor & Program Implementation	\$ 521,103
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 261,546
Total Mobilization Cost	\$ 994,649

Hours of Operation	
Weeks / Year	50
Days / Week	2
Hours / Day	5
Hours / Year	500
Starts / Year	50

Multi-Year Annual Fee Summary

	<i>June 1, 2015 May 31, 2016</i>	<i>June 1, 2016 May 31, 2017</i>	<i>June 1, 2017 May 31, 2018</i>	<i>June 1, 2018 May 31, 2019</i>	<i>June 1, 2019 May 31, 2020</i>
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,379,047	\$ 1,413,524	\$ 1,448,862	\$ 1,485,083	\$ 1,522,210
Consumables	\$ 175,097	\$ 179,475	\$ 183,961	\$ 188,561	\$ 193,275
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 429,116	\$ 439,843	\$ 450,840	\$ 462,111
TOTAL Multi-Year Annual Fee Summary	\$ 2,767,682	\$ 2,836,874	\$ 2,907,795	\$ 2,980,491	\$ 3,055,003

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,379,047		\$ 1,379,047	
			\$ -	
Consumables	\$ 175,097	\$ 12,001	\$ 163,096	\$ 0.07
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 969,985	\$ 140,471	\$ 829,514	\$ 0.83
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 6,321	\$ 412,328	\$ 0.04
TOTAL	\$ 2,767,682	\$ 146,792	\$ 2,620,890	\$ 0.87

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Charles County, MD Simple Cycle without SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC Power Facility located in Charles County, MD



Pre Operation - Mobilization	
<i>12 Month Period - Jun 1, 2014 to May 31, 2015</i>	US\$
Facility Labor & Program Implementation	\$ 509,039
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 261,546
Total Mobilization Cost	\$ 982,585

Hours of Operation	
<i>Weeks / Year</i>	50
<i>Days / Week</i>	2
<i>Hours / Day</i>	5
<i>Hours / Year</i>	500
<i>Starts / Year</i>	50

Multi-Year Annual Fee Summary

	<i>June 1, 2015 May 31, 2016</i>	<i>June 1, 2016 May 31, 2017</i>	<i>June 1, 2017 May 31, 2018</i>	<i>June 1, 2018 May 31, 2019</i>	<i>June 1, 2019 May 31, 2020</i>
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,300,035	\$ 1,332,536	\$ 1,365,849	\$ 1,399,995	\$ 1,434,995
Consumables	\$ 175,097	\$ 179,475	\$ 183,961	\$ 188,561	\$ 193,275
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 429,116	\$ 439,843	\$ 450,840	\$ 462,111
TOTAL Multi-Year Annual Fee Summary	\$ 2,688,669	\$ 2,755,886	\$ 2,824,783	\$ 2,895,403	\$ 2,967,788

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,300,035		\$ 1,300,035	
			\$ -	
Consumables	\$ 175,097	\$ 12,001	\$ 163,096	\$ 0.07
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 969,985	\$ 140,471	\$ 829,514	\$ 0.83
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 6,321	\$ 412,328	\$ 0.04
TOTAL	\$ 2,688,669	\$ 146,792	\$ 2,541,877	\$ 0.87

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Middlesex County, NJ Simple Cycle without SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC Power Facility located in Middlesex County, NJ



Pre Operation - Mobilization	
<i>12 Month Period - Jun 1, 2014 to May 31, 2015</i>	US\$
Facility Labor & Program Implementation	\$ 548,759
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 261,546
Total Mobilization Cost	\$ 1,022,305

Hours of Operation	
<i>Weeks / Year</i>	50
<i>Days / Week</i>	2
<i>Hours / Day</i>	5
<i>Hours / Year</i>	500
<i>Starts / Year</i>	50

Multi-Year Annual Fee Summary

	<i>June 1, 2015 May 31, 2016</i>	<i>June 1, 2016 May 31, 2017</i>	<i>June 1, 2017 May 31, 2018</i>	<i>June 1, 2018 May 31, 2019</i>	<i>June 1, 2019 May 31, 2020</i>
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,473,690	\$ 1,510,532	\$ 1,548,296	\$ 1,587,003	\$ 1,626,678
Consumables	\$ 175,097	\$ 179,475	\$ 183,961	\$ 188,561	\$ 193,275
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 429,116	\$ 439,843	\$ 450,840	\$ 462,111
TOTAL Multi-Year Annual Fee Summary	\$ 2,862,324	\$ 2,933,883	\$ 3,007,229	\$ 3,082,411	\$ 3,159,471

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,473,690		\$ 1,473,690	
			\$ -	
Consumables	\$ 175,097	\$ 12,001	\$ 163,096	\$ 0.07
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 969,985	\$ 140,471	\$ 829,514	\$ 0.83
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 6,321	\$ 412,328	\$ 0.04
TOTAL	\$ 2,862,324	\$ 146,792	\$ 2,715,532	\$ 0.87

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Northampton County, PA Simple Cycle without SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC Power Facility located in Northampton County, PA



Pre Operation - Mobilization	
12 Month Period - Jun 1, 2014 to May 31, 2015	US\$
Facility Labor & Program Implementation	\$ 487,945
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 261,546
Total Mobilization Cost	\$ 961,491

Hours of Operation	
Weeks / Year	50
Days / Week	2
Hours / Day	5
Hours / Year	500
Starts / Year	50

Multi-Year Annual Fee Summary

	June 1, 2015 May 31, 2016	June 1, 2016 May 31, 2017	June 1, 2017 May 31, 2018	June 1, 2018 May 31, 2019	June 1, 2019 May 31, 2020
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,260,467	\$ 1,291,978	\$ 1,324,278	\$ 1,357,385	\$ 1,391,319
Consumables	\$ 175,097	\$ 179,475	\$ 183,961	\$ 188,561	\$ 193,275
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 429,116	\$ 439,843	\$ 450,840	\$ 462,111
TOTAL Multi-Year Annual Fee Summary	\$ 2,649,101	\$ 2,715,329	\$ 2,783,211	\$ 2,852,792	\$ 2,924,112

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,260,467		\$ 1,260,467	
Consumables	\$ 175,097	\$ 12,001	\$ 163,096	\$ 0.07
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 969,985	\$ 140,471	\$ 829,514	\$ 0.83
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 6,321	\$ 412,328	\$ 0.04
TOTAL	\$ 2,649,101	\$ 146,792	\$ 2,502,309	\$ 0.87

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Fauquier County, VA Simple Cycle without SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC Power Facility located in Fauquier County, VA



Pre Operation - Mobilization	
<i>12 Month Period - Jun 1, 2014 to May 31, 2015</i>	
	US\$
Facility Labor & Program Implementation	\$ 499,050
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 261,546
Total Mobilization Cost	\$ 972,596

Hours of Operation	
<i>Weeks / Year</i>	50
<i>Days / Week</i>	2
<i>Hours / Day</i>	5
Hours / Year	500
Starts / Year	50

Multi-Year Annual Fee Summary

	<i>June 1, 2015 May 31, 2016</i>	<i>June 1, 2016 May 31, 2017</i>	<i>June 1, 2017 May 31, 2018</i>	<i>June 1, 2018 May 31, 2019</i>	<i>June 1, 2019 May 31, 2020</i>
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,254,444	\$ 1,285,805	\$ 1,317,950	\$ 1,350,899	\$ 1,384,671
Consumables	\$ 175,097	\$ 179,475	\$ 183,961	\$ 188,561	\$ 193,275
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 429,116	\$ 439,843	\$ 450,840	\$ 462,111
TOTAL Multi-Year Annual Fee Summary	\$ 2,643,078	\$ 2,709,156	\$ 2,776,884	\$ 2,846,306	\$ 2,917,464

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,254,444		\$ 1,254,444	
			\$ -	
Consumables	\$ 175,097	\$ 12,001	\$ 163,096	\$ 0.07
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 969,985	\$ 140,471	\$ 829,514	\$ 0.83
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,649	\$ 6,321	\$ 412,328	\$ 0.04
TOTAL	\$ 2,643,078	\$ 146,792	\$ 2,496,286	\$ 0.87

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Will County, IL Simple Cycle with SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC w/SCR Power Facility located in Will County, IL



Pre Operation - Mobilization	
<i>06 Month Period - Jun 1, 2014 to May 31, 2015</i>	
	US\$
Facility Labor & Program Implementation	\$ 770,282
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 149,046
Total Mobilization Cost	\$ 1,131,328

Hours of Operation	
<i>Weeks / Year</i>	50
<i>Days / Week</i>	2
<i>Hours / Day</i>	5
<i>Hours / Year</i>	500
<i>Starts / Year</i>	50

Multi-Year Annual Fee Summary

	<i>June 1, 2015 May 31, 2016</i>	<i>June 1, 2016 May 31, 2017</i>	<i>June 1, 2017 May 31, 2018</i>	<i>June 1, 2018 May 31, 2019</i>	<i>June 1, 2019 May 31, 2020</i>
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,379,047	\$ 1,413,524	\$ 1,448,862	\$ 1,485,083	\$ 1,522,210
Consumables	\$ 181,090	\$ 185,618	\$ 190,258	\$ 195,015	\$ 199,890
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 429,392	\$ 440,127	\$ 451,130	\$ 462,408
TOTAL Multi-Year Annual Fee Summary	\$ 2,773,944	\$ 2,843,294	\$ 2,914,375	\$ 2,987,235	\$ 3,061,915

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,379,047		\$ 1,379,047	
Consumables	\$ 181,090	\$ 17,994	\$ 163,096	\$ 0.11
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 975,978	\$ 146,464	\$ 829,514	\$ 0.87
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 6,591	\$ 412,328	\$ 0.04
TOTAL	\$ 2,773,944	\$ 153,055	\$ 2,620,890	\$ 0.91

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Charles County, MD Simple Cycle with SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC w/SCR Power Facility located in Charles County, MD



Pre Operation - Mobilization	US\$
<i>06 Month Period - Jun 1, 2014 to May 31, 2015</i>	
Facility Labor & Program Implementation	\$ 747,269
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 149,046
Total Mobilization Cost	\$ 1,108,315

Hours of Operation	
Weeks / Year	50
Days / Week	2
Hours / Day	5
Hours / Year	500
Starts / Year	50

Multi-Year Annual Fee Summary

	June 1, 2015 May 31, 2016	June 1, 2016 May 31, 2017	June 1, 2017 May 31, 2018	June 1, 2018 May 31, 2019	June 1, 2019 May 31, 2020
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,300,035	\$ 1,332,536	\$ 1,365,849	\$ 1,399,995	\$ 1,434,995
Consumables	\$ 181,090	\$ 185,618	\$ 190,258	\$ 195,015	\$ 199,890
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 429,392	\$ 440,127	\$ 451,130	\$ 462,408
TOTAL Multi-Year Annual Fee Summary	\$ 2,694,932	\$ 2,762,306	\$ 2,831,363	\$ 2,902,147	\$ 2,974,701

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,300,035		\$ 1,300,035	
Consumables	\$ 181,090	\$ 17,994	\$ 163,096	\$ 0.11
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 975,978	\$ 146,464	\$ 829,514	\$ 0.87
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 6,591	\$ 412,328	\$ 0.04
TOTAL	\$ 2,694,932	\$ 153,055	\$ 2,541,877	\$ 0.91

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Middlesex County, NJ Simple Cycle with SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC w/SCR Power Facility located in Middlesex County, NJ



Pre Operation - Mobilization	
<i>06 Month Period - Jun 1, 2014 to May 31, 2015</i>	
	US\$
Facility Labor & Program Implementation	\$ 799,603
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 149,046
Total Mobilization Cost	\$ 1,160,650

Hours of Operation	
<i>Weeks / Year</i>	50
<i>Days / Week</i>	2
<i>Hours / Day</i>	5
<i>Hours / Year</i>	500
<i>Starts / Year</i>	50

Multi-Year Annual Fee Summary

	<i>June 1, 2015 May 31, 2016</i>	<i>June 1, 2016 May 31, 2017</i>	<i>June 1, 2017 May 31, 2018</i>	<i>June 1, 2018 May 31, 2019</i>	<i>June 1, 2019 May 31, 2020</i>
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,473,690	\$ 1,510,532	\$ 1,548,296	\$ 1,587,003	\$ 1,626,678
Consumables	\$ 181,090	\$ 185,618	\$ 190,258	\$ 195,015	\$ 199,890
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 429,392	\$ 440,127	\$ 451,130	\$ 462,408
TOTAL Multi-Year Annual Fee Summary	\$ 2,868,587	\$ 2,940,302	\$ 3,013,809	\$ 3,089,155	\$ 3,166,383

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,473,690		\$ 1,473,690	
Consumables	\$ 181,090	\$ 17,994	\$ 163,096	\$ 0.11
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 975,978	\$ 146,464	\$ 829,514	\$ 0.87
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 6,591	\$ 412,328	\$ 0.04
TOTAL	\$ 2,868,587	\$ 153,055	\$ 2,715,532	\$ 0.91

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Northampton County, PA Simple Cycle with SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC w/SCR Power Facility located in Northampton County, PA



Pre Operation - Mobilization	
<i>06 Month Period - Jun 1, 2014 to May 31, 2015</i>	
	US\$
Facility Labor & Program Implementation	\$ 731,962
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 149,046
Total Mobilization Cost	\$ 1,093,008

Hours of Operation	
<i>Weeks / Year</i>	50
<i>Days / Week</i>	2
<i>Hours / Day</i>	5
<i>Hours / Year</i>	500
<i>Starts / Year</i>	50

Multi-Year Annual Fee Summary

	<i>June 1, 2015 May 31, 2016</i>	<i>June 1, 2016 May 31, 2017</i>	<i>June 1, 2017 May 31, 2018</i>	<i>June 1, 2018 May 31, 2019</i>	<i>June 1, 2019 May 31, 2020</i>
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,260,467	\$ 1,291,978	\$ 1,324,278	\$ 1,357,385	\$ 1,391,319
Consumables	\$ 181,090	\$ 185,618	\$ 190,258	\$ 195,015	\$ 199,890
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 429,392	\$ 440,127	\$ 451,130	\$ 462,408
TOTAL Multi-Year Annual Fee Summary	\$ 2,655,364	\$ 2,721,748	\$ 2,789,792	\$ 2,859,537	\$ 2,931,025

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,260,467		\$ 1,260,467	
Consumables	\$ 181,090	\$ 17,994	\$ 163,096	\$ 0.11
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 975,978	\$ 146,464	\$ 829,514	\$ 0.87
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 6,591	\$ 412,328	\$ 0.04
TOTAL	\$ 2,655,364	\$ 153,055	\$ 2,502,309	\$ 0.91

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Fauquier County, VA Simple Cycle with SCR

Wood Group Power Plant Services Cost Plus Estimate for a 2 x Frame 7FA SC w/SCR Power Facility located in Fauquier County, VA



Pre Operation - Mobilization	US\$
<i>06 Month Period - Jun 1, 2014 to May 31, 2015</i>	
Facility Labor & Program Implementation	\$ 732,068
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 149,046
Total Mobilization Cost	\$ 1,093,114

Hours of Operation	
Weeks / Year	50
Days / Week	2
Hours / Day	5
Hours / Year	500
Starts / Year	50

Multi-Year Annual Fee Summary

	June 1, 2015 May 31, 2016	June 1, 2016 May 31, 2017	June 1, 2017 May 31, 2018	June 1, 2018 May 31, 2019	June 1, 2019 May 31, 2020
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 1,254,444	\$ 1,285,805	\$ 1,317,950	\$ 1,350,899	\$ 1,384,671
Consumables	\$ 181,090	\$ 185,618	\$ 190,258	\$ 195,015	\$ 199,890
Office Administration	\$ 161,347	\$ 165,381	\$ 169,515	\$ 173,753	\$ 178,097
Maintenance & Minor Repairs	\$ 633,541	\$ 649,379	\$ 665,614	\$ 682,254	\$ 699,310
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 429,392	\$ 440,127	\$ 451,130	\$ 462,408
TOTAL Multi-Year Annual Fee Summary	\$ 2,649,341	\$ 2,715,575	\$ 2,783,464	\$ 2,853,051	\$ 2,924,377

June 1, 2015 to May 31, 2016 - Projected Costs

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 1,254,444		\$ 1,254,444	
Consumables	\$ 181,090	\$ 17,994	\$ 163,096	\$ 0.11
Office Administration	\$ 161,347	\$ 5,014	\$ 156,333	\$ 0.03
Maintenance & Minor Repairs	\$ 633,541	\$ 123,456	\$ 510,085	\$ 0.73
Subtotal	\$ 975,978	\$ 146,464	\$ 829,514	\$ 0.87
Purchasing, Handling, Corporate, & Administrative Charges	\$ 418,919	\$ 6,591	\$ 412,328	\$ 0.04
TOTAL	\$ 2,649,341	\$ 153,055	\$ 2,496,286	\$ 0.91

Note: When online, units assumed to be at 100% maximum load for variable cost calculation.

Will County, IL Combined Cycle

Wood Group Power Plant Services Cost Plus Estimate for a 2 x 1 Frame 7FA CC Power Facility located in Will County, IL



Pre Operation - Mobilization	US\$
12 Month Period	
Facility Labor and Program Implementation	\$ 2,302,001
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 262,244
Total Mobilization Cost	\$ 2,776,245

Hours of Operation	
Weeks / Year	50
Days / Week	5
Hours / Day	20
Hours / Year	5,000
Starts / Year	150

Multi-Year Annual Fee Summary

	June 1, 2015 May 31, 2016	June 1, 2016 May 31, 2017	June 1, 2017 May 31, 2018	June 1, 2018 May 31, 2019	June 1, 2019 May 31, 2020
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 3,631,653	\$ 3,722,445	\$ 3,815,506	\$ 3,910,893	\$ 4,008,666
Consumables	\$ 1,069,272	\$ 1,096,003	\$ 1,123,403	\$ 1,151,488	\$ 1,180,276
Office Administration	\$ 216,029	\$ 221,429	\$ 226,965	\$ 232,639	\$ 238,456
Maintenance & Minor Repairs	\$ 1,181,221	\$ 1,210,751	\$ 1,241,020	\$ 1,272,046	\$ 1,303,847
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 498,143	\$ 510,597	\$ 523,362	\$ 536,446
TOTAL Multi-Year Annual Fee Summary	\$ 6,584,169	\$ 6,748,771	\$ 6,917,491	\$ 7,090,428	\$ 7,267,691

June 1, 2015 to May 31, 2016

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 3,631,653		\$ 3,631,653	
Consumables	\$ 1,069,272	\$ 1,128,759	\$ 299,050	\$ 0.14
Office Administration	\$ 216,029	\$ 1,205	\$ 214,019	\$ 0.10
Maintenance & Minor Repairs	\$ 1,181,221	\$ 195,201	\$ 919,198	\$ 0.42
Subtotal	\$ 2,466,522	\$ 1,325,166	\$ 1,432,267	\$ 0.66
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 59,632	\$ 426,361	\$ 0.19
TOTAL	\$ 6,584,169	\$ 1,384,799	\$ 5,490,281	\$ 0.85

Note: When online, units assumed to be at 80% maximum load for variable cost calculation.

Charles County, MD Combined Cycle

Wood Group Power Plant Services Cost Plus Estimate for a 2 x 1 Frame 7FA CC Power Facility located in Charles County, MD



Pre Operation - Mobilization	US\$
12 Month Period	
Facility Labor and Program Implementation	\$ 2,232,371
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 262,244
Total Mobilization Cost	\$ 2,706,615

Hours of Operation	
Weeks / Year	50
Days / Week	5
Hours / Day	20
Hours / Year	5,000
Starts / Year	150

Multi-Year Annual Fee Summary

	June 1, 2015 May 31, 2016	June 1, 2016 May 31, 2017	June 1, 2017 May 31, 2018	June 1, 2018 May 31, 2019	June 1, 2019 May 31, 2020
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 3,454,910	\$ 3,541,282	\$ 3,629,814	\$ 3,720,560	\$ 3,813,574
Consumables	\$ 1,069,272	\$ 1,096,003	\$ 1,123,403	\$ 1,151,488	\$ 1,180,276
Office Administration	\$ 216,029	\$ 221,429	\$ 226,965	\$ 232,639	\$ 238,456
Maintenance & Minor Repairs	\$ 1,181,221	\$ 1,210,751	\$ 1,241,020	\$ 1,272,046	\$ 1,303,847
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 498,143	\$ 510,597	\$ 523,362	\$ 536,446
TOTAL Multi-Year Annual Fee Summary	\$ 6,407,425	\$ 6,567,609	\$ 6,731,799	\$ 6,900,095	\$ 7,072,599

June 1, 2015 to May 31, 2016

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 3,454,910		\$ 3,454,910	
Consumables	\$ 1,069,272	\$ 1,128,759	\$ 299,050	\$ 0.14
Office Administration	\$ 216,029	\$ 1,205	\$ 214,019	\$ 0.10
Maintenance & Minor Repairs	\$ 1,181,221	\$ 195,201	\$ 919,198	\$ 0.42
Subtotal	\$ 2,466,522	\$ 1,325,166	\$ 1,432,267	\$ 0.66
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 59,632	\$ 426,361	\$ 0.19
TOTAL	\$ 6,407,425	\$ 1,384,799	\$ 5,313,537	\$ 0.85

Note: When online, units assumed to be at 80% maximum load for variable cost calculation.

Middlesex County, NJ Combined Cycle

Wood Group Power Plant Services Cost Plus Estimate for a 2 x 1 Frame 7FA CC Power Facility located in Middlesex County, NJ



Pre Operation - Mobilization	US\$
12 Month Period	
Facility Labor and Program Implementation	\$ 2,414,955
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 262,244
Total Mobilization Cost	\$ 2,889,199

Hours of Operation	
Weeks / Year	50
Days / Week	5
Hours / Day	20
Hours / Year	5,000
Starts / Year	150

Multi-Year Annual Fee Summary

	June 1, 2015 May 31, 2016	June 1, 2016 May 31, 2017	June 1, 2017 May 31, 2018	June 1, 2018 May 31, 2019	June 1, 2019 May 31, 2020
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 3,880,667	\$ 3,977,684	\$ 4,077,126	\$ 4,179,054	\$ 4,283,530
Consumables	\$ 1,069,272	\$ 1,096,003	\$ 1,123,403	\$ 1,151,488	\$ 1,180,276
Office Administration	\$ 216,029	\$ 221,429	\$ 226,965	\$ 232,639	\$ 238,456
Maintenance & Minor Repairs	\$ 1,181,221	\$ 1,210,751	\$ 1,241,020	\$ 1,272,046	\$ 1,303,847
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 498,143	\$ 510,597	\$ 523,362	\$ 536,446
TOTAL Multi-Year Annual Fee Summary	\$ 6,833,182	\$ 7,004,010	\$ 7,179,110	\$ 7,358,589	\$ 7,542,555

June 1, 2015 to May 31, 2016

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 3,880,667		\$ 3,880,667	
			\$ -	
Consumables	\$ 1,069,272	\$ 1,128,759	\$ 299,050	\$ 0.14
Office Administration	\$ 216,029	\$ 1,205	\$ 214,019	\$ 0.10
Maintenance & Minor Repairs	\$ 1,181,221	\$ 195,201	\$ 919,198	\$ 0.42
Subtotal	\$ 2,466,522	\$ 1,325,166	\$ 1,432,267	\$ 0.66
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 59,632	\$ 426,361	\$ 0.19
TOTAL	\$ 6,833,182	\$ 1,384,799	\$ 5,739,295	\$ 0.85

Note: When online, units assumed to be at 80% maximum load for variable cost calculation.

Northampton County, PA Combined Cycle

Wood Group Power Plant Services Cost Plus Estimate for a 2 x 1 Frame 7FA CC Power Facility located in Northampton County, PA



Pre Operation - Mobilization	
12 Month Period	US\$
Facility Labor and Program Implementation	\$ 2,163,772
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 262,244
Total Mobilization Cost	\$ 2,638,015

Hours of Operation	
Weeks / Year	50
Days / Week	5
Hours / Day	20
Hours / Year	5,000
Starts / Year	150

Multi-Year Annual Fee Summary

	<i>June 1, 2015</i> <i>May 31, 2016</i>	<i>June 1, 2016</i> <i>May 31, 2017</i>	<i>June 1, 2017</i> <i>May 31, 2018</i>	<i>June 1, 2018</i> <i>May 31, 2019</i>	<i>June 1, 2019</i> <i>May 31, 2020</i>
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 3,338,601	\$ 3,422,066	\$ 3,507,618	\$ 3,595,308	\$ 3,685,191
Consumables	\$ 1,069,272	\$ 1,096,003	\$ 1,123,403	\$ 1,151,488	\$ 1,180,276
Office Administration	\$ 216,029	\$ 221,429	\$ 226,965	\$ 232,639	\$ 238,456
Maintenance & Minor Repairs	\$ 1,181,221	\$ 1,210,751	\$ 1,241,020	\$ 1,272,046	\$ 1,303,847
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 498,143	\$ 510,597	\$ 523,362	\$ 536,446
TOTAL Multi-Year Annual Fee Summary	\$ 6,291,117	\$ 6,448,393	\$ 6,609,603	\$ 6,774,843	\$ 6,944,216

June 1, 2015 to May 31, 2016

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 3,338,601		\$ 3,338,601	
			\$ -	
Consumables	\$ 1,069,272	\$ 1,128,759	\$ 299,050	\$ 0.14
Office Administration	\$ 216,029	\$ 1,205	\$ 214,019	\$ 0.10
Maintenance & Minor Repairs	\$ 1,181,221	\$ 195,201	\$ 919,198	\$ 0.42
Subtotal	\$ 2,466,522	\$ 1,325,166	\$ 1,432,267	\$ 0.66
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 59,632	\$ 426,361	\$ 0.19
TOTAL	\$ 6,291,117	\$ 1,384,799	\$ 5,197,229	\$ 0.85

Note: When online, units assumed to be at 80% maximum load for variable cost calculation.

Fauquier County, VA Combined Cycle

Wood Group Power Plant Services Cost Plus Estimate for a 2 x 1 Frame 7FA CC Power Facility located in Fauquier County, VA



Pre Operation - Mobilization	US\$
12 Month Period	
Facility Labor and Program Implementation	\$ 2,159,263
Facility Costs	\$ 212,000
Purchasing, Handling, Corporate, & Administrative Charges	\$ 262,244
Total Mobilization Cost	\$ 2,633,506

Hours of Operation	
Weeks / Year	50
Days / Week	5
Hours / Day	20
Hours / Year	5,000
Starts / Year	150

Multi-Year Annual Fee Summary

	June 1, 2015 May 31, 2016	June 1, 2016 May 31, 2017	June 1, 2017 May 31, 2018	June 1, 2018 May 31, 2019	June 1, 2019 May 31, 2020
	Year 1	Year 2	Year 3	Year 4	Year 5
Labor	\$ 3,310,788	\$ 3,393,557	\$ 3,478,396	\$ 3,565,356	\$ 3,654,490
Consumables	\$ 1,069,272	\$ 1,096,003	\$ 1,123,403	\$ 1,151,488	\$ 1,180,276
Office Administration	\$ 216,029	\$ 221,429	\$ 226,965	\$ 232,639	\$ 238,456
Maintenance & Minor Repairs	\$ 1,181,221	\$ 1,210,751	\$ 1,241,020	\$ 1,272,046	\$ 1,303,847
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 498,143	\$ 510,597	\$ 523,362	\$ 536,446
TOTAL Multi-Year Annual Fee Summary	\$ 6,263,303	\$ 6,419,884	\$ 6,580,381	\$ 6,744,891	\$ 6,913,515

June 1, 2015 to May 31, 2016

	Year 1 Total Costs			Variable Cost
	TOTAL	Variable	Fixed	\$/MWh
Facility staff labor costs	\$ 3,310,788		\$ 3,310,788	
Consumables	\$ 1,069,272	\$ 1,128,759	\$ 299,050	\$ 0.14
Office Administration	\$ 216,029	\$ 1,205	\$ 214,019	\$ 0.10
Maintenance & Minor Repairs	\$ 1,181,221	\$ 195,201	\$ 919,198	\$ 0.42
Subtotal	\$ 2,466,522	\$ 1,325,166	\$ 1,432,267	\$ 0.66
Purchasing, Handling, Corporate, & Administrative Charges	\$ 485,993	\$ 59,632	\$ 426,361	\$ 0.19
TOTAL	\$ 6,263,303	\$ 1,384,799	\$ 5,169,415	\$ 0.85

Note: When online, units assumed to be at 80% maximum load for variable cost calculation.

LTSA Budgets

- There are many different contract payment structures where the cash flow varies on an annual basis because of the delivery schedule of the parts for a scheduled event, and when the major maintenance events occur based on the plant's operations. Plant operations will determine how long it takes for the plant to reach the total factored fired starts (FFS) or factored fired hours (FFH) limit requiring such a maintenance event to be scheduled. For your purposes, we understand the LTSA costs are intended to reflect the total variable costs of the LTSA including major equipment costs incurred during these maintenance events (including combustion and hot gas path parts).
- The simple cycle and combined cycle plants were modeled with nominal operating profiles of 50 starts and 150 starts per year, respectively, although the resulting variable cost numbers would be consistent with a range of operating profiles
- We assumed a seventeen (17) year contract
- The Simple Cycle configuration would have the same LTSA budget on a \$/FFS and \$/FFH basis with or without an SCR
- The nominal dollars reported are for the year starting June 1, 2015 and would be escalated with a 2.5% inflation rate thereafter
- For both the simple cycle and combined cycle plant, LTSA fees would be assessed on either an FFS basis or an FFH basis. If the plant is operating at greater than 27 FFH/FFS, the maintenance intervals would be hours based, otherwise the costs would be assessed on a starts basis.

There are several factors that will affect the maintenance intervals regardless of whether the unit is hours or starts based. For example, fuel type, trips, type of NOx control, operational considerations, etc. will all affect how the FFS and FFH are calculated. General Electric GER3620, Heavy-Duty Gas Turbine Operating and Maintenance Considerations, provides details for why these factors affects the maintenance intervals.

Simple Cycle Inspection Schedule

Project Name: Brattle Group - 50 Starts Simple Cycle
Project Location: Various
Date: 2015-06-01

Date	Date End	Unit	Inspection Type
2023-09-24	2023-09-30	GT02	CI
2024-03-17	2024-03-23	GT01	CI
2032-09-24	2032-10-05	GT02	HGPI
2033-03-17	2033-03-28	GT01	HGPI

Combined Cycle Inspection Schedule

Project Name: Brattle Group USA- 150 Starts Combined Cycle
Project Location: Various
Date: 2015-06-01

Date	Date End	Unit	Inspection Type
2017-01-26	2017-02-01	GT02	CI
2017-11-09	2017-11-15	GT01	CI
2020-01-26	2020-02-06	GT02	HGPI
2020-11-09	1900-01-20	GT01	HGPI
2023-01-26	2023-02-01	GT02	CI
2023-11-09	2023-11-15	GT01	CI
2026-01-26	2026-02-06	GT02	HGPI
2026-11-09	2026-11-20	GT01	HGPI
2029-01-26	2029-02-01	GT02	CI
2029-11-09	2029-11-15	GT01	CI
2032-01-26	2032-02-22	GT02	MI
2032-11-09	2032-12-01	GT01	MI

LTSA Costs

Project Name: Brattle Group - LTSA Variable Costs

	Simple Cycle		Combined Cycle	
		\$/FFS		\$/FFH
Will County, IL	\$	18,565	\$	291
Charles County, MD	\$	17,501	\$	274
Middlesex County, NJ	\$	19,846	\$	311
Northampton County, PA	\$	16,968	\$	266
Fauquier County, VA	\$	16,887	\$	265