



Reliability Analysis Update

Transmission Expansion Advisory
Committee

April 7, 2016




2016 RTEP Timeline

- Cases
 - 2016 RTEP summer case finalized (quality control check in-progress)
 - 2016 RTEP winter case sent to TO for modeling updates
 - 2016 RTEP light load case sent to TO for modeling updates
- Analysis
 - Performed preliminary N-1 and generation deliverability analysis; currently in the process of the quality control check
 - Finalize the N-1 and generation deliverability analysis
 - Perform load deliverability and N-1-1 analysis
- Windows
 - Post the preliminary N-1 thermal and Generation deliverability results by mid April 2016




2016 RTEP Proposal Window #1


- Scope
 - Generator Deliverability and Common Mode Outage Violations
 - End of life facilities
- Preliminary Files Released: 2/5/2016
- Window Opened: 2/16/2016
- Window Closes: 3/17/2016 – Proposal definitions, simulation data and planning cost estimate due
- Detailed Cost due: 4/1/2016 – Additional 15 days to develop and provide detailed cost data – See the window documentation for additional information



- **Generation Deliverability and Common Mode Outage (FG# 60, 61, 62, 66, 68, 70, 71, 72, 76, 78, 248, 249)**
- The Chesterfield – Messer Road – Charles City Road 230kV circuit is overloaded for several contingencies



- **Generation Deliverability and Common Mode Outage (FG# 102)**
- The Carson – Rogers Rd 500 kV circuit is overloaded for single contingency loss of the Carson – Rawlings 500 kV circuit.




- 26 Proposals from 7 entities
 - 3 Transmission Owner Upgrades
 - Cost range of \$7.7M to \$48.5M
 - 23 Greenfield Projects
 - Cost range of \$15.6M to \$111.5M
- Proposal Fee
- Next Steps
 - Proposal evaluations
 - More Detailed overview of proposals received to be presented at a future TEAC



Artificial Island Update

Artificial Island Area Network



- New Freedom SVC Technical Specifications
 - Development of a technical spec to provide engineering, procurement and construction of an SVC at New Freedom
 - Detailed PSCAD (transient study tool) Study
 - Confirmed previous PJM study results

- Consideration of increased cost estimates for the current approved scope of work
- Examining configuration changes to terminate the planned Cedar Creek – Salem transmission facility at Hope Creek
 - Electrical performance
 - Cost estimates
 - Constructability
 - Consideration of process implications



RTEP Next Steps

Questions?

Email: RTEP@pjm.com

- Revision History
 - V1 - Original version posted to PJM.com – 4/6/2016