Subregional RTEP Committee – Western FirstEnergy Supplemental Projects

June 16, 2023

Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



ATSI Transmission Zone M-3 Process Napoleon – Campbell Soup 69 kV Line Customer Connection

Need Number: ATSI-2023-007

Process Stage: Need Meeting – 06/16/2023

Supplemental Project Driver(s):

Customer Service

Specific Assumption Reference(s):


New customer connection request will be evaluated per FirstEnergy's "Requirements for Transmission Connected Facilities" document and "Transmission Planning Criteria" document.

Problem Statement

Customer Connection – Customer is requesting to retire an existing 69 kV delivery point on the Napoleon – Campbell Soup 69 kV Line. In addition, the customer is requesting a new 69 kV delivery point along the same transmission line to replace the retired delivery point which will have an anticipated load of 25 MVA.

Requested In-Service Date:

03/31/2024





ATSI Transmission Zone M-3 Process Litchfield Tap Need

Need Number: ATSI-2023-010

Process Stage: Need Meeting – 06/16/2023

Supplemental Project Driver(s):

Operational Flexibility and Efficiency Equipment Material Condition, Performance and Risk Infrastructure Resilience


Specific Assumption Reference(s):

Global Considerations

- System reliability and performance
- Load at risk in planning and operational scenarios
- Age/condition of transmission line conductor, hardware and structures
- Negatively impact customer outage frequency and/or duration

Network Radial Lines

- Load at risk and/or customers affected
- Proximity to other networked facilities
- Reconductor/Rebuild Transmission Lines
- Build New Transmission Line






ATSI Transmission Zone M-3 Process Litchfield Tap Need

Need Number: ATSI-2023-010

Process Stage: Need Meeting – 06/16/2023

Problem Statement:

- Litchfield Substation is located on the Carlisle Wellington 69 kV Line via a radial tap line of approximately 6.3 miles.
- The substation serves approximately 7.1 MW of load and approximately 2,000 customers with no alternative feed.
- A CVI inspection identified that 22 of the 87 structures on the tap line have defects noted with decay and sound test failures. Also, all 87 structures are greater than 40 years old.
- The Carlisle –Wellington 69 kV Line is approximately 29 miles and since 2017 has experienced sixteen total outages: seven momentary and nine sustained outages with average sustained outage duration of 29 minutes.
 - In 2021 and 2020, the Litchfield Substation experienced two extended sustained outages, approximately 12 hours and one (1) hour, respectively due to weather related events.
- A forced or maintenance outage on the tapped line would require the outage of the Litchfield Substation for an extended period.
- The Carlisle-Wellington 69 kV Line is being rehabbed/rebuilt under ATSI-2018-018 (s1803). However, the Litchfield radial tap line was excluded from the scope of ATSI-2018-018 due to lack of an alternate feed to Litchfield and constructability challenges.





ATSI Transmission Zone M-3 Process Akron/Barberton/Wadsworth Area Need

Need Number: ATSI-2023-011

Process Stage: Need Meeting – 6/16/2023

Supplemental Project Driver(s):

Operational Flexibility and Efficiency Equipment Material Condition, Performance and Risk Infrastructure Resilience


Specific Assumption Reference(s):

Global Considerations

- System reliability and performance
- Load at risk in planning and operational scenarios

Add/Expand Bus Configuration

- Loss of substation bus adversely impacts transmission system performance
- Eliminate simultaneous outages to multiple networked elements under N-1 analysis
- Accommodate future transmission facilities
- Capability to perform system maintenance






ATSI Transmission Zone M-3 Process Akron/Barberton/Wadsworth Area Need

Need Number: ATSI-2023-011

Process Stage: Need Meeting – 6/16/2023

Problem Statement:

- An N-1-1 outage will result in approximately 29,100 customers at risk and cause a consequential load loss of approximately 119 MW.
- An N-1-1 outage will result in approximately 9,360 customers at risk and cause a consequential load loss of approximately 38 MW and cause a backfeed condition from the Akron 23 kV system.
- Since 2014, the following lines have a combined total of seven momentary outages and six sustained outages:
 - Star Urban 138 kV Line experienced three outages: 1 momentary. 2 sustained
 - Star Wadsworth 138 kV Line experienced two outages: 1 momentary. 1 sustained
 - Pine West Akron 138 kV Line experienced one outage: 0 momentary. 1 sustained
 - Star Tusc 138 kV Line experienced no outages
 - Firestone South Akron 138 kV Line experienced one outage: 0 momentary, 1 sustained
 - Firestone Urban 138 kV Line experienced six outages: 5 momentary, 1 sustained





ATSI Transmission Zone M-3 Process Cloverdale – Dale #2 69 kV Line Need

Need Number: ATSI-2023-012

Process Stage: Need Meeting – 6/16/2023

Supplemental Project Driver(s):

Operational Flexibility and Efficiency Equipment Material Condition, Performance and Risk Infrastructure Resilience

Specific Assumption Reference(s):

Global Considerations


- System reliability and performance
- Load at risk in planning and operational scenarios

Add/Expand Bus Configuration

- Loss of substation bus adversely impacts transmission system performance
- Eliminate simultaneous outages to multiple networked elements under N-1 analysis
- Accommodate future transmission facilities
- Capability to perform system maintenance

Problem Statement:

- The Cloverdale Dale #2 69 kV Line is 14.74 miles and serves seven (7) delivery points
- A line fault will cause approximately 82 MW consequential loss of load and approximately 18,000 customers at risk
- Since 2015, the Cloverdale Dale #2 69 kV Line has experienced a total of five (5) momentary outages and ten (10) sustained outages.



Solution

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



ATSI Transmission Zone M-3 Process Chrysler-Maclean 138 kV New Customer

Need Number: ATSI-2023-003

Process Stage: Solution Meeting –6/16/2023

Previously Presented: Need Meeting – 4/21/2023

Project Driver(s):

Customer Service


Specific Assumption Reference(s)

New customer connection request will be evaluated per FirstEnergy's "Requirements for Transmission Connected Facilities" document and "Transmission Planning Criteria" document.

Problem Statement

New Customer Connection – Customer has requested a new 138 kV delivery point near the Chrysler-Maclean 138 kV line. The anticipated load of the new customer connection is 30 MVA.

Requested in-service date is 10/01/2024.





ATSI Transmission Zone M-3 Process Chrysler-Maclean 138 kV New Customer

Need Number: ATSI-2023-003

Process Stage: Solution Meeting -6/16/2023

Previously Presented: Need Meeting – 4/21/2023

Proposed Solution:

138 kV Transmission Line Tap

■ Install three SCADA controlled transmission line switches


 Construct approximately 250 ft of transmission line using 954 45/7 ACSR from tap point to the customer substation

Alternatives Considered:

■ No feasible alternatives to meet customer's request

Estimated Project Cost: \$0.9M

Projected In-Service: 10/1/2024
Status: Engineering



Appendix

High Level M-3 Meeting Schedule

Assum	ntions
, 133 a i i i	Puons

Activity	Timing
Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
Stakeholder comments	10 days after Assumptions Meeting

Needs

Activity	Timing
TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
Stakeholder comments	10 days after Needs Meeting

Solutions

Activity	Timing
TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
Stakeholder comments	10 days after Solutions Meeting

Submission of Supplemental Projects & Local Plan

Activity	Timing
Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
Post selected solution(s)	Following completion of DNH analysis
Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions

Revision History

6/xx/2023 – V1 – Original version posted to pjm.com