Salt Fork-Leatherwood Rebuild

General Information

Proposing entity name AEPSCT

Does the entity who is submitting this proposal intend to be the Designated Entity for this proposed project?

Yes

Company proposal ID AEP_D

PJM Proposal ID 115

Project title Salt Fork-Leatherwood Rebuild

Project description AEP is proposing to rebuild ~4.2 miles of overloaded sections of the 69 kV line between Salt Fork

Switch and Leatherwood Switch with 556 ACSR. Update relay settings at Broom Road station. Final

ratings after proposed upgrades: 245489-245493: 73/73/91/91 SN/SE/WN/WE MVA

245478-245489: 73/90/91/106 SN/SE/WN/WE MVA

Email nckoehler@aep.com

Project in-service date 08/2025

Tie-line impact No

Interregional project No

Is the proposer offering a binding cap on capital costs?

Additional benefits

Associated with b3274: Sections of this line were approved in the 2020 PJM v

Associated with b3274: Sections of this line were approved in the 2020 PJM Window 1 to be rebuilt. That project is currently in the detailed design phase. Associated with AEP-2021-OH006: The remaining sections (non-baseline) of this line were submitted to PJM as a need in 2/17/2021. This

proposal addresses an additional 4.2 miles of the supplemental need.

Project Components

- 1. Salt Fork-Leatherwood Line Rebuild
- 2. Broom Road Relay Settings Update

2021-W1-115

Transmission Line Upgrade Component

Component title Salt Fork-Leatherwood Line Rebuild

Project description Rebuild approximately 4.2 miles of line between Salt Fork Switch and Leatherwood Switch.

Impacted transmission line Salt Fork-Leatherwood 69 kV line

Point A Salt Fork Switch

Point B Leatherwood Switch

Point C Broom Road

Terrain description Wooded and hilly terrain.

Existing Line Physical Characteristics

Operating voltage 69

Conductor size and type 3/0 CU (7 strand) and 336 ACSR 18/1

Hardware plan description No hardware will be reused on the rebuilt portions.

Transware plan description

• Steel lattice (1920s vintage) and wood pole (1960s vintage) • Number of open conditions: Newcomerstown-Cambridge-88, Leatherwood-North Cambridge-13 • Additional Info: Ground lead wire missing, stolen or broken, structure related conditions affecting the cross arm or pole including rot, split or woodpecker holes, contaminated or broken insulator hardware See also the need presented on 2/17/2021 under AEP-2021-OH006

Operating

Emergency retings

Proposed Line Characteristics

Tower line characteristics

Voltage (kV)	69.000000	69.000000

	Normarratings	Emergency ratings
Summer (MVA)	102.00000	142.000000

Designed

Normal ratings

Winter (MVA) 129.000000 160.000000

Conductor size and type 556.5 KCM ACSR (26/7) "Dove"

Shield wire size and type 7#10 Alumoweld

Rebuild line length 4.2 miles

Rebuild portion description

Rebuild approximately of 4.2 miles of line between Salt Fork Switch and Leatherwood Switch with steel monopoles and 556 ACSR conductor.

Steel monopoles and 556 ACSK conduction

The Project will rebuild AEP's existing Salt Fork Switch-Leatherwood Switch 69kV Line for 60' (30'/30') wide ROW for 4.2 miles. The Project begins at AEP's existing Salt Fork Switch and runs in a general southerly direction to AEP's existing Leatherwood Switch that are both in Guernsey County, Ohio. The tabletop analysis found there were no public lands required for this Project. The private land use is predominantly agricultural & residential that were verified through the Guernsey County Clerk's Office classifications/assessments. The private land requirements include rebuilding the AEP's existing Salt Fork Switch-Leatherwood Switch 69kV Line. The rebuild line will require supplementing the existing lands rights in Guernsey County, Ohio where the land use is predominantly agricultural & residential with flat/rolling terrain.

Construction responsibility AEP

Benefits/Comments Business confidential practices.

Component Cost Details - In Current Year \$

Right of way

Engineering & design Detailed cost breakdown

Permitting / routing / siting Detailed cost breakdown

ROW / land acquisition Detailed cost breakdown

Materials & equipment Detailed cost breakdown

Construction & commissioning Detailed cost breakdown

Construction management Detailed cost breakdown

Overheads & miscellaneous costs

Detailed cost breakdown

Contingency Detailed cost breakdown

Total component cost \$9,061,603.00

Component cost (in-service year) \$.00

Substation Upgrade Component

Component title Broom Road Relay Settings Update

Project description Update relay settings at Broom Road to coordinate with remote ends due to impedance change

caused by the line rebuild

Substation name Broom Road

Substation zone 205 - AEP

Substation upgrade scope

Update relay settings on breaker G at Broom Road 69 kV station.

Transformer Information

None

New equipment description N/A. Settings update only.

Substation assumptions N/A. Settings update only.

Real-estate description N/A. Settings update only.

Construction responsibility AEP

Benefits/Comments

Component Cost Details - In Current Year \$

Engineering & design Detailed cost breakdown

Permitting / routing / siting Detailed cost breakdown

ROW / land acquisition Detailed cost breakdown

Materials & equipment Detailed cost breakdown

Construction & commissioning Detailed cost breakdown

Construction management Detailed cost breakdown

Overheads & miscellaneous costs Detailed cost breakdown

Contingency Detailed cost breakdown

Total component cost \$38,828.00

Component cost (in-service year) \$.00

Congestion Drivers

None

Existing Flowgates

FG#	From Bus No.	From Bus Name	To Bus No.	To Bus Name	СКТ	Voltage	TO Zone	Analysis type	Status
AEP -T39	245478	05LEATHERW	245489	05BROOMRD	1	69	205	FERC 715 Thermal	Included
AEP -T40	245478	05LEATHERW	245489	05BROOMRD	1	69	205	FERC 715 Thermal	Included
AEP -T41	245489	05BROOMRD	245493	05SALTFRKZ	1	69	205	FERC 715 Thermal	Included
AEP -T42	245489	05BROOMRD	245493	05SALTFRKZ	1	69	205	FERC 715 Thermal	Included

New Flowgates

None

Financial Information

Capital spend start date 09/2022

Construction start date 09/2024

Project Duration (In Months) 35

Additional Comments

None